

18681 Lake Drive East Chanhassen, MN 55317 952-607-6512 www.rpbcwd.org

Riley Purgatory Bluff Creek Watershed District Permit Application Review

Permit No: 2023-079

Considered at Board of Managers Meeting: February 7, 2024

Received complete: January 16, 2024

Applicant: Grace Church, Dale Nelson **Consultant:** HGA, Inc., Kenneth W. Horns

Project: Grace Church Playground - Development of a new playground for Grace Church in Eden

Prairie, MN. Stormwater management includes an infiltration basin to provide volume

control, water quality, and rate control.

Location: 9301 Eden Prairie Road, Eden Prairie, MN, 55344

Reviewer: Heather Lau P.E. and Scott Sobiech P.E.; Barr Engineering Co.

Dunmanad Danud Astion						
Proposed Board Action						
·	ermit report that follows and the	seconded adoption of the following presentation of the matter at the				
• •	Resolved that the application for Permit 2023-079 is approved, subject to the conditions and stipulations set forth in the Recommendations section of the attached report;					
permit have been affirmat	•	tor that the conditions of approval of the dent or administrator is authorized and nt, on behalf of RPBCWD.				
Upon vote, the resolutions	were adopted, [VOTE TA	ILLY].				

Applicable Rule Conformance Summary

Rule	Issue		Conforms to RBPCWD Rules?	Comments
С	Erosion Control Plan		Yes	
J	Stormwater	Rate	Yes	
	Management	Volume	Yes	See stipulation #5 related to verifying the infiltration capacity of the soils
		Water Quality	Yes	
		Low Floor Elev.	Yes	
		Maintenance	See comment	See rule-specific permit condition J1 related to recordation of stormwater facility maintenance declaration.

Rule	Issue		Conforms to RBPCWD Rules?	Comments
		Chloride Management	See comment	See stipulation #6 related to providing an executed chloride management plan prior to permit close-out.
L	Permit Fee Deposit		Yes	\$3,000 deposit fee received January 16, 2024. The applicant must replenish the permit fee deposit to the original amount due before the permit will be issued. As of January 31, 2024 the amount due is \$2,869
M	Financial Assurance		See Comment	The financial assurance is calculated at \$129,168

Background

The proposed redevelopment will include the removal of an existing play area on the south side of the Grace Church building and the construction of a new playground on the site in Eden Prairie, Minnesota. The applicant proposes to use a stormwater infiltration basin to provide water quality treatment, rate control, and volume abstraction.

The project site information is summarized in Table 1.

Table 1. Project Site Information

14216 2.1.10,000 0.10 1.110111411011					
Site Information	Project Area				
Total Site Area (acres)	53.6				
Existing Site Impervious Area (acres)	27.9				
Post Construction Site Impervious (acres)	28.46				
New (increase) in Site Impervious Area (acres)	0.56				
Percent Increase in Impervious Surface	2%				
Disturbed Site Impervious Area (acres)	0.02				
Percent Disturbance of Existing Impervious Surface	<0.1%				
Total Disturbed Area (acres)	1.5				

Exhibits:

- 1. Permit application dated December 26, 2023 (Notified applicant on January 10, 2024 that submittal was incomplete, revised materials completing the application received January 16, 2024)
- 2. Stormwater Management Report dated December 13, 2023 (Revised January 16, 2024)

- 3. Project Plan set (11 sheets) dated October 13, 2023 (revised sheets C400 and C401 dated January 11, 2024)
- 4. Existing and Proposed HydroCAD Models received December 26, 2023 (revised January 16, 2024)
- 5. Test Pit Infiltration Letter by America Engineering Testing, Inc. dated December 8, 2023
- 6. Report of Geotechnical Exploration by America Engineering Testing, Inc. dated January 31, 2023
- 7. Earthwork Specification No. 310000 received January 16, 2024
- 8. HydroCAD Report for 100-year, 10-day snowmelt event received January 16, 2024
- 9. Review Responses dated January 16, 2024 (the applicant's responses to the January 10th incomplete notice/review comments)

Rule Specific Permit Conditions

Rule C: Erosion Prevention and Sediment Control

Because the applicant proposes to alter 1.5 acres of land-surface area, the project must conform to the requirements in the RPBCWD Erosion Prevention and Sediment Control rule (Rule C, Subsection 2.1).

The erosion control plan prepared by HGA, Inc. includes installation of perimeter control (sediment control logs and silt fence), a stabilized rock construction entrance, inlet protection, daily inspection, decompaction of areas compacted during construction, placement of a minimum of 6 inches of topsoil with 5 percent organic content, and retention of native topsoil onsite to the greatest extent possible. The applicant listed Shirley Kasiano with Visioneering Studios Construction (562-335-7384, skasiano@visioneeringstudios.com) as the individual responsible for erosion control at the site. The proposed project conforms to the RPBCWD Rule C requirements.

Rule J: Stormwater Management

Because the applicant proposes to disturb 1.5 acres of land-surface area, the project must meet the criteria of RPBCWD's Stormwater Management rule (Rule J, Subsection 2.1). The criteria listed in Subsection 3.1 will only apply to the disturbed areas and additional impervious surface on the project site because the proposed activity will not disturb more than 50 percent of the existing impervious surface and increases the impervious surface on the parcel by less than 50 percent (Rule J, Subsection 2.3).

The applicant is proposing construction of an infiltration basin to provide the rate control, volume abstraction, and water quality management for the disturbed and replaced impervious area. Pretreatment for runoff entering the infiltration basin is being provided by vegetated overland flow and drainage structures with 4-foot-deep sumps.

Rate Control

In order to meet the rate control criteria listed in Subsection 3.1.a, the 2-, 10-, and 100-year post development peak runoff rates must be equal to or less than the existing discharge rates at all locations where stormwater leaves the site. The applicant used a HydroCAD hydrologic model to simulate runoff rates for pre- and post-development conditions for the 2-, 10-, and 100-year frequency storm events using a 24-hour nested rainfall distribution, and a 100-year frequency, 10-day snowmelt event. Because runoff from the regulated impervious area only impacts the flows at a single location, the rate control analysis was limited to the one discharge location to the southwest (i.e., SW Discharge). The existing and proposed 2-, 10-, and 100-year frequency discharges from the site are summarized in Table 2 below. The proposed project conforms to RPBCWD Rule J, Subsection 3.1.a.

Table 2. Existing and Proposed Peak Runoff Rates

Modeled Discharge Location	2-Year Di (cf	_	10-Year Discharge (cfs)		100-Year Discharge (cfs)		10-Day Snowmelt (cfs)	
	Ex	Prop	Ex	Prop	Ex	Prop	Ex	Prop
SW discharge	0.3	<0.1	1.4	0.7	5.1	1.9	0.6	0.6

Volume Abstraction

Subsection 3.1.b of Rule J requires the abstraction onsite of 1.1 inches of runoff from the regulated impervious surface of the site. An abstraction volume of 2,308 cubic feet is required from the 0.58 acres (25,171 square feet) of regulated impervious area. Pretreatment of runoff entering the facility is provided with upstream drainage structures with 4-foot-deep sumps and overland vegetated flow to conform to Rule J, Subsection 3.1.b.1.

The soil borings performed by American Engineering Testing throughout the site show that soils in the project area primarily consist of sand and silty sand. Groundwater was not observed at any of the soil borings near the proposed infiltration basin down to an elevation of approximately 845 feet. The subsurface investigation information summarized in Table 3 shows that groundwater, assumed to be at the end of the boring, is at least 3 feet below the bottom of the proposed underground stormwater management facility (Rule J, Subsection 3.1.b.2.a).

Table 3. Groundwater Separation Analysis

Proposed BMP	Nearest Subsurface Investigation	Boring is within footprint?	Groundwater Elevation (feet)	BMP Bottom Elevation (feet)	Separation (feet)
Infiltration Basin	I-6	Yes	No groundwater observed at boring bottom (approx. el 845 ft)	864	19

The engineer concurs with the applicant's design infiltration rate of 0.80 inches per hour reflecting sand (SP) soils based on the guidelines provided in the Mn Stormwater Manual. Based on the design infiltration rate, the engineer concurs that the basin will draw down within 48 hours (Rule J, subsection 3.1b.3). Because of frozen ground conditions, subsurface infiltration testing was not performed at the BMP location. Per Rule J, Subsection 3.1.b.2.c, measured infiltration capacity of the soils at the bottom of the infiltration system must be provided. Due to frozen soil conditions, in-situ subsurface infiltration testing was not performed at the BMP location. Per Rule J, Subsection 3.1.b.2.c measured infiltration capacity of the soils at the bottom of the infiltration systems must be provided. The applicant must submit documentation verifying the infiltration capacity of the soils and that the volume control capacity is calculated using the measured infiltration rate. If infiltration capacity is less than needed to conform with the volume abstraction requirement in subsection 3.1b or there is inadequate separation to groundwater, design modifications to achieve compliance with RPBCWD requirements will need to be submitted (in the form of an application for a permit modification or new permit).

Table 4 summarizes the volume abstraction required and the volume abstraction achieved by the proposed stormwater management facilities on site. With the stipulation noted above regarding verification of amended soil infiltration rate, the engineer concurs with the submitted information and finds that the proposed project will conform with Rule J, Subsection 3.1.b.

Required **Required Abstraction** Provided **Provided Abstraction Depth** Abstraction Volume Abstraction (inches) (cubic feet) Depth Volume (inches) (cubic feet) 1.1 1.2 2,308 2,766

Table 4. Volume Abstraction Summary

With the conditions noted above, the engineer concurs with the submitted information and finds that the proposed project will conform with Rule J, Subsection 3.3.a.

Water Quality Management

Subsection 3.1.c of Rule J requires the Applicant to provide volume abstraction in accordance with 3.1b or least 60 percent annual removal efficiency for total phosphorus (TP), and at least 90 percent annual removal efficiency for total suspended solids (TSS) from site runoff, and no net increase in TSS or TP loading leaving the site from existing conditions. Because the infiltration basin proposed by the applicant provides volume abstraction meeting the standard in 3.1b and the engineer concurs with the modeling, under paragraph 3.1c.i, the engineer finds that the proposed project provides the required stormwater-quality protection.

Low floor Elevation

All new buildings must be constructed such that the lowest floor is at least two feet above the 100-year high-water elevation or one foot above the emergency overflow of a stormwater-management facility according to Rule J, Subsection 3.6a. No new buildings are being constructed as part of the project. The lowest elevation of the nearest existing building and the 100-year event flood elevation in the stormwater infiltration basin is summarized below. The RPBCWD Engineer concurs that the proposed project is in conformance with Rule J, Subsection 3.6. Because the low floor elevations are more than two feet above the proposed 100-year flood elevation, the proposed project is in conformance with Rule J, Subsection 3.6.

Table 5. Low Floor Evaluation

Location	Low Floor Elevation of Building (feet)	100-year Event Flood Elevation (feet)	Freeboard (feet)
Infiltration Basin	872.17	869.13	3.04

Maintenance

Subsection 3.7 of Rule J requires the submission of maintenance plan. All stormwater management structures and facilities must be designed for maintenance access and properly maintained in perpetuity to assure that they continue to function as designed. To conform to the RPBCWD Rule J the following revisions are needed:

J1. Permit applicant must provide a maintenance and inspection declaration as required by Rule J, Subsection 3.7. A draft declaration must be provided for District review and approval prior to recordation as a condition of issuance of the permit.

Wetland Protection

Because runoff from this site is tributary to Riley Creek and is not tributary to any wetland, the proposed project does not trigger analysis under Rule J, subsection 3.10.

Chloride Management

Subsection 3.8 of Rule J requires the submission of chloride management plan that designates the individual authorized to implement the chloride management plan and the MPCA-certified salt applicator engaged in implementing the plan. To close out the permit and release the \$5,000 in financial assurance held for the purpose of chloride management, the permit applicant must provide a chloride management plan that designates the individual authorized to implement the chloride management plan and the MPCA-certified salt applicator engaged in implementing the plan at the site.

Rule L: Permit Fee Deposit:

The RPBCWD permit fee schedule adopted in February 2020 requires permit applicants to deposit \$3,000 to be held in escrow and applied to cover the \$10 permit-processing fee and reimburse RPBCWD for permit review and inspection-related costs and when a permit application is approved, the deposit must be replenished to the applicable deposit amount by the applicant before the permit will be issued to cover actual costs incurred to monitor compliance with permit conditions and the RPBCWD Rules. A permit fee deposit of \$3,000 was received on January 16, 2024. If the costs of review, administration, inspections and closeout-related or other regulatory activities exceed the fee deposit amount, the applicant will be required to replenish the deposit to the original amount or such lesser amount as the RPBCWD administrator deems sufficient within 30 days of receiving notice that such deposit is due. The administrator will close out the relevant application or permit and revoke prior approvals, if any, if the permit-fee deposit is not timely replenished.

L1. The applicant must replenish the permit fee deposit to the original amount due before the permit will be issued. As of January 31, 2024 the amount due is \$2,869.

Rule M: Financial Assurance

	Unit	Unit Cost	# of	Total
			Units	
Rule C: Erosion Control				
Perimeter Control	LF	\$2.50	1,300	\$3,250
Inlet Protection	EA	\$100	3	\$300
Rock Entrance	EA	\$250	1	\$250
Restoration	AC	\$2,500	1.50	\$3,750
Rule J: Chloride Management	LS	\$5,000	1	\$5,000
Rule J: Stormwater Management:	EA	125% OPC	1	\$104,875
125% of engineer's opinion of cost				
(\$83,900)				
Contingency (10%)		10%		\$11,743
Total Financial Assurance				\$129,168

Applicable General Requirements:

- 1. The RPBCWD Administrator and Engineer must be notified at least three days prior to commencement of work.
- 2. Construction must be consistent with the plans and specifications approved by the District as a part of the permitting process. The date of the approved plans and specifications is listed on the permit.
- 3. Construction must be consistent with the plans, specifications, and models that were submitted by the applicant that were the basis of permit approval. The date(s) of the approved plans, specifications, and modeling are listed on the permit. The grant of the permit does not in any way relieve the permittee, its engineer, or other professional consultants of responsibility for the permitted work.

- 4. The grant of the permit will not relieve the permittee of any responsibility to obtain approval of any other regulatory body with authority.
- 5. The issuance of this permit will not convey any rights to either real or personal property, or any exclusive privileges, nor will it authorize any injury to private property or any invasion of personal rights, nor any infringement of federal, state, or local laws or regulations.
- 6. In all cases where the doing by the permittee of anything authorized by this permit involves the taking, using or damaging of any property, rights or interests of any other person or persons, or of any publicly owned lands or improvements or interests, the permittee, before proceeding therewith, must acquire all necessary property rights and interest.
- 7. RPBCWD's determination to approve the permit application was made in reliance on the information provided by the applicant. Any substantive change in the work affecting the nature and extent of applicability of RPBCWD regulatory requirements or substantive changes in the methods or means of compliance with RPBCWD regulatory requirements must be the subject of an application for a permit modification to the RPBCWD.
- 8. If the conditions herein are met and the permit is issued by RPBCWD, the applicant, by accepting the permit, grants access to the site of the work at all reasonable times during and after construction to authorized representatives of the RPBCWD for inspection of the work.

Findings

- 1. The proposed project includes the information necessary, plan sheets and erosion control plan for review.
- 2. The proposed project conforms to Rule C and will conform to Rule J if the Rule Specific Permit Conditions listed above are met.

Recommendation:

Approval of the permit contingent upon:


- 1. Financial Assurance in the amount of \$129,168
- Receipt by RPBCWD of documentation of recordation of a maintenance declaration for the stormwater management facility. A draft of the declaration must be reviewed and approved by the District prior to recordation.
- 3. The applicant must replenish the permit fee deposit to the original amount due before the permit will be issued. As of January 31, 2024 the amount due is \$2,869.

By accepting the permit, when issued, the applicant agrees to the following stipulations:

- 1. Continued compliance with General Requirements.
- 2. Per Rule J Subsection 4.5, upon completion of the site work, the permittee must submit as-built drawings demonstrating that at the time of final stabilization the stormwater management facility conforms to design specifications and functions as intended and approved by the District. As-

built/record drawings must be signed by a professional engineer licensed in Minnesota and include, but not limited to:

- a) the surveyed bottom elevations, water levels, and general topography of all facilities;
- b) the size, type, and surveyed invert elevations of all stormwater facility inlets and outlets;
- c) the surveyed elevations of all emergency overflows including stormwater facility, street, and other;
- d) other important features to show that the project was constructed as approved by the Managers and protects the public health, welfare, and safety.
- 3. Providing the following additional close-out materials:
 - a. Documentation that disturbed pervious areas remaining pervious have been decompacted per Rule C.2c criteria.
 - b. Documentation that constructed infiltration facilities perform as designed. This may include infiltration testing, flood testing, or other with prior approval from RPBCWD.
- 4. The work on the Grace Church Playground development under the terms of permit 2023-079, if issued, must have an impervious surface area and configuration materially consistent with the approved plans. Design that differs materially from the approved plans (e.g., in terms of total impervious area) will need to be the subject of a request for a permit modification or new permit, which will be subject to review for compliance with all applicable regulatory requirements.
- 5. Per Rule J, Subsection 3.1.b.ii measured infiltration capacity of the soils at the bottom of the infiltration system must be provided. The applicant must submit documentation verifying the infiltration capacity of the soils and that the volume control capacity is calculated using the measured infiltration rate. In addition, subsurface soil investigation is needed to verify adequate separation to groundwater (Rule J subsection 3.1.b.2). If infiltration capacity is less than needed to conform with the volume abstraction requirement in subsection 3.1b or there is inadequate separation to groundwater, design modifications to achieve compliance with RPBCWD requirements will need to be submitted (in the form of an application for a permit modification or new permit).
- 6. To close out the permit and release the \$5,000 in financial assurance held for the purpose of the chloride management, the permit applicant must provide a chloride management plan that designates the individual authorized to implement the chloride management plan and the MPCA-certified salt applicator engaged in implementing the plan at the site.
- 7. The Applicant must notify RPBCWD if the individual responsible for erosion control at the site changes during the permit term.



ABBREVIATIONS AREA DRAIN AMERICAN DISABILITY ACT **AGGREGATE** AMERICAN LAND TITLE ASSOCIATION **ARCH** ARCHITECTURAL AMERICAN SOCIETY FOR TESTING & MATERIALS BITUMINOUS BEST MANAGEMENT PRACTICE BOTTOM **CATCH BASIN** CO **CLEAN OUT** CONC CONCRETE CSP CORRUGATE STEEL PIPE CY CUBIC YARD DIAMETER DUCTILE IRON PIPE DWGS DRAWINGS **ELECTRICAL** FES FLARED END SECTION GATE VALVE HIGH DENSITY POLYETHYLENE PIPE HIGH WATER **HYDRANT** INVERT LINEAR FOOT MAXIMUM **MECHANICAL MANHOLE** MINIMUM NOT TO SCALE POLYETHYLENE PIPE POUNDS/SQUARE INCH POLY VINYL CHLORIDE RADIUS REINFORCED CONCRETE PIPE SEWER **SQUARE FOOT STRUCTURE** STM STORM STRUCT STRUCTURAL **TESTING AGENCY** T/W TOP OF WALL TYP **TYPICAL**

UNLESS NOTED OTHERWISE

WATER

WAT

EROSION AND SEDIMENT CONTROL

- 1. INSTALL PERIMETER EROSION CONTROLS AS INDICATED IN PLANS PRIOR TO START OF WORK. HAY BALES ARE NOT ALLOWED AS EROSION AND SEDIMENT CONTROL DEVICES.
- 2. ESTABLISH ROCK CONSTRUCTION ENTRANCES PRIOR TO BEGINNING LAND DISTURBING ACTIVITIES. 1 "-3" WASHED AGGREGATE IS RECOMMENDED FOR ROCK ENTRANCES, A GEOTEXTILE FABRIC IS REQUIRED.
- 3. REMOVE ALL SOILS AND SEDIMENTS DEPOSITED ONTO PUBLIC AND/OR PRIVATE PAVEMENT AREAS WITHIN 24 HOURS OF DEPOSITION. REMOVAL OF TRACKING MATERIALS SHALL BE COMPLETED AT THE END OF EACH WORK DAY WHEN TRACKING OCCURS. SWEEPING MAY BE ORDERED AT ANY TIME IF CONDITIONS WARRANT. SWEEPING SHALL BE MAINTAINED THROUGHOUT THE DURATION OF CONSTRUCTION AND IN SUCH A MANNER TO PREVENT DUST BEING BLOWN TO ADJACENT PROPERTIES.
- 4. INSTALL INLET PROTECTION IN ALL DOWNSTREAM CATCH BASINS WHICH RECEIVE RUNOFF FROM THE DISTURBED AREA. CATCH BASIN INSERTS ARE REQUIRED AT ALL LOCATIONS NOT WITHIN THE DISTURBED AREA WHICH RECEIVE RUNOFF (MNDOT TYPE C INLET PROTECTION). NOTE HAY BALES AND SILT FENCE WRAPPED GRATES ARE NOT EFFECTIVE AND ARE NOT APPROVED FOR USE AS INLET PROTECTION DEVICES.
- 5. LOCATE ALL SOIL AND DIRT PILES NOT LESS THAN 25 FEET FROM ANY PUBLIC OR PRIVATE ROADWAY OR DRAINAGE CHANNEL. ALL STOCK PILES THAT REMAIN IN PLACE FOR 7 DAYS OR MORE SHALL BE STABILIZED BY MULCHING, VEGETATIVE COVER, TARPING OR OTHER MEANS. TEMPORARY STOCK PILES LOCATED ON PAVED SURFACES MUST BE AT LEAST 2 FET OR MORE AWAY FROM THE DRAINAGE/GUTTER LINE AND SHALL BE COVERED, IF REMAINING MORE THAN 24 HOURS.
- MAINTAIN ALL TEMPORARY EROSION CONTROL DEVICES IN PLACE UNTIL THE CONTRIBUTING DRAINAGE AREA HAS BEEN STABILIZED. INSPECT TEMPORARY EROSION AND SEDIMENT CONTROL DEVICES ON A WEEKLY BASIS AND REPLACE DETERIORATED, DAMAGED OR ROTTED EROSION CONTROL DEVICES IMMEDIATELY.
- MAINTENANCE OF EROSION AND SEDIMENT CONTROL DEVICES SHALL BE PERFORMED WHENEVER THE DEVICE IS 30% FULL, FAILURE TO MAINTAIN EROSION CONTROL DEVICES MAY LEAD TO FURTHER ENFORCEMENT ACTION. WEEKLY INSPECTIONS REQUIRED AND AFTER EACH 1 OR MORE RAIN EVENT WITHIN 24 HOURS.
- READY MIXED CONCRETE AND BATCH PLANT WASHOUTS PROHIBITED WITHIN THE PUBLIC RIGHT OF WAY, DESIGNATE CONCRETE WASHOUT AND MIXING LOCATIONS IN THE EROSION CONTROL PLANS. UNDER NO CIRCUMSTANCES MAY WASHOUT WATER DRAIN ONTO THE PUBLIC RIGHT OF WAY OR INTO THE PUBLIC STORM DRAIN.
- TEMPORARY OR PERMANENTLY STABILIZE ALL DENUDED AREAS WHICH HAVE BEEN FINISH GRADED WITHIN 7-14 DAYS (SLOPE DEPENDENT). USE SEEDING AND MULCHING, EROSION CONTROL MATTING AND/OR SODDING WITH TEMPORARY STAKING IN GREEN SPACE AREAS. USE EARLY APPLICATION OF GRAVEL BASE FOR AREAS DESIGNATED FOR PAVED SURFACING.
- 10. REMOVE ALL TEMPORARY SYNTHETIC, STRUCTURAL AND NON-BIODEGRADABLE EROSION AND SEDIMENT CONTROL AFTER THE SITE HAS UNDERGONE FINAL STABILIZATION AND PERMANENT VEGETATION HAS BEEN ESTABLISHED, MINIMUM VEGETATION COVER OF 70% REQUIRED, ALL TEMPORARY EROSION AND SEDIMENT CONTROL DEVICES SHALL BE MAINTAINED UNTIL THE SITE HAS 70% ESTABLISHED VEGETATIVE COVER AND ALL PAVED AREAS HAVE BEEN STABILIZED WITH THE SELECTED PAVEMENT TYPE.
- 11. FURNISH AND INSTALL EROSION PREVENTION AND SEDIMENT CONTROL BMPs AS NECESSARY TO PREVENT EROSION FROM DISTURBED SURFACES AND CAPTURE SEDIMENT ON SITE. ALL EROSION CONTROL MEASURES SHALL BE IN PLACE PRIOR TO ANY REMOVAL WORK AND/OR GROUND DISTURBING ACTIVITIES COMMENCE AND SHALL BE MAINTAINED UNTIL THE POTENTIAL FOR EROSION HAS BEEN ELIMINATED. SEDIMENT CONTROL DEVICES MUST BE ESTABLISHED ON ALL DOWN-GRADIENT PERIMETERS BEFORE ANY UP-GRADIENT LAND DISTURBING ACTIVITIES BEGIN.
- 12. STORM SEWER INLETS SHALL BE PROTECTED AT ALL TIMES WITH THE APPROPRIATE INLET PROTECTION DEVICE FOR EACH SPECIFIC PHASE OF CONSTRUCTION. INLET PROTECTION DEVICES MAY NEED TO BE REPLACED MULTIPLE TIMES IN THE SAME LOCATION OVER THE LIFE OF THE PROJECT. ALL STORM SEWER INLET PROTECTION DEVICES SHALL BE KEPT IN GOOD FUNCTIONAL CONDITION AT ALL TIMES.

STANDARD EROSION CONTROL NOTES FOR RPBCWD DEVELOPMENT REVIEWS:

- C1. THE EROSION CONTROL PLAN MUST INCLUDE THE FOLLOWING NOTES:
- a. NATURAL TOPOGRAPHY AND SOIL CONDITIONS MUST BE PROTECTED, INCLUDING RETENTION ONSITE OF NATIVE TOPSOIL TO THE GREATEST EXTENT POSSIBLE.
- b. ADDITIONAL MEASURES, SUCH AS HYDRAULIC MULCHING AND OTHER PRACTICES AS SPECIFIED BY THE DISTRICT MUST BE USED ON SLOPES OF 3:1 (H:V) OR STEEPER TO PROVIDE ADEQUATE STABILIZATION.
- c. FINAL SITE STABILIZATION MEASURES MUST SPECIFY THAT AT LEAST SIX INCHES OF TOPSOIL OR ORGANIC MATTER BE SPREAD AND INCORPORATED INTO THE UNDERLYING SOIL DURING FINAL SITE TREATMENT WHEREVER TOPSOIL HAS BEEN REMOVED.
- d. CONSTRUCTION SITE WASTE SUCH AS DISCARDED BUILDING MATERIALS, CONCRETE TRUCK WASHOUT, CHEMICALS, LITTER AND SANITARY WASTE MUST BE PROPERLY MANAGED.
- e. ALL TEMPORARY EROSION AND SEDIMENT CONTROL BMPS MUST BE MAINTAINED UNTIL COMPLETION OF CONSTRUCTION AND VEGETATION IS ESTABLISHED SUFFICIENTLY TO ENSURE STABILITY OF THE SITE, AS DETERMINED BY THE DISTRICT.
- f. ALL TEMPORARY EROSION AND SEDIMENT CONTROL BMPS MUST BE REMOVED UPON FINAL STABILIZATION. g. SOIL SURFACES COMPACTED DURING CONSTRUCTION AND REMAINING PERVIOUS UPON COMPLETION OF CONSTRUCTION MUST BE DECOMPACTED TO ACHIEVE A SOIL COMPACTION TESTING PRESSURE OF LESS THAN 1,400 KILOPASCALS OR 200 POUNDS PER SQUARE INCH IN THE UPPER 12 INCHES OF THE SOIL PROFILE
- WHILE TAKING CARE TO PROTECT UTILITIES, TREE ROOTS, AND OTHER EXISTING VEGETATION. h. ALL DISTURBED AREAS MUST BE STABILIZED WITHIN 7 CALENDAR DAYS AFTER LAND-DISTURBING WORK HAS TEMPORARILY OR PERMANENTLY CEASED ON A PROPERTY THAT DRAINS TO AN IMPAIRED WATER, WITHIN 14 DAYS ELSEWHERE
- i. THE PERMITTEE MUST, AT A MINIMUM, INSPECT, MAINTAIN AND REPAIR ALL DISTURBED SURFACES AND ALL EROSION AND SEDIMENT CONTROL FACILITIES AND SOIL STABILIZATION MEASURES EVERY DAY WORK IS PERFORMED ON THE SITE AND AT LEAST WEEKLY UNTIL LAND-DISTURBING ACTIVITY HAS CEASED. THEREAFTER, THE PERMITTEE MUST PERFORM THESE RESPONSIBILITIES AT LEAST WEEKLY UNTIL VEGETATIVE COVER IS ESTABLISHED. THE PERMITTEE WILL MAINTAIN A LOG OF ACTIVITIES UNDER THIS SECTION FOR INSPECTION BY THE DISTRICT ON REQUEST.

GENERAL CIVIL NOTES:

PREPARATION & RESTORATION

- EXISTING SITE CONDITIONS DEPICTED ON THE DRAWINGS ARE BASED ON TOPOGRAPHIC & UTILITY SURVEY PROVIDED BY THE OWNER. THE CONTRACTOR MUST VISIT THE SITE TO VERIFY EXISTING CONDITIONS.
- CONTRACTOR MUST OBTAIN ALL REQUIRED PERMITS FROM CITY, STATE AND OTHER REGULATORY AGENCIES. OWNER WILL OBTAIN THE RILEY-PURGATORY-BLUFF CREEK WATERSHED DISTRICT PERMIT ALL WORK MUST COMPLY WITH PERMIT CONDITIONS.
- 3. UTILIZE THE STATE ONE CALL SYSTEM @ 1-800-252-1166, 48 HOURS PRIOR TO PERFORMING ANY EXCAVATION. EXISTING UNDERGROUND UTILITIES ARE SHOWN AT APPROXIMATE LOCATIONS BASED ON INFORMATION PROVIDED BY UTILITY COMPANIES IN RESPONSE TO A LOCATE REQUEST MADE BY THE SURVEYOR. ALL EXISTING UTILITIES MAY NOT BE SHOWN.
- 4. PRIOR TO CONSTRUCTION, FIELD-VERIFY LOCATION AND ELEVATION OF UTILITIES THAT MAY BE IMPACTED OR DAMAGED BY CONSTRUCTION. REPORT ANY CONFLICTS OR EXISTING DAMAGE TO THE OWNER AND A/E PRIOR TO ORDERING ANY MATERIALS FOR CONSTRUCTION.
- 5. INSTALL ALL EROSION AND SEDIMENT CONTROL PRACTICES, PRIOR TO COMMENCEMENT OF LAND DISTURBING ACTIVITIES IN ACCORDANCE WITH APPLICABLE PERMIT(S).
- PROTECT EXISTING UTILITY PIPES AND APPURTENANCES FROM DAMAGE DUE TO CONSTRUCTION ACTIVITY. PROVIDE TEMPORARY SUPPORT AND BRACING OF UTILITIES IN ACCORDANCE WITH UTILITY OWNER'S REQUIREMENTS AS REQUIRED FOR CONSTRUCTION.
- 7. COORDINATE DISRUPTION OF UTILITY SERVICES WITH OWNER. LIMIT SERVICE DISRUPTION TO TIMES APPROVED BY OWNER.
- 8. PROVIDE TRAFFIC CONTROL IN ACCORDANCE WITH THE MINNESOTA MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES, INCLUDING THE TEMPORARY TRAFFIC CONTROL ZONE LAYOUTS FIELD MANUAL LATEST EDITION, AT ALL TIMES THAT CONSTRUCTION ACTIVITY DISRUPTS TRAFFIC ON PUBLIC ROADWAYS

9. COORDINATE DISRUPTION OF PEDESTRIAN AND VEHICULAR TRAFFIC WITH OWNER. OBTAIN ALL REQUIRED

- STREET AND SIDEWALK CLOSURE PERMITS. CONTACT CITY OR ROAD AUTHORITY TO VERIFY REQUIREMENTS.
- 10. CARE MUST BE TAKEN DURING CONSTRUCTION TO PROTECT SURVEY MONUMENTS AND PROPERTY
- 11. PROTECT ALL TREES NOT SPECIFICALLY DESIGNATED FOR REMOVAL
- 12. SAWCUT PAVEMENT THAT REMAINS AT REMOVAL LIMITS.
- 13. REMOVE & REPLACE ALL TRAFFIC SIGNS DISTURBED BY CONSTRUCTION ACTIVITY
- 14. RESTORE OR REPAIR DAMAGED ROADS, WALKS, CURBS, UTILITIES, OR PLANT MATERIALS TO CONDITION EQUAL TO OR BETTER THAN PRE-CONSTRUCTION CONDITION AND AS REQUIRED BY OWNER.
- 15. ALL WORK MUST COMPLY WITH APPLICABLE SECTIONS OF THE MNDOT STANDARD SPECIFICATIONS FOR CONSTRUCTION AND SUPPLEMENTAL DOCUMENTS, LATEST EDITION; AND THE CITY ENGINEERS ASSOCIATION OF MINNESOTA STANDARD SPECIFICATIONS, LATEST EDITION.
- 16. LEGALLY DISPOSE OF ALL WASTE MATERIALS, DEBRIS AND EXCESS EXCAVATED MATERIAL
- 17. MAINTAIN ACCURATE RECORDS OF ALL NEW UTILITY CONSTRUCTION INCLUDING SURVEYED ELEVATIONS OF PIPE AND STRUCTURE INVERTS FOR AS-BUILT OR RECORD DOCUMENTS
- 18. MITIGATE DISTURBED SITE AREA SOILS COMPACTED BY CONSTRUCTION ACTIVITY THAT WILL BE SEEDED OR PLANTED BY SCARIFYING SOIL TO A DEPTH OF 24", COVERING SOIL WITH 2" OF GRADE 2 COMPOST (MNDOT 3890), AND TILLING COMPOST INTO SOIL PRIOR TO SEEDING OR PLANTING.

LAYOUT & SURFACING

- 1. ALL DIMENSIONS TO CURBS AND CURB&GUTTER ARE TO THE FACE OF CURB UNLESS OTHERWISE NOTED. BACK OF CURB IS TYPICALLY 8-INCHES BEHIND THE FACE OF CURB.
- 2. GUIDELINES FOR CONSTRUCTION OF NEW CONCRETE SURFACING
- a. MAXIMUM SPACING OF CONTROL JOINTS IN WALKS TO BE 8-FEET, BUT GENERALLY MATCH THE WALK
- b. MAXIMUM SPACING OF CONTROL JOINTS IN CONCRETE TRAFFIC SLABS TO BE 12-FEET.
- c. ALIGN JOINTS WITH WALK CORNERS, HORIZONTAL DEFLECTIONS, BUILDING CORNERS, ETC. AND USE NOMINALLY EQUAL PANEL SIZES.
- d. SEE 4/C900 FOR JOINTING DETAILS.
- e. PROVIDE 2% CROSS SLOPE UNLESS DESIGNATED OTHERWISE ON SITE PLANS.
- 3. DRIVEWAY APRON, SIDEWALK AND CURB & GUTTER WITHIN THE PUBLIC RIGHT-OF-WAY MUST BE CONSTRUCTED IN ACCORDANCE WITH THE APPLICABLE CITY OR STATE DOT STANDARDS.

GRADING

- SEE SITE SURVEY SHEET(S) FOR BENCHMARKS.
- 2. ALL EXPOSED SOIL AREAS MUST BE TEMPORARILY OR PERMANENTLY STABILIZED NO MORE THAN 7 DAYS AFTER CONSTRUCTION ACTIVITY ON THAT PORTION OF THE SITE HAS CEASED.
- 3. SPOT ELEVATIONS ARE TYPICALLY GIVEN AT FINISHED SURFACE. AT TOP OF CURB, ELEVATIONS ARE NOTED WITH A "TC".
- 4. PRIOR TO CONSTRUCTION, FIELD-VERIFY EXISTING BUILDING FLOOR ELEVATION(S) TO CONFIRM MATCH WITH NEW FLOOR ELEVATION(S).
- 5. SEE REPORT OF GEOTECHNICAL EXPLORATION PREPARED BY AMERICAN ENGINEERING TESTING, INC, DATED JANUARY 31, 2023 FOR INFORMATION ON SOILS AND SUBGRADE PREPARATION.
- AREAS. b. OVERSIZE EXCAVATION 1-FOOT LATERALLY FOR EACH FOOT OF EXCAVATION BELOW BOTTOM OF FOOTING ELEVATION.

a. REMOVE ALL TOPSOIL, FILL AND UNSUITABLE MATERIAL FROM THE PROPOSED PAVEMENT AND FOOTING

- c. EXISTING EXCAVATED SOIL WITH MORE THAN 2% ORGANIC CONTENT OR DEBRIS CAN NOT BE USED WITHIN THE FOOTING AREA AS FILL
- d. REMOVE ALL TOPSOIL, FILL, AND ORGANIC MATERIALS WITHIN 3-FEET OF THE FINISHED PAVEMENT SURFACE.
- e. TEST ROLL SUBGRADE SOILS WITH A FULLY LOADED TANDEM AXLE TRUCK, AND CORRECT ALL UNSTABLE AREAS. CORRECTION OPTIONS INCLUDE SUBCUTTING AND REPLACING WITH CRUSHED AGGREGATE, CHEMICAL STABILIZATION AND/OR USE OF GEOTEXTILES.
- 6. TESTING AGENCY MUST OBSERVE AND APPROVE ALL BUILDING AND PAVEMENT SUBGRADE SOILS

UTILITIES

- 1. VERIFY BUILDING STORM, SANITARY, AND WATER SERVICE LOCATIONS AND ELEVATIONS WITH PLUMBING CONTRACTOR PRIOR TO CONSTRUCTION OF SERVICE LINES.
- 2. ALL UTILITY DEMOLITION OR ABANDONMENT MUST COMPLY WITH UTILITY OWNER'S REQUIREMENTS
- 3. PROVIDE MINIMUM 8.0' COVER ON ALL WATER MAINS. ALL WATER MAIN CONSTRUCTION MUST COMPLY WITH CITY REQUIREMENTS.
- 4. SANITARY AND STORM SEWER CONSTRUCTION MUST COMPLY WITH CITY REQUIREMENTS.
- COORDINATE CONNECTIONS TO EXISTING UTILITY SYSTEMS WITH UTILITY OWNER.

OF PIPE AND STRUCTURE INVERTS FOR AS-BUILT OR RECORD DOCUMENTS.

- 6. SEE SHEET C405 FOR NEW STORM STRUCTURE INFORMATION
- 7. ADJUST ALL CASTINGS AND VALVE BOXES WITHIN PROJECT LIMITS TO FINAL ELEVATION 1/4" BELOW FINISHED SURFACE.
- 9. PROVIDE SUBSOIL DRAINAGE PIPE AT ALL BELOW GRADE BUILDING WALL AND LOW AREAS IN PARKING LOTS.
- 10. ALL PIPE CONSTRUCTION IS SUBJECT TO VIDEO INSPECTION TO CONFIRM THAT THERE ARE NO SAGS IN THE PIPE PROFILE. PIPES MUST HAVE A CONTINUOUS STRAIGHT SLOPE BETWEEN MANHOLES. 11. MAINTAIN ACCURATE RECORDS OF ALL NEW UTILITY CONSTRUCTION INCLUDING SURVEYED ELEVATIONS

UTILITY CONTACTS:

WATER SEWER CENTERPOINT ENERGY 612-321-5363 XCEL ENERGY 800-848-7558 CENTURY LINK 877-366-8344

PLAN LEGEND (SEE SITE SURVEY FOR EXISTING FEATURES LEGEND) X REMOVE TREE/SHRUB REMOVE CURB REMOVE UNDERGROUND UTILITY · X X X X ABANDON UTILITY IN-PLACE REMOVE PAVEMENT/WALK SAWCUT LINE ____..._ TREE PROTECTION DOOR / EXIT **NEW CURB TAPER** 144444 **NEW SINGLE SIGN** NEW DOUBLE SIGN **NEW ISOLATION JOINT** ___<u>IJ</u>___ **NEW CONTROL JOINT** CONSTRUCTION LIMITS EXISTING INDEX CONTOUR **EXISTING CONTOUR EXISTING CONTOUR DISTURBED** PROPOSED CONTOUR $_{\perp}936.00$ PROPOSED SPOT ELEVATION **EXISTING SPOT ELEVATION** DRAINAGE ARROW DRAINAGE DIVIDE **NEW MANHOLE** NEW DRAINAGE STRUCTURE SOIL BORING **EXISTING SANITARY SEWER EXISTING STORM SEWER** _____ **EXISTING WATERMAIN** ______ **EXISTING GAS** NEW SANITARY SEWER —>—>— NEW STORM SEWER ——>> —— **NEW WATERMAIN** NEW SUB-DRAIN **NEW LIGHT FIXTURES** SILT FENCE **INLET PROTECTION EROSION FIBER LOG EROSION CONTROL BLANKET**

Owner Grace Church Eden Prairie 9301 Eden Prairie Rd. Eden Prairie, MN 55347 isioneering Studios Architecture 106 W. 4th Street, Suite 600 Hammel, Green and Abrahamson Sunde Land Surveying, LLC 9001 East Bloomington Freeway Bloomington, MN 55420 **DESIGN TEAM** Drawn By TEAM Checked By CHECKER **REVISIONS** NO. DATE | COMMENT 2023-12-26 RILEY PURGATORY BLUFF CREEK WATERSHED DISTRICT

(952) 224-3000

Santa Ana, CA 92701

(888) 539-1957

420 North 5th Street

Minneapolis, MN 55401

(612) 758-4000

STE 118

(952) 886-3118

PROJECT

22641

OWNER, PROJECT NAME & LOCATION:

GRACE CHURCH PROJECT NAME: PRESCHOOL TI

STREET: 9301 EDEN PRAIRIE ROAD CITY: EDEN PRAIRIE COUNTY: HENNEPIN STATE: MN

ZIP CODE: 55347 LATITUDE/LONGITUDE: 44.83475. -93.47786

MPCA CONTACT INFORMATION: MINNESOTA POLLUTION CONTROL AGENCY CONSTRUCTION STORMWATER ERMIT PROGRAM 520 LAYFAYETTE ROAD NORTH

651-296-6300 OR https://www.pca.state.mn.us/water/construction-stormwater

PROJECT DESCRIPTION/LOCATION:

THIS PROJECT IS LOCATED IN EDEN PRAIRIE, MN, AND WILL CONSIST OF THE CONSTRUCTION OF A NEW PLAYGROUND WITH SITE GRADING, STORM SEWER, AND A STORM WATER BASIN.

SWPPP TRAINING

ST. PAUL. MN 55155-4194

LOCATION:

THE PROJECT SWPPP WAS PREPARED BY PERSONNEL THAT ARE CERTIFIED IN THE DESIGN OF CONSTRUCTION SWPPP'S. A CERTIFICATION CARD IS AVAILABLE UPON REQUEST

THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING A CERTIFIED EROSION CONTROL SUPERVISOR THAT IS RESPONSIBLE FOR OVERSEEING THE IMPLEMENTATION OF THE SWPPP.

SWPPP COMPONENTS AND LOCATIONS

THE SWPPP IS A COMBINATION OF NARRITIVE, PLAN SHEETS AND STANDARD DETAIL SHEETS THAT ADDRESS THE FORESEEABLE CONDITIONS THAT MAY OCCUR DURING THE CONSTRUCTION OR POST CONSTRUCTION ACTIVITIES. THE SWPPP COMPONENTS ARE PROVIDED IN THE **FOLLOWING LOCATIONS:**

SWPPP NARRATIVE	THIS SHEET
LOCATION AND TYPE OF BMPs	SHEETS C101
ESTIMATED QUANTITIES	THIS SHEET
IMPERVIOUS SURFACE AREA CALCULATIONS	THIS SHEET
SITE MAP	THIS SHEET - SEE ABOVE RIGHT
LOCATIONS OF AREAS NOT TO BE DISTURBED	SHEETS C101
CONSTRUCTION PHASING	CONSTRUCTION WILL NOT BE PHASED
MAPS OF SURFACE WATERS AND WETLANDS	THIS SHEET
FINAL STABILIZATION	SHEETS L200 AND SPEC SECTION 329200
BMP DETAILS	SHEET C102
SITE GRADING	SHEETS C400-C401

EROSION CONTROI

DESCRIPTION

A REPORT OF GEOTECHNICAL EXPLORATION AND REVIEW WAS PREPARED BY AMERICAN ENGINEERING TESTING, DATED JANUARY 31, 2023. IN GENERAL, THE PROJECT SITE CONSISTS OF SEVERAL FEET OF TOPSOIL OR FILL SOILS (1' - 7'). THESE SOILS ARE GENERALLY UNDERLAIN BY ONE OR MORE LAYERS OF SAND WITH SILT (SP-SM), SILTY SAND (SM) OR SAND (SP).

SHEETS C101

LOCATION

POTENTIAL FOR RAINFALL AND SOIL PARTICLE SIZES

TEMPORARY STORMWATER BMPs MUST BE CONSTRUCTED ON SITE TO ADDRESS POTENTIAL RAINFALL SOIL PARTICLE SIZES RANGE FROM GRANULAR MATERIAL TO CLAY AND SHOULD BE CONSIDERED WHEN PROVIDING TEMPORARY STORMWATER BMPs FOR THIS SITE. A TEMPORARY WILL BE CONSTRUCTED IN THE NORTHERN PORTION OF THE SITE TO ADDRESS STORMWATER RUNOFF DURING CONSTRUCTION.

STORMWATER VOLUME REDUCTION REQUIREMENT

THE STATE RULES REQUIRE STORMWATER VOLUME REDUCTION EQUIVALENT TO 1.0-INCHES OF RUNOFF FROM THE IMPERVIOUS AREAS OF THE SITE. HOWEVER, THIS SITE IS PROHIBITED FROM INFILTRATION DUE TO THE NATIVE "D" SOILS.

CALCULATIONS FOR TEMPORARY SEDIMENT BASINS AND PERMANENT STORMWATER

TREATMENT SYSTEMS

THE CALCULATIONS FOR TEMPORARY AND PERMANENT STORMWATER TREATMENT SYSTEMS ARE INLCUDED IN THE PROJECT STORMWATER DRAINAGE REPORT

DESCRIPTION OF PERMANENT STORMWATER TREATMENT SYSTEMS

PERMANENT STORMWATER TREATMENT SYSTEMS ARE PROVIDED ON SITE INCLUDE THE CONSTRUCTION OF ONE (1) WET SEDIMENATION BASIN. THIS BASIN COLLECTS RUNOFF FROM THE DISTURBED AREAS OF THE SITE AND PROVIDES TREATMENT REQUIRED BY THE STATE CONSTRUCTION STORMWATER PERMIT

PRELIMINARY ESTIMATED QUANTITIES OF BMPs

ITEM	QUANTITY	UNIT
ROCK CONSTRUCTION EXIT/ENTRANCE	1	EACH
SILT FENCE	-	LF
HEAVY-DUTY SILT FENCE	1150	LF
SEDIMENT CONTROL LOG	150	LF
INLET PROTECTION	3	EACH
EROSION CONTROL BLANKET	400	SY
TEMPORARY SEED (SEED MIX 2X-XXX @ 300 LBS/ACRE) * SEE TABLE AT RIGHT	300	LBS
MULCH (MnDOT TYPE 1 @ 2 TONS/ACRE)	4	TONS
HYDRAULIC SOIL STABILIZER (MnDOT TYPE 6 @ 2,100 LBS/ACRE)	-	LBS

SITE IMPERVIOUS AREA CALCULATIONS

THE EXISTING SITE CONSISTS OF BUILDING, PAVING AND PLANTED AREAS.					
AREA	SQUARE FEET	ACRES			
TOTAL SITE AREA	-	53			
TOTAL DISTURBED AREA	-	1.5			
ADDED IMPERVIOUS AREA	-	0.56			

ANTICIPATED CONSTRUCTION SEQUENCING

COMPLETED BEFORE NEXT RAINFALL EVENT.

17. TOP DRESS TURF AREAS

19. STABILIZE SITE

CLEANED OF SEDIMENT AND DEBRIS.

HAS ESTABLISHED VEGETATION

18. REMOVE ACCUMULATED SEDIMENT FROM BMPs

21. REMOVE TEMPORARY EROSION & SEDIMENT CONTROLS

AFTER A MINIMUM 75% OF CONTRIBUTING PERVIOUS AREA

ACTIVITY IS COMPLETE AND TRIBUTARY SURFACES ARE

- 1. INSTALL STABILIZED CONSTRUCTION EXIT(S)
- 2. INSTALL SILT FENCE AND/OR SEDIMENT CONTROL LOGS 16. DURING CONSTRUCTION, STORMWATER MUST BE ROUTED AROUND INFILTRATION AREAS UNTIL ALL CONSTRUCTION 6 3. INSTALL INLET PROTECTION
- 4. REMOVE SHED
- STRIP TOPSOIL
- ROUGH GRADE SITE
- 10. CONSTRUCT STORM SEWER 11. PREPARE SUBGRADE FOR PLAYGROUND SURFACING AND 20. COMPLETE SITE CONSTRUCTION
- EQUIPMENT. 12. MAINTAIN ALL TEMPORARY EROSION & SEDIMENT
- CONTROLS
- 13. PREPARE SUBGRADESUB PAD FOR NEW CONSTRUCTION
- 14. COMPLETE SITE GRADING
- 15. INSTALLATION OF STORM WATER FILTRATION PRACTICES MUST BE DURING PERIODS OF DRY WEATHER AND

SPECIAL AND IMPAIRED RECEIVING WATERS

NAME OF WATER BODY	TYPE OF WATER BODY	SPECIAL WATER	IMPAIRED WATER
RILEY CREEK	RIVER	NO	YES
STARING LAKE	LAKE	[YES/NO]	[YES/NO]

RILEY CREEK

THIS RIVER SEGMENT HAS AN EPA-APPROVED IMPAIRMENT FOR: BENTHIC MACROINVERTEBRATES BIOASSESSMENTS; ESCHERICHIA COLI (E. COLI); FISH BIOASSESSMENTS; TURBIDITY.

THESE IMPAIRMENT(S) ARE CONSIDERED TO BE CONSTRUCTION RELATED PARAMETERS AND REQUIRE THE ADDITIONAL BEST MANAGEMENT PRACTICES (BMPS) FOUND IN ITEMS 23.9 AND 23.10 OF THE PERMIT IF THE PROJECT HAS A DISCHARGE POINT ON THE PROJECT WITHIN 1 MILE (AERIAL RADIUS MEASUREMENT) OF, AND FLOWS TO THE IMPAIRED STREAM.

23.9:

PERMITTEES MUST IMMEDIATELY INITIATE STABILIZATION OF EXPOSED SOIL AREAS, AS DESCRIBED IN ITEM 8.4, AND COMPLETE THE STABILIZATION WITHIN SEVEN (7) CALENDAR DAYS AFTER THE CONSTRUCTION ACTIVITY IN THAT PORTION OF THE SITE TEMPORARILY OR PERMANENTLY CEASES.

23.10:

STARING LAKE

PERMITTEES MUST PROVIDE A TEMPORARY SEDIMENT BASIN AS DESCRIBED IN SECTION 14 FOR COMMON DRAINAGE LOCATIONS THAT SERVE AN AREA WITH FIVE (5) OR MORE ACRES DISTURBED AT ONE TIME

ALSO, A MANDATORY STORMWATER POLLUTION PREVENTION PLAN (SWPPP) REVIEW IS REQUIRED BY THE MPCA IF THE PROJECT WILL DISTURB OVER 50 ACRES AND HAS A DISCHARGE POINT ON THE PROJECT WITHIN 1 MILE (AERIAL RADIUS MEASUREMENT) OF, AND FLOWS TO THE IMPAIRED WATER. OWNERS MUST SUBMIT THE APPLICATION FOR COVERAGE AND THE STORM WATER POLLUTION PREVENTION PLAN AT LEAST 30-DAYS BEFORE THE CONSTRUCTION START DATE. THE SWPPP CAN BE ATTACHED ELECTRONICALLY WHEN USING THE ONLINE APPLICATION.

THIS LAKE HAS AN EPA-APPROVED IMPAIRMENT FOR: MERCURY IN FISH TISSUE; NUTRIENTS.

THESE IMPAIRMENT(S) ARE CONSIDERED TO BE CONSTRUCTION RELATED PARAMETERS AND REQUIRE THE ADDITIONAL BEST MANAGEMENT PRACTICES (BMPS) FOUND IN ITEMS 23.9 AND 23.10 OF THE PERMIT IF THE PROJECT HAS A DISCHARGE POINT ON THE PROJECT WITHIN 1 MILE (AERIAL RADIUS MEASUREMENT) OF, AND FLOWS TO THE IMPAIRED WATER.

23.9:

PERMITTEES MUST IMMEDIATELY INITIATE STABILIZATION OF EXPOSED SOIL AREAS, AS DESCRIBED IN ITEM 8.4, AND COMPLETE THE STABILIZATION WITHIN SEVEN (7) CALENDAR DAYS AFTER THE CONSTRUCTION ACTIVITY IN THAT PORTION OF THE SITE TEMPORARILY OR PERMANENTLY CEASES. 23.10:

PERMITTEES MUST PROVIDE A TEMPORARY SEDIMENT BASIN AS DESCRIBED IN SECTION 14 FOR COMMON DRAINAGE LOCATIONS THAT SERVE AN AREA WITH FIVE (5) OR MORE ACRES DISTURBED AT ONE TIME.


ALSO, A MANDATORY STORMWATER POLLUTION PREVENTION PLAN (SWPPP) REVIEW IS REQUIRED BY THE MPCA IF THE PROJECT WILL DISTURB OVER 50 ACRES AND HAS A DISCHARGE POINT ON THE PROJECT WITHIN 1 MILE (AERIAL RADIUS MEASUREMENT) OF, AND FLOWS TO THE IMPAIRED WATER. OWNERS MUST SUBMIT THE APPLICATION FOR COVERAGE AND THE SWPPP AT LEAST 30-DAYS BEFORE THE CONSTRUCTION START DATE. THE SWPPP CAN BE ATTACHED ELECTRONICALLY WHEN USING THE ONLINE APPLICATION.

GENERAL SWPPP NOTES FOR CONSTRUCTION ACTIVITY

- 1. THE CONTRACTOR IS RESPONSIBLE TO COMPLY WITH ALL ASPECTS OF THE NPDES STORMWATER CONSTRUCTION PERMIT AT ALL TIMES UNTIL THE NOTICE OF TERMINATION HAS BEEN SUBMITTED TO THE MPCA. THE CONTRACTOR WILL DEVELOP A CHAIN OF COMMAND WITH ALL OPERATORS ON THE SITE TO ENSURE THAT THE SWPPP WILL BE IMPLEMENTED AND STAY IN EFFECT UNTIL THE CONSTRUCTION PROJECT IS COMPLETE, HAS UNDERGONE FINAL STABILIZATION AND A NOTICE OF TERMINATION (N.O.T.) HAS BEEN SUBMITTED TO THE MPCA.
- 2. THE CONTRACTOR MUST PREPARE WEEKLY AND EVENT-DRIVEN EROSION INSPECTION REPORTS AS NOTED IN THE PERMIT. THE REPORTS MUST BE WRITTEN AND FILED ON SITE.
- THE CONTRACTOR MUST COMPLY WITH THE REQUIREMENTS OF THE PERMIT REGARDING POLLUTION PREVENTION MANAGEMENT DURING CONSTRUCTION. WHICH INCLUDES BUT IS NOT LIMITED TO THE FOLLOWING:
- A. CONCRETE WASHOUT AREAS. THE LOCATION OF WASHOUT AREAS MUST BE IDENTIFIED BY SIGNS AND MUST UTILIZE A LEAK-PROOF CONTAINMENT FACILITY OR IMPERMEABLE LINER THAT PREVENTS RUNOFF FROM DISCHARGING ON TO ADJACENT SOILS. AN ENGINEERED COLLECTION SYSTEM MAY BE USED IF APPROVED BY THE PERMITTING AUTHORITY.
- B. SOLID WASTE COLLECTION AND REMOVAL
- C. SECONDARY CONTAINMENT
- D. SECURED HAZARDOUS WASTE STORAGE CONTAINERS
- CHEMICAL SPILL KITS
- F. PORTABLE RESTROOM FACILITIES THAT ARE ANCHORED TO PREVENT TIPPING

POLLUTION AND SPILL PREVENTION AND MANAGEMENT

- 1. CHEMICALS MUST BE KEPT IN A SECURE STORAGE AREA WHEN NOT IN USE. CHEMICAL STORAGE CONTAINERS MUST HAVE SECONDARY CONTAINMENT WHEN BEING USED OR STORED ON THE PROJECT SITE. CHEMICAL SPILLS OF ANY KIND (OIL, FUEL, FERTILIZER, ETC.) MUST BE CLEANED UP AND REMOVED FROM THE SITE IMMEDIATELY. THE CONTRACTOR MUST HAVE A SPILL KIT ON SITE AT ALL TIMES. THE FOLLOWING GOOD HOUSEKEEPING SPILL PREVENTION PRACTICES MUST BE FOLLOWED ONSITE THROUGH THE DURATION OF THE CONSTRUCTION PROJECT.
- A. AN EFFORT WILL BE MADE TO STORE ONLY ENOUGH MATERIAL ONSITE TO COMPLETE THE
- B. ALL MATERIALS STORED ONSITE MUST BE STORED IN A NEAT, ORDERLY MANNER IN THEIR APPROPRIATE CONTAINERS AND, IF POSSIBLE, UNDER A ROOF OR OTHER ENCLOSURE WITH SECONDARY CONTAINMENT.
- C. PRODUCTS MUST BE KEPT IN THEIR ORIGINAL CONTAINERS WITH THEIR ORIGINAL
- D. SUBSTANCES MUST NOT BE MIXED WITH ONE ANOTHER UNLESS RECOMMENDED BY THE **MANUFACTURER**
- THE ENTIRE PRODUCT MUST BE USED UP, WHENEVER POSSIBLE, BEFORE DISPOSING OF
- THE MANUFACTURER'S RECOMMENDATIONS FOR USE AND PROPER DISPOSAL MUST BE G. THE CONTRACTOR'S SUPERINTENDENT MUST INSPECT DAILY TO ENSURE PROPER USE
- AND DISPOSAL OF MATERIALS ONSITE. 5. THE FOLLOWING PRACTICES MUST BE USED TO REDUCE THE RISKS ASSOCIATED WITH HAZARDOUS MATERIALS STORED ONSITE:
- A. PRODUCTS MUST BE KEPT IN THEIR ORIGINAL CONTAINERS UNLESS THEY CANNOT BE
- ORIGINAL LABELS AND MATERIAL SAFETY DATA SHEETS MUST BE RETAINED ON SITE AND ACCESSIBLE AT ALL TIMES. C. THE MANUFACTURER'S RECOMMENDED METHODS FOR PROPER DISPOSAL OF SURPLUS
- PRODUCT MUST BE FOLLOWED. IN ADDITION TO THE GOOD HOUSEKEEPING AND MATERIAL MANAGEMENT PRACTICES DISCUSSED IN THE PREVIOUS SECTIONS OF THIS PLAN, THE FOLLOWING PRACTICES FOR SPILL PREVENTION AND CLEANUP MUST BE FOLLOWED.
- A. IF A SPILL OCCURS, OBSERVE THE MANUFACTURERS' SAFETY PRECAUTIONS ASSOCIATED WITH THE SPILLED MATERIAL. THE MANUFACTURERS' RECOMMENDED METHODS FOR SPILL CLEANUP MUST BE CLEARLY POSTED AND SITE PERSONNEL MUST BE MADE AWARE OF THE PROCEDURES AND LOCATIONS OF THE INFORMATION AND CLEANUP SUPPLIES.
- B. STOP THE SOURCE OF THE SPILL, IF POSSIBLE. CALL THE LOCAL FIRE AND/OR POLICE DEPARTMENTS IF FIRE OR PUBLIC SAFETY HAZARDS ARE CREATED. C. CONTAIN THE SPILLED MATERIAL. TOPSOIL, SAND OR ANY SEMI-IMPERMEABLE MATERIAL MAY BE USED TO CREATE A TEMPORARY CONTAINMENT STRUCTURE TO PREVENT THE
- SPILLED MATERIAL FROM FLOWING. D. SPILLS OF TOXIC OR HAZARDOUS MATERIALS MUST BE REPORTED TO THE APPROPRIATE STATE AND/OR LOCAL GOVERNMENT AGENCY, REGARDLESS OF THE SIZE OF DISCHARGE. IN ADDITION TO REPORTING TO LOCAL AUTHORITIES, REPORT THE SPILL TO THE MINNESOTA POLLUTION CONTROL AGENCY (MPCA) THROUGH THE STATE DUTY OFFICER.



- 24 HOUR TELEPHONE NUMBERS ARE: 651-649-5451 OR 800-422-0798
- E. CLEAN UP THE SPILLED MATERIAL IMMEDIATELY AFTER DISCOVERY AND DISPOSE OF THE WASTES PROPERLY. WITH THE EXCEPTION OF USED OIL, WASTES GENERATED FROM PETROLEUM SPILLS THAT HAVE BEEN REPORTED AND CLEANED UP IMMEDIATELY ARE EXEMPT FROM MINNESOTA'S HAZARDOUS WASTE RULES. WASTE GENERATED FROM USED OIL SPILLS MUST BE SENT TO A FACILITY FOR ENERGY RECOVERY
- THE SPILL AREA MUST BE KEPT WELL VENTILATED AND PERSONNEL MUST WEAR APPROPRIATE PROTECTIVE CLOTHING TO PREVENT INJURY FROM CONTACT WITH A SPILLS MUST BE STUDIED TO DETERMINE WHY THEY OCCURRED AND PREVENTATIVE
- IF CONTAMINATED SOILS ARE DISCOVERED DURING THE COURSE OF THE PROJECT, THE STATE DUTY OFFICER SHALL IMMEDIATELY BE CALLED, AT THE NUMBERS NOTED ABOVE, AND
- 8. TRASH AND CONSTRUCTION DEBRIS MUST BE DISPOSED OF PROPERLY. PROPER MEASURES SHALL BE TAKEN BY THE CONTRACTOR TO KEEP DEBRIS FROM SURFACE WATERS.

METHODS MUST BE IMPLEMENTED TO ENSURE SIMILAR SPILLS DO NOT OCCUR IN THE

EROSION PREVENTION PRACTICES

EMERGENCY CONTAINMENT ACTIONS SHALL BE TAKEN.

- ALL EXPOSED SOIL AREAS MUST BE TEMPORARILY OR PERMANENTLY STABILIZED NO MORE THAN 7 DAYS AFTER CONSTRUCTION ACTIVITY ON THAT PORTION OF THE SITE HAS TEMPORARILY OR PERMANENTLY CEASED. IN MANY INSTANCES THIS WILL REQUIRE STABILIZATION TO OCCUR MORE THAN ONCE DURING ROUGH GRADING. RAPID STABILIZATION METHOD 3, OR OTHER APPROVED METHOD MUST BE USED TO PROVIDE TEMPORARY COVER IN THESE AREAS AS APPROPRIATE.
- THE EROSION PREVENTION AND SEDIMENT CONTROL BMPS MUST BE INSTALLED AS NECESSARY TO MINIMIZE EROSION FROM DISTURBED SURFACES AND CAPTURE SEDIMENT ON SITE. ALL EROSION CONTROL MEASURES SHALL BE IN PLACE PRIOR TO THE COMMENCEMENT OF ANY REMOVAL WORK AND/OR GROUND DISTURBING ACTIVITIES AND SHALL BE MAINTAINED UNTIL THE POTENTIAL FOR EROSION HAS BEEN ELIMINATED.

SEDIMENT CONTROL PRACTICES

- SEDIMENT CONTROL DEVICES MUST BE ESTABLISHED ON ALL DOWN-GRADIENT PERIMETERS BEFORE ANY UP-GRADIENT LAND DISTURBING ACTIVITIES BEGIN. SEDIMENT CONTROL DEVICES INCLUDE, BUT ARE NOT LIMITED TO:
- A. PERIMETER CONTROL SHALL BE LOCATED ON THE CONTOUR TO CAPTURE OVERLAND LOW-VELOCITY SHEET FLOWS DOWN-GRADIENT OF ALL EXPOSED SOILS AND PRIOR TO DISCHARGING TO SURFACE WATERS.
- B. DITCH CHECKS MUST BE PLACED AS INDICATED ON THE PLANS DURING ALL PHASES OF
- C. SEDIMENT DAMAGE FROM STOCKPILES MUST BE MINIMIZED BY PLACING A ROW OF SILT FENCE A MAXIMUM OF 5-FEET FROM THE TOE OF THE SLOPE OF THE STOCKPILE. 2. STORM SEWER INLETS MUST BE PROTECTED AT ALL TIMES WITH THE APPROPRIATE INLET PROTECTION DEVICE FOR EACH SPECIFIC PHASE OF CONSTRUCTION. INLET PROTECTION DEVICES MAY NEED TO BE REPLACED MULTIPLE TIMES IN THE SAME LOCATION OVER THE LIFE OF THE PROJECT BUT WILL BE PAID FOR ONLY ONCE PER INLET LOCATION REGARDLESS OF THE NUMBER OF TIMES THE BMP IS REPLACED. AL STORM SEWER INLET PROTECTION DEVICES WILL BE KEPT IN GOOD FUNCTIONAL CONDITION AT ALL TIMES. IF THE PROJECT ENGINEER, CITY OR WATERSHED PERSONNEL DEEM AN INLET PROTECTION DEVICE TO BE NONFUNCTIONAL, IN POOR CONDITION, INEFFECTIVE, OR NOT APPROPRIATE FOR THE CURRENT CONSTRUCTION ACTIVITIES IT WILL BE REPLACED AT NO COST TO THE OWNER.
- THE CONTRACTOR MUST PLACE CONSTRUCTION EXITS, AS NECESSARY, TO PREVENT TRACKING OF SEDIMENT ONTO PAVED SURFACES AND IN COMPLIANCE WITH PART IV OF THE NPDES PERMIT. CONSTRUCTION EXITS MUST BE SUFFICIENTLY SIZED AND MAINTAINED TO PREVENT TRACK OUT.
- THE CONTRACTOR SHALL CLEAN ALL TRACKED MATERIALS ON ADJACENT ROADWAYS ON A DAILY BASIS, OR MORE OFTEN IF REQUIRED BY THE PROJECT ENGINEER, CITY AND/OR WATERSHED DISTRICT. PAVEMENT SHALL BE LIGHTLY WETTED PRIOR TO SWEEPING OR AS DIRECTED BY THE PROJECT ENGINEER.
- THE CONTRACTOR MUST USE METHODS AND OPERATIONAL PROCEDURES THAT PREVENT DISCHARGE OR PLACEMENT OF BITUMINOUS GRINDINGS, CUTTINGS, MILLINGS AND OTHER BITUMINOUS WASTES FROM AREAS OF EXISTING OR FUTURE VEGETATED SOILS, AND ALL WATER CONVEYANCE SYSTEMS, INCLUDING INLETS.
- 6. THE CONTRACTOR MUST USE METHODS AND OPERATIONAL PROCEDURES THAT PREVENT CONCRETE DUST, PARTICLES, SAW-CUT SLURRY, AND PLANT WASTE FROM ENTERING STORMWATER CONVEYANCE SYSTEMS, INCLUDING INLETS AND CURB FLOW LINES.
- 7. DITCHES AND EXPOSED SOILS MUST BE KEPT IN AN EVEN ROUGH GRADED CONDITION IN ORDER TO APPLY EROSION CONTROL MULCHES AND BLANKETS. OUTLETS INTO SURFACE WATERS SHALL BE STABILIZED WITH ENERGY DISSIPATION WITHIN 24
- HOURS OF BEING CONSTRUCTED 9. ALL EXPOSED SOIL AREAS MUST BE STABILIZED PRIOR TO THE ONSET OF WINTER, ANY WORK STILL BEING PERFORMED MUST BE SNOW MULCHED, SEEDED OR BLANKETED WITHIN THE
- TIME FRAMES IN THE NPDES PERMIT. 10. THE CONTRACTOR SHALL COMPLY WITH THE FOLLOWING INSPECTION AND MAINTENANCE REQUIREMENTS:
- A. SILT FENCE MUST BE REPAIRED, REPLACED OR SUPPLEMENTED WHEN IT BECOMES NON-FUNCTIONAL OR SEDIMENT REACHES 1/3 THE HEIGHT OF THE SILT FENCE. REPAIRS
- MUST BE MADE WITHIN 24 HOURS OF DISCOVERY B. INLET PROTECTION DEVICES SHOULD BE REPAIRED WHEN THEY BECOME
- NON-FUNCTIONAL OR SEDIMENT REACHES 1/3 THE HEIGHT OR DEPTH OF THE DEVICE. C. ALL OTHER NON-FUNCTIONAL BMPS MUST BE REPAIRED, REPLACED OR SUPPLEMENTED WITHIN 24 HOURS OF DISCOVERY.
- D. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING ALL BMPS UNTIL WORK HAS BEEN COMPLETED, THE SITE HAS UNDERGONE FINAL STABILIZATION AND A NOTICE OF TERMINATION (N.O.T.) HAS BEEN SUBMITTED TO THE MPCA IN ACCORDANCE WITH THE CONDITIONS OF THE NPDES PERMIT.

11. IF SEDIMENT DEPOSITS WITHIN WATERS OF THE STATE THE MATERIAL MUST BE REMOVED WITHIN 7 DAYS.

12. CONTRACTOR MUST OBTAIN LGU AND MnDNR APPROVALS AS REQUIRED

DEWATERING AND BASIN DRAINING

- DEWATERING MAY BE REQUIRED FOR THE CONSTRUCTION OF THIS PROJECT. IN ADDITION, DEWATERING OF TEMPORARY SEDIMENT BASINS WILL BE REQUIRED. THE CONTRACTOR SHALL SUBMIT A DEWATERING PLAN, FOR ANY TEMPORARY SEDIMENT BASINS AND UTILITY CONSTRUCTION, TO THE PROJECT ENGINEER FOR APPROVAL PRIOR TO COMMENCEMENT OF THESE ACTIVITIES. THE DEWATERING PLAN MUST INCLUDE BMP'S TO PREVENT SEDIMENT TRANSPORT, EROSION, AND ADVERSE IMPACTS TO DOWNSTREAM RECEIVING WATERS.
- 2. IT IS POSSIBLE THAT A PERMIT FOR TEMPORARY APPROPRIATION OF WATERS OF THE STATE NON-IRRIGATION FROM THE DNR WILL BE REQUIRED FOR THIS PROJECT. THE CONTRACTOR WILL BE RESPONSIBLE FOR OBTAINING THIS PERMIT. ALL TEMPORARY DEWATERING SHALL BE Drawn By TEAM DISCHARGED TO AN APPROVED LOCATION FOR TREATMENT PRIOR TO DISCHARGE TO THE RECEIVING WATER.
- 3. ALL STORM SEWER PIPE, MANHOLES AND CATCH BASINS MUST BE CLEANED OF ANY ACCUMULATED SEDIMENT UPON THE COMPLETION OF ALL LAND DISTURBING ACTIVITIES.

- ALL OWNERS MUST KEEP THE SWPPP, ALONG WITH THE FOLLOWING RECORDS, ON FILE FOR THREE (3) YEARS AFTER SUBMITTAL OF THE NOT (THIS DOES NOT INCLUDE RECORDS OF OTHER PERMITS FOR THE PROJECT AFTER SUBMITTAL OF THE NOT).
- 1.A. RECORDS OF ALL INSPECTIONS AND MAINTENANCE CONDUCTED DURING CONSTRUCTION 1.B. ALL PERMANENT OPERATION AND MAINTENANCE AGREEMENTS THAT HAVE BEEN
 - IMPLEMENTED, INCLUDING ALL: 1.B.A. RIGHT-OF-WAY, CONTRACTS, COVENANTS AND OTHER BINDING REQUIREMENTS REGARDING PERPETUAL MAINTENANCE
- 1.B.B. ALL REQUIRED CALCULATIONS FOR DESIGN OF THE TEMPORARY AND PERMANENT STORMWATER MANAGEMENT SYSTEM.
- 2. THE PERMITTEE(S) MUST IMPLEMENT THE ENTIRE SWPPP AND THE REQUIREMENTS OF THE NPDES PERMIT (PART IV A) THE BMP's IDENTIFIED IN THE SWPPP AND IN THIS PERMIT MUST BI SELECTED, INSTALLED AND MAINTAINED IN AN APPROPRIATE AND FUNCTIONAL MANNER THAT IS IN ACCORDANCE WITH RELEVANT MANUFACTURER SPECIFICATIONS AND ACCEPTED ENGINEERING PRACTICES.

BUFFER ZONES AND AREAS NOT TO BE DISTURBED

- NATURAL BUFFER ZONES (50') ARE NOT REQUIRED ADJACENT TO ROAD DITCHES, JUDICIAL DITCHES, COUNTY DITCHES, STORMWATER CONVEYANCE CHANNELS, STORM DRAIN INLETS. AND SEDIMENT BASINS AND THEREFORE NOT APPLICABLE TO THIS PROJECT. PERMANENT BUFFER ZONES (100') ARE REQUIRED ADJACENT TO SPECIAL WATERS. THIS SITE
- IS NOT LOCATED WITHIN 100 FEET OF A SPECIAL WATER AND THEREFORE PERMANENT BUFFER ZONES NOT APPLICABLE TO THIS PROJECT.
- DELINEATE THE LOCATION OF ALL AREAS NOT TO BE DISTURBED BEFORE CONSTRUCTION BEGINS. GRADING AND CONSTRUCTION LIMITS ARE SHOWN ON THE PLANS. SEE SHEET C101 & C102 FOR CONSTRUCTION AND GRADING LIMITS

PERMITTING, INSPECTION & MAINTENANCE FOR STORM WATER FACILITIES: CITY OF EDEN PRAIRIE AND RILEY-PURGATORY-BLUFF CREEK WATERSHED DISTRICT (WWW.RPBCWD.ORG) STORM WATER MANAGEMENT PERMITS ARE REQUIRED FOR THIS

- PREPARE, EXECUTE AND RECORD THE "INSPECTION AND MAINTENANCE AGREEMENT FOR PRIVATE STORMWATER FACILITIES." STANDARD EROSION CONTROL NOTES FOR RPBCWD DEVELOPMENT REVIEWS
- C1. THE EROSION CONTROL PLAN MUST INCLUDE THE FOLLOWING NOTES: a. NATURAL TOPOGRAPHY AND SOIL CONDITIONS MUST BE PROTECTED, INCLUDING RETENTION ONSITE OF NATIVE TOPSOIL TO THE GREATEST EXTENT POSSIBLE.
- b. ADDITIONAL MEASURES, SUCH AS HYDRAULIC MULCHING AND OTHER PRACTICES AS SPECIFIED BY THE DISTRICT MUST BE USED ON SLOPES OF 3:1 (H:V) OR STEEPER TO PROVIDE ADEQUATE c. FINAL SITE STABILIZATION MEASURES MUST SPECIFY THAT AT LEAST SIX INCHES OF TOPSOIL OR
- ORGANIC MATTER BE SPREAD AND INCORPORATED INTO THE UNDERLYING SOIL DURING FINAL SITE TREATMENT WHEREVER TOPSOIL HAS BEEN REMOVED. d. CONSTRUCTION SITE WASTE SUCH AS DISCARDED BUILDING MATERIALS, CONCRETE TRUCK
- WASHOUT, CHEMICALS, LITTER AND SANITARY WASTE MUST BE PROPERLY MANAGED. e. ALL TEMPORARY EROSION AND SEDIMENT CONTROL BMPS MUST BE MAINTAINED UNTIL COMPLETION OF CONSTRUCTION AND VEGETATION IS ESTABLISHED SUFFICIENTLY TO ENSURE
- STABILITY OF THE SITE, AS DETERMINED BY THE DISTRICT. f. ALL TEMPORARY EROSION AND SEDIMENT CONTROL BMPS MUST BE REMOVED UPON FINAL STABILIZATION.
- g. SOIL SURFACES COMPACTED DURING CONSTRUCTION AND REMAINING PERVIOUS UPON COMPLETION OF CONSTRUCTION MUST BE DECOMPACTED TO ACHIEVE A SOIL COMPACTION TESTING PRESSURE OF LESS THAN 1,400 KILOPASCALS OR 200 POUNDS PER SQUARE INCH IN THE UPPER 12 INCHES OF THE SOIL PROFILE WHILE TAKING CARE TO PROTECT UTILITIES, TREE ROOTS, AND OTHER EXISTING VEGETATION.
- h. ALL DISTURBED AREAS MUST BE STABILIZED WITHIN 7 CALENDAR DAYS AFTER LAND-DISTURBING WORK HAS TEMPORARILY OR PERMANENTLY CEASED ON A PROPERTY THAT DRAINS TO AN IMPAIRED WATER, WITHIN 14 DAYS ELSEWHERE.
- i. THE PERMITTEE MUST. AT A MINIMUM. INSPECT. MAINTAIN AND REPAIR ALL DISTURBED SURFACES AND ALL EROSION AND SEDIMENT CONTROL FACILITIES AND SOIL STABILIZATION MEASURES EVERY DAY WORK IS PERFORMED ON THE SITE AND AT LEAST WEEKLY UNTIL LAND-DISTURBING ACTIVITY HAS CEASED. THEREAFTER, THE PERMITTEE MUST PERFORM THESE RESPONSIBILITIES AT LEAST WEEKLY UNTIL VEGETATIVE COVER IS ESTABLISHED. THE PERMITTEE WILL MAINTAIN A LOG OF ACTIVITIES UNDER THIS SECTION FOR INSPECTION BY THE DISTRICT ON REQUEST.



Grace Church Eden Prairie 9301 Eden Prairie Rd. Eden Prairie, MN 55347 (952) 224-3000

/isioneering Studios Architecture

Santa Ana, CA 92701

(612) 758-4000



Sunde Land Surveying, LLC 9001 East Bloomington Freeway STE 118 Bloomington, MN 55420 (952) 886-3118

DESIGN TEAM Checked By CHECKER

NO. DATE | COMMENT

2023-12-26 RILEY PURGATORY BLUFF CREEK WATERSHED DISTRICT


10/13/2023 **PROJECT**


hool TI MWATE ENTION

S O E R


C


Sheet No.







11 FILTER BERM-TYPE 3 (ROCK WEEPER)






10 FILTER BERM-TYPE 1 (COMPOST), TYPE 2 (SLASH MULCH), OR TYPE 4 (TOPSOIL)






9 INLET PROTECTION - ROCK FILTER BERM W/SILT FENCE USE WHERE INLET DRAINS AN AREA WITH SLOPES 1:3 OR LESS



THE SEDIMENT CONTROL BARRIER SHALL BE A METAL OR PLASTIC/POLYETHYLENE RISER SIZED TO FIT INSIDE THE CATCH BASIN/MANHOLE: HAVE PERFORATIONS TO ALLOW FOR WATER INFILTRATION: HAVE AN OVERFLOW OPENING FLANGES AND A LID/COVER.

8 INLET PROTECTION - SEDIMENT CONTROL INLET HAT



- 1. ALL GEOTEXTILE USED FOR INLET PROTECTION TO BE MONAFILAMENT IN **BOTH DIRECTIONS**
- (2.) FINISHED SIZE INCLUDING POCKETS WHERE REQUIRED SHALL EXTEND A MINIMUM OF 10 INCHES AROUND PERIMETER TO FACILITATE MAINTENANCE AND REMOVAL
- (3.) DO NOT PLACE FILTER BAG INSERT IN INLETS SHALLOWER THAN 30 INCHES, MEASURED FROM THE BOTTOM OF THE INLET TO THE TOP OF THE GRATE. THE PLACED BAG SHALL HAVE A MINIMUM SIDE CLEARANCE OF 3 INCHES BETWEEN THE INLET WALLS AND THE BAG, MEASURED AT THE BOTTOM OF THE OVERFLOW HOLES. WHERE NECESSARY THE CONTRACTOR SHALL CLINCH THE BAG, USING PLASTIC ZIP TIES, TO ACHIEVE THE 3 INCH SIDE CLEARANCE.
- (4.) FLAP POCKETS SHALL BE LARGE ENOUGH TO ACCEPT WOOD 2" x 4", OR USE A ROCK SOCK OR SAND BAGS IN PLACE OF FLAP POCKETS


CAN BE INSTALLED IN ANY INLET TYPE WITH OR WITHOUT A CURB BOX 7 INLET PROTECTION - FILTER BAG INSERT

1" x 2"x 24" LONG WOODEN STAKES. STAKES SHALL BE DRIVEN THROUGH THE BACK HALF OF THE SEDIMENT CONTROL LOG AT AN ANGLE OF 45 DEGREES WITH THE TOP OF THE STAKE POINTING UPSTREAM. SEDIMENT CONTROL LOG ~ 8" TO 10" EMBEDMENT DEPTH PLACE STAKES AS NEEDED TO PREVENT MOVEMENT OF SEDIMENT CONTROL LOGS ON SLOPES, OR AS NEEDED DUE TO OTHER FACTORS (STAKES ARE INCIDENTAL TO INSTALLATION).

TYPES: WOOD CHIP, COMPOST, OR ROCK 1" x 2"x 24" LONG WOODEN STAKES. STAKES SHALL BE DRIVEN THROUGH THE BACK HALF OF THE SEDIMENT SEDIMENT CONTROL LOG CONTROL LOG AT AN ANGLE OF 45 DEGREES WITH THE TOP OF THE STAKE POINTING UPSTREAM. BACKFILL AND COMPACT SOIL FROM TRENCH ON UP GRADIENT SIDE OF SEDIMENT CONTROL LOG PLACE SEDIMENT CONTROL LOG IN 8" TO 10" EMBEDMENT DEPTH SHALLOW TRENCH (1" TO 2" DEPTH) SPACE BETWEEN STAKES SHALL BE MAXIMUM 1 FOOT FOR DITCH CHECKS,


AND 2 FEET FOR OTHER APPLICATIONS TYPES: STRAW, WOOD FIBER, OR COIR

SEDIMENT CONTROL LOGS




SILT FENCE TYPE PA (PREASSEMBLED)


FOR SHEET FLOW WITH MAXIMUM CONTRIBUTING AREA = 0.25 ACRES



SILT FENCE TYPE MS (MACHINE SLICED) FOR SHEET FLOW WITH MAXIMUM CONTRIBUTING AREA = 1 ACRE



OPTIONAL METHOD



3 SILT FENCE-TYPE HI (HAND INSTALLED) FOR SHEET FLOW WITH MAXIMUM CONTRIBUTING AREA = 1 ACRE

— TAPER EDGES GEOTEXTILE FABRIC AT 1:1 COMPACTED SOIL — 6" MIN. DEPTH OF 1" TO 2" CRUSHED ROCK OR SLASH MULCH PUBLIC ROAD 10 FT MIN. REQUIRED **RUMBLE PAD** SEDIMENT 4 SURFACE FLOW 10 FT MIN. SLASH MULCH CRUSHED ROCK, SHEET PAD, OR OTHER PER **ENTRANCE WIDTH** SPECIFICATION. AS REQUIRED 24' MINIMUM


CORRUGATED STEEL PANELS

- CROSS SLOPE 3% OR FLATTER


CONSTRUCTION EXIT (RUMBLE PAD TYPE) 5 7

NOTES FOR DETAILS 1 & 2

- MINIMUM LENGTH IS 50 FEET OR A LENGTH SUFFICIENT TO ALLOW A MINIMUM OF 5 TIRE ROTATIONS ON THE PROVIDED PAD. MINIMUM LENGTH SHALL BE CALCULATED USING THE LARGEST TIRE WHICH WILL BE USED IN TYPICAL OPERATIONS.
- PROVIDE RADIUS OR WIDEN PAD SUFFICIENTLY TO PREVENT VEHICLE TIRES FROM TRACKING OFF OF PAD WHEN LEAVING SITE.
- (3.) IF RUNOFF FROM DISTURBED AREAS FLOWS TOWARD CONSTRUCTION EXIT, PREVENT RUNOFF FROM DRAINING DIRECTLY TO PUBLIC ROAD OVER CONSTRUCTION EXIT BY CROWNING THE EXIT OR SLOPING TO ONE SIDE. IF SURFACE GRADING IS INSUFFICIENT. PROVIDE OTHER MEANS OF INTERCEPTING
- (4.) IF RUNOFF FROM CONSTRUCTION EXIT WILL DRAIN OFF OF PROJECT SITE, PROVIDE SEDIMENT TRAP WITH STABILIZED OVERFLOW.
- (5.) IF A TIRE WASH OFF IS REQUIRED THE CONSTRUCTION EXIT SHALL BE GRADED TO DRAIN THE WASH WATER TO A SEDIMENT TRAP.
- (6.) MINIMUM LENGTH OF RUMBLE PAD IS 20 FEET, OR AS REQUIRED TO REMOVE SEDIMENT FROM TIRES. IF SIGNIFICANT SEDIMENT IS TRACKED FROM THE SITE. THE RUMBLE PAD SHALL BE LENGTHENED OR THE DESIGN MODIFIED TO PROVIDE ADDITIONAL VIBRATION. WASH-OFF LENGTH SHALL BE AS REQUIRED TO
- EFFECTIVELY REMOVE CONSTRUCTION SEDIMENT FROM VEHICLE TIRES. MAINTENANCE OF CONSTRUCTION EXITS SHALL OCCUR WHEN THE EFFECTIVENESS OF SEDIMENT REMOVAL HAS BEEN REDUCED. MAINTENANCE SHALL CONSIST OF REMOVING SEDIMENT AND CLEANING THE MATERIALS OR PLACING ADDITIONAL MATERIAL (SLASH MULCH OR CRUSHED ROCK) OVER SEDIMENT FILLED MATERIAL TO RESTORE EFFECTIVENESS.



CRUSHED ROCK OR GEOTEXTILE FABRIC SLASH MULCH TAPER EDGES AT 1:1 /& 8°°%, °C6" MIN'S 0°%, &, &) - INPLACE GROUND SLASH MULCH OR CRUSHED ROCK



CONSTRUCTION EXIT 57 (SLASH MULCH, CRUSHED ROCK OR SHEET PAD)

DESIGN TEAM Drawn By TEAM Checked By CHECKER **REVISIONS** NO. DATE | COMMENT 2023-12-26 RILEY PURGATORY BLUFF CREEK WATERSHED DISTRICT

Grace Church Eden Prairie

9301 Eden Prairie Rd.

Eden Prairie, MN 55347

(952) 224-3000

Visioneering Studios Architecture

106 W. 4th Street, Suite 600

Santa Ana, CA 92701 (888) 539-1957

Hammel, Green and Abrahamson

420 North 5th Street Minneapolis, MN 55401

(612) 758-4000

Sunde Land Surveying, LLC

STE 118

(952) 886-3118

Bloomington, MN 55420

9001 East Bloomington Freeway

52

rairie

3

C


10/13/2023


PROJECT CODE


22641


SiO <u>r</u>

C









I HEREBY CERTIFY THAT THIS PLAN. SPECIFICATION OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA

NAME: KENNETH W. HORNS REGISTRATION NUMBER: 18235

Consultant: Civil Engineering

420 North 5th Street, Suite 100 Minneapolis, Minnesota 55401 Telephone 612.758.4000

REVISIONS/SUBMITTALS NO. DATE | COMMENT

1 01-11-2024 BLDG DEPT SUBMITTAL

ORMW


DESIGN TEAM Designed By Drawn By Checked By


01/11/2024 **Project Status**


CONSTRUCTION DOCUMENTS

23668

Sheet No.







NOTES:

- 1. EXISTING TOPSOIL TO BE SALVAGED AND STOCKPILED FOR USE AS PLANTING SOIL.
- 2. ALL PLANTINGS TO BE PERMANENTLY IRRIGATED. REPAIR, REPLACE AND MODIFY EXISTING SYSTEM TO THE NEEDS OF THE PROJECT.
- 3. PLANT LIST QUANTITIES ARE FOR THE CONVENIENCE OF THE CONTRACTOR. THE CONTRACTOR IS RESPONSIBLE FOR PLANTING ALL PLANTS AS THEY APPEAR ON THE PLANS. SHOULD THERE BE A DISCREPANCY BETWEEN THE LIST AND THE PLANS, THE PLANS TAKE PRECEDENCE.
- 4. FINAL LOCATION OF ALL PLANT MATERIALS SHALL BE SUBJECT TO THE APPROVAL OF THE LANDSCAPE ARCHITECT.
- 5. THE LANDSCAPE ARCHITECT RESERVE THE RIGHT TO REFUSE ANY PLANT MATERIALS DEEMED UNACCEPTABLE.
- 6. MULCH, WHERE DESIGNATED ON THE PLANS, SHALL EXTEND UNDER ALL SHRUBS AND GROUNDCOVER TO THE DEPTH SPECIFIED.
- 7. ALL WEEDS AND UNWANTED GRASSES SHALL BE TREATED WITH CONTACT HERBICIDE AS PER MANUFACTURER'S INSTRUCTIONS. REAPPLY AS NECESSARY DURING THE CONSTRUCTION AND MAINTENANCE PERIODS TO COMPLETELY KILL WEEDS. REMOVE ALL DEAD DEBRIS.
- 8. FINISH GRADE OF ALL PLANTING BEDS AND LAWN AREAS TO BE ONE
- HALF INCH $(\frac{1}{2}")$ BELOW ADJACENT PAVING. 9. PLANTS SHALL BE LOCATED A MINIMUM OF THREE (3) FEET FROM ANY FIRE HYDRANT, TRANSFORMER, LIGHT FIXTURE OR SIMILAR OBJECT.
- 10. STAKE TREES AS REQUIRED AND INDICATED ON THE PLANS AND IN THE DETAILS.
- 11. REPAIR ANY DAMAGED TURF WITH TURF SEED, TURF TYPE: TALL FESCUE BLEND, RESILIENCE BY TWIN CITY SEED @ 10LBS/1,000 SF, OR APPROVED EQUAL. ALL SEED TO HAVE EROSION CONTROL BLANKET.
- 12. TREES PLANTED IN TURF TO HAVE A THREE (3) FOOT RADIUS MULCH RING, 4" DEPTH WITH MULCH PULLED AWAY FROM TRUNK AND A SPADED EDGE BETWEEN MULCH AND TURF.

KEY NOTES:

- PLANTING AREA; 4" DEPTH MULCH OVER 12" DEPTH 1 PLANTING SOIL, REFER TO PLANT MATERIAL SCHEDULE ON L-4
- 2 STEEL EDGING; BLACK STEEL, $\frac{3}{16}$ " x 4"
- 3 STONE MAINTENANCE SURFACE; 6" DEPTH OVER GEOTEXTILE
- 4 REPAIR ANY DISTURBED EXTENTS NOT IDENTIFIED WITH TURF SEED, REFER TO NOTES TURF GRASS, SOD; TURF TYPE TALL FESCUE BLEND, OR APPROVED EQUAL.

LEGEND:

DECIDUOUS TREE; REFER TO PLANT MATERIAL SCHEDULE ON L-4

DECIDUOUS SHRUB;

REFER TO PLANT MATERIAL SCHEDULE ON L-4 CONIFEROUS SHRUB; REFER TO PLANT MATERIAL SCHEDULE ON L-4

PERENNIAL OR ORNAMENTAL GRASS; REFER TO PLANT MATERIAL SCHEDULE ON L-4

TURF GRASS, SOD; TURF TYPE TALL FESCUE BLEND, OR APPROVED EQUAL.

TURF GRASS, SEED; TURF TYPE TALL FESCUE BLEND, RESILIENCE BY TWIN CITY SEED @ 10 LBS/1,000 SF, OR APPROVED EQUAL. (ALL SEED TO HAVE EROSION CONTROL BLANKET)

---- STEEL EDGING; BLACK STEEL, $\frac{3}{16}$ " x 4"

urc U

Grace Church Eden Prairie 9301 Eden Prairie Rd. Eden Prairie, MN 55347 (952) 224-3000

Visioneering Studios Architecture 106 W. 4th Street, Suite 600 Santa Ana, CA 92701 (888) 539-1957

¬ Hammel, Green and Abrahamson,

420 North 5th Street Minneapolis, MN 55401 (612) 758-4000

Sunde Land Surveying, LLC

STE 118 Bloomington, MN 55420 (952) 886-3118

SUNDE 9001 East Bloomington Freeway -

DESIGN TEAM

REVISIONS

2023-12-14 RESPONSES TO EDEN PRAIRIE COMMENTS

10/13/2023

PROJECT

22641

Drawn By TEAM

Checked By CHECKER

NO. DATE | COMMENT

Architect