

18681 Lake Drive East
Chanhassen, MN 55317
952-607-6512
www.rpbcwd.org

Riley Purgatory Bluff Creek Watershed District Permit Application Review

Permit No: 2021-063

Considered at Board of Managers Meeting: April 6, 2022

Received complete: October 25, 2021 (RPBCWD extended the application-review period by 60 days on December 14, 2021 and the RPBCWD approved the applicant's request for a second extension until April 23, 2022)

Applicant: Kraus-Anderson Realty Company

Consultant: ISG Inc., Jeremy Foss P.E.

Project: Reserve at Autumn Woods – The applicant proposes the construction of a new single-family residential subdivision project, underground utilities, associated roadways, landscaping, and stormwater management facilities. Stormwater management facilities include surface water detention basins, infiltration basins, and a vegetated swale to provide volume control, water quality, and rate control.

Location: Southwest Corner of Autumn Woods Drive and Audubon Road, Chaska, MN

Reviewer: Dallen Webster E.I.T. and Scott Sobiech P.E., Barr Engineering

Potential Board Variance Action

Manager _____ moved and Manager _____ seconded adoption of the following resolution based on the permit report that follows, the presentation of the matter at the April 6, 2022, meeting of the managers and the managers' findings, as well as the factual findings in the permit report that follows:

Resolved that the variance request for Permit 2021-063 from compliance with Rule B, subsection 3.2b is approved, based on the facts and analysis provided by the RPBCWD engineer below and placed in the record at the April 6, 2022 meeting of the managers, and the managers' findings in the record of the April 6 meeting, and subject to the following conditions: 1. [CONDITION(S)],

Potential Board Exception Action

Manager _____ moved and Manager _____ seconded adoption of the following resolution based on the permit report that follows, the presentation of the matter at the April 6, 2022, meeting of the managers and the managers' findings, as well as the factual findings in the permit report that follows:

Resolved that the exception request from compliance with Rule G, subsection 3.2, for Permit 2021 063 is approved based on the facts and analysis provided by the RPBCWD engineer below and placed in the record at the April 6, 2022 meeting of the managers, and the managers' findings in the record of the April 6 meeting, and subject to the following conditions: 1. [CONDITION(S)],

Proposed Board Action

Manager _____ moved and Manager _____ seconded adoption of the following resolutions based on the permit report that follows and the presentation of the matter at the April 6, 2022 meeting of the managers:

Resolved that the application for Permit 2021-063 is approved, subject to the conditions and stipulations set forth in the Recommendations section of the attached report.

Resolved that on determination by the RPBCWD administrator that the conditions of approval have been affirmatively resolved, the RPBCWD president or administrator is authorized and directed to sign and deliver Permit 2021-063 to the applicant on behalf of RPBCWD.

Upon roll call vote, the resolutions were adopted, _____.

Applicable Rule Conformance Summary

Rule	Issue	Conforms to RPBCWD Rules?	Comments	
B	Floodplain Management and Drainage Alterations	No	See Rule K Variance discussion for compensatory storage not being provided within the floodplain of the same waterbody.	
C	Erosion Control Plan	See Comment	See rule-specific permit condition C1 related to name of individual responsible for on-site erosion control.	
D	Wetland and Creek Buffers	See Comment	See rule-specific permit condition D1 related to recordation of buffer maintenance declaration.	
G	Waterbody Crossings and Structures	No	See Rule K Exception discussion for the construction of a waterbody crossing in contact with the bed and bank of drainageway leaving Wetland D and rule-specific permit condition G1 related to recordation of a waterbody crossing maintenance declaration.	
J	Stormwater Management	Rate	Yes	
		Volume	Yes	
		Water Quality	Yes	
		Low Floor Elev.	Yes	
		Maintenance	See Comment	See rule-specific permit condition J1 related to recordation of stormwater facility maintenance declaration.
		Chloride Management	See Comment	See stipulation #5 related to providing a chloride management plan prior to project close-out.
		Wetland Protection	Yes	

Rule	Issue	Conforms to RPBCWD Rules?	Comments
K	Variance Request	See Comment	See exception discussion for the construction of a waterbody crossing in contact with the bed and bank of drainageway leaving Wetland D and variance discussion for compensatory storage not being provided within the floodplain of the same waterbody.
L	Permit Fee Deposit	See Comment	\$3,000 received July 27, 2021. The applicant must replenish the permit fee deposit to the original amount due before the permit will be issued and provide the addition \$2,000 fee deposit for the variance request.
M	Financial Assurances	See Comment	The financial assurance is calculated at \$876,352.

Background

The applicant proposes construction of an 86-lot single-family residential development on approximately 45 acres southeast of Hazeltine Lake. The project site is located between the intersections of Audubon Road and Autumn Woods Drive and Audubon Road and Butternut Drive at 9430 Audubon Road in Chaska, Minnesota. The existing site is currently a homestead with most of the area farmed. There are 5 wetlands onsite, three of which will be filled and replaced under a Wetland Conservation Act replacement plan approved by the city of Chaska, acting as the local governmental unit administering WCA. A large wetland at the north end of the site will be preserved and receives a majority of stormwater runoff from the northern portion of the site. Wetland D, a farmed wetland at the south end of the site, receives stormwater runoff from the southern portion of the site. Flows leaving this wetland are conveyed to a chain of stormwater ponds by a natural channel. The applicant is proposing a waterbody crossing on the natural channel from Wetland D to restore the wetland hydrology and off-set some of the lost wetland functions and values on-site due to filling of three other wetlands. The site will be mass graded prior to construction of public improvements for urban development, including utilities, streets, storm sewer and five stormwater best management practices. Proposed stormwater management facilities include stormwater detention basins, infiltration basins, and a vegetated swale to provide volume control, water quality, and rate control.

The following water resources are within the project site or downgradient of the proposed activities. The following table provides a brief explanation of how each resource is implicated by the project.

Water resources implicated by project

Water Resource	Potential resource impacts
Wetland A	Wetland is preserved; downgradient from proposed land-disturbing activities
Wetland B	A farmed wetland that will be filled during construction and the floodplain will be filled
Wetland C	A farmed wetland that will be filled during construction and the floodplain will be filled
Wetland D	A farmed wetland will be expanded and restored during construction and is downgradient from proposed land-disturbing activities
Wetland E	A farmed wetland that will be filled during construction and the floodplain will be filled
Watercourse connecting Wetland E to D	An eroded, non-public watercourse conveying flows from Wetland E to Wetland D that will be filled
Southern Watercourse	A waterbody crossing is proposed to aid in the restoration of Wetland D.

The project site information is summarized below:

Project Site Information	Area (acres)
Total Site Area	45.43
Existing Site Impervious	0.61
Disturbed Existing Impervious Area	0.61 (100% disturbance)
Proposed Site Impervious Area	12.08
Change in Impervious Area	11.47 (>100% increase)
Regulated Impervious Area	12.08
Total Disturbed Area	36.79

The following materials were reviewed in support of the permit request:

1. Permit Application received July 22, 2021 (Notified applicant on August 9, 2021 that submittal was incomplete); materials submitted to complete the application October 25, 2021.
2. Stormwater Management Report dated July 2, 2021 (revised October 1, 2021; October 22, 2021; January 3, 2022; February 4, 2022; and March 17, 2022)
3. Project Plan Set (39 sheets) dated July 6, 2021 (revised with 47 sheets October 1, 2021; 47 sheets October 25, 2021; 77 sheets January 4, 2022; 77 sheets on February 10, 2022; and 77 sheets on March 17, 2022)
4. Electronic HydroCAD models received on October 1, 2021 (revised October 25, 2021; January 4, 2022; and February 10, 2022)

5. Electronic p8 models received on October 1, 2021 (revised October 25, 2021 and February 10, 2022)
6. Electronic MIDS models received on October 25, 2021 (revised February 10, 2022)
7. Soil Boring Log by Braun Intertec Corporation dated May 21, 2021
8. Double Ring Infiltrometer Testing Results by Braun Intertec Corporation dated June 30, 2021
9. Wetland Delineation Report by ISG Inc dated June 23, 2021
10. Liberty On Bluff Creek Storm Sewer Record Drawing received October 1, 2021
11. Engineer's Opinion of Probable Construction Costs dated October 22, 2021 (revised March 17, 2022)
12. Draft Maintenance Agreement received on October 25, 2021
13. MnRAM Site Response Report for Wetland A received on October 25, 2021
14. MnRAM Site Response Report for Wetland B received on October 25, 2021
15. MnRAM Site Response Report for Wetland C received on October 25, 2021
16. MnRAM Site Response Report for Wetland D received on October 25, 2021
17. MnRAM Site Response Report for Wetland E received on October 25, 2021
18. Wetland Delineation Overview Map received on October 25, 2021
19. Draft Minnesota Wetland Conservation Act Application received October 25, 2021 (revised February 10, 2022)
20. Minnesota Wetland Conservation Act Notice of Decision dated March 7, 2022
21. Variance Request Letter dated October 26, 2021 (revised January 3, 2022)
22. Wetland storage computations received October 29, 2021
23. Section 6 of City of Chaska's Surface Water Management Plan received February 10, 2022
24. Wetland Replacement Plan Memo by Stantec dated December 1, 2021
25. Applicant's response to RPBCWD August 9, 2021 comments received October 1, 2021
26. Applicant's response to RPBCWD October 8, 2021 comments received October 25, 2021
27. Applicant's response to RPBCWD November 8, 2021 comments received January 4, 2022
28. Applicant's response to RPBCWD January 17, 2022 comments received February 10, 2022
29. Applicant's response to RPBCWD March 2, 2022 comments received March 18, 2022

Rule B: Floodplain management and drainage alteration

Because the proposed redevelopment project involves the placement of a total of 1.13 acre-feet of fill below the 100-year flood elevation of Wetlands B, C, D, and E and existing southern watercourse, the project activities must conform to the RPBCWD's Floodplain Management and Drainage Alterations rule (Rule B). No fill or land-disturbing activities are proposed in floodplain of Wetland A.

The proposed new structures must conform with low floor elevation requirements set forth by Rule B, Subsection 3.1 which references the low floor criteria in Rule J, subsection 3.6. All new buildings must be constructed such that the lowest floor is at least two feet above the 100-year high-water elevation or

one foot above the natural overflow of a waterbody according to Rule J, Subsection 3.6a. In addition, each of the planned stormwater-management facilities must be constructed at an elevation that ensures that no adjacent habitable building will be brought into noncompliance with this requirement according to Rule J, Subsection 3.6b. Low floor requirements were evaluated for 36 proposed structures adjacent to the 100-year floodplain extents. The results demonstrate the provided freeboard is greater than the minimum required.

Structure (Block – Lot)	Low Floor Elevation of Building (ft)	Waterbody	100-year Event Flood Elevation of Waterbody (ft)	Freeboard to 100-year Event (ft)
3 - 13	937.4	Wetland D	932.53	4.87
3 - 14	937.4	Wetland D	932.53	4.87
3 - 15	937.4	Wetland D	932.53	4.87
3 - 16	937.4	Wetland D	932.53	4.87
3 - 17	937.05	Wetland D	932.53	4.52
3 - 18	937.05	Wetland D	932.53	4.52
3 - 19	937.3	Wetland D	932.53	4.77
3 - 20	937.3	Basin C	933.49	3.81
3 - 21	936.3	Basin C	933.49	2.81
3 - 22	936.3	Basin C	933.49	2.81
3 - 23	936.05	Basin C	933.49	2.56
3 - 24	937.05	Basin C	933.49	3.56
3 - 25	935.8	Basin C	933.49	2.31
4 - 1	946.05	Basin F	939.96	6.09
4 - 2	945.55	Basin F	939.96	5.59
4 - 3	946.05	Basin F	939.96	6.09
4 - 4	946.8	Basin F	939.96	6.84
4 - 5	948.8	Basin F	939.96	8.84
4 - 6	950.05	Basin F	939.96	10.09
4 - 7	950.3	Basin F	939.96	10.34
4 - 8	949.45	Basin F	939.96	9.49
4 - 9	946.8	Basin F	939.96	6.84
4 - 10	943.8	Basin F	939.96	3.84
4 - 15	942.3	Basin F	939.96	2.34
4 - 16	942.3	Basin F	939.96	2.34
4 - 17	942.3	Basin F	939.96	2.34
4 - 18	943.8	Basin F	939.96	3.84
4 - 19	947.3	Basin F	939.96	7.34
4 - 20	947.3	Basin F	939.96	7.34
5 - 14	945.3	Basin E	941.49	3.81
5 - 15	945.3	Basin E	941.49	3.81
5 - 16	946.8	Basin E	941.49	5.31

Structure (Block – Lot)	Low Floor Elevation of Building (ft)	Waterbody	100-year Event Flood Elevation of Waterbody (ft)	Freeboard to 100-year Event (ft)
5 - 17	949.95	Basin E	941.49	8.46
5 - 18	950.55	Basin E	941.49	9.06
5 - 19	949.55	Basin E	941.49	8.06
5 - 20	946.8	Basin E	941.49	5.31

Because the low floor elevation of the nearest structures to Basin B, Basin F, and Basin E are below the 100-year high-water elevation, an alternative low floor analysis was conducted as outlined in Rule J, Appendix J.1 – Low-Floor Elevation Assessment. Groundwater was not discovered in the three borings in the vicinity of structures near Basin B, Basin F, and Basin E, thus the groundwater elevations were presumed to be at the elevation of the bottom of each individual soil boring nearest each structure. The engineer concurs with the applicant’s seasonal groundwater adjustment determined by increasing the presumed water table elevation by 25% of the total annual rainfall for the area.

The results of the low floor analysis using *Appendix J1 Plot 1: Minimum Depth to Water Table for No Further Evaluation* is summarized in the following table. Low floor requirements were also evaluated for three existing habitable structures beyond the southern parcel boundary of the site on Butternut Drive. The results demonstrate the provided separation is greater than the minimum required, thus meeting the habitable structure requirements in Rule J, Subsection 3.6.

Structure (Block – Lot)	Low Floor Elevation of Building (ft)	Waterbody	100-year Event Flood Elevation of Waterbody (ft)	Freeboard to 100-year Event (ft)	Distance from Building to Adjacent Facility (ft)	Water Table Elevation ¹ (ft)	Minimum Permissible Depth to Water Table ² (ft)	Provided Depth from Low Floor Elevation to Water Table (ft)
1 - Ex 1	925.25	Basin B	932.78	-7.53	95	920.5	2.5	4.8
1 - Ex 2	923.63	Basin B	932.78	-9.15	95	920.5	2.5	3.1
1 - Ex 3	924.2	Basin B	932.78	-8.58	95	920.5	2.5	3.7
2 - 8	928.9	Basin B	932.78	-3.88	32	920.5	8.0	8.4
4 - 11	941.3	Basin F	939.96	1.34	81	933.8	3.0	7.5
5 - 1	938.9	Basin E	941.49	-2.59	108	929.5	2.5	9.4
5 - 2	937.65	Basin E	941.49	-3.84	68	929.5	5.0	8.2
5 - 3	937.8	Basin E	941.49	-3.69	63	929.5	5.5	8.3
5 - 4	938.05	Basin E	941.49	-3.44	69	926.7	5.0	11.4
5 - 5	937.3	Basin E	941.49	-4.19	71	926.7	5.0	10.6
5 - 6	937.8	Basin E	941.49	-3.69	76	926.7	4.5	11.1
5 - 7	939.04	Basin E	941.49	-2.45	88	926.7	3.5	12.3
5 - 8	940.28	Basin E	941.49	-1.21	88	933.6	3.5	6.7
5 - 9	941.09	Basin E	941.49	-0.4	86	930.9	3.5	10.2

Structure (Block – Lot)	Low Floor Elevation of Building (ft)	Waterbody	100-year Event Flood Elevation of Waterbody (ft)	Freeboard to 100-year Event (ft)	Distance from Building to Adjacent Facility (ft)	Water Table Elevation ¹ (ft)	Minimum Permissible Depth to Water Table ² (ft)	Provided Depth from Low Floor Elevation to Water Table (ft)
5 - 10	942.05	Basin E	941.49	0.56	65	930.9	5.0	11.2
5 - 11	942.05	Basin E	941.49	0.56	65	930.9	5.0	11.2
5 - 12	941.55	Basin E	941.49	0.06	65	930.9	5.0	10.7
5 - 13	941.8	Basin E	941.49	0.31	64	930.9	5.0	10.9
5 - 21	941.05	Basin E	941.49	-0.44	250	929.5	0.0	11.6

¹Includes seasonal groundwater adjustment (1.3 feet)

²Based on Plot 1 of Rule J, Appendix J1

Placement of fill below the 100-year flood elevation is prohibited unless fully compensatory flood storage at or below the same elevation and within the floodplain of the same water basin is provided (Rule B, Subsection 3.2). Compensatory storage values are summarized in the following table. The supporting materials demonstrate, and the RPBCWD Engineer concurs, that 1.13 acre-feet of fill will be placed to facilitate site grading, and 5.11 acre-feet of excavation to create the compensatory storage below the 100-year floodplain, thus providing a net increase in floodplain storage. Because the compensatory storage will not be provided within the floodplain of the same waterbody, the applicant has requested a variance from this requirement of Rule B, Subsection 3.2b. See the Rule K discussion for additional information on the variance request.

Wetland Name	Proposed Fill below Existing 100-Year HWL (ac-ft)	Proposed Feature Providing Compensatory Storage	Provided Compensatory Storage (ac-ft)
B	0.82	Basin E	4.77
C	0.01	ST-48	0.02
D	0.10	Wetland D	0.25
Watercourse connecting Wetland E to Wetland D	0.12		
E	0.08	Swale from FES-39A	0.07

Because filling of wetlands onsite to facilitate site development and providing alternative storage areas will alter the timing and duration of flows leaving the site, the applicant must demonstrate that the alterations are not reasonably likely have an adverse offsite impact and will not adversely affect flood risk, basin or channel stability, groundwater hydrology, stream baseflow, water quality, or aquatic or riparian habitat (Rule B subsection 3.3). The applicant provided pre- and post-project water quality modeling to demonstrate the project is not reasonably likely to have an adverse impact to water quality. The modeling results show the total suspended solids and total phosphorus load leaving the site after

the development will be less than the existing load leaving the site. The water quality modeling also shows the proposed project will meet the water quality treatment criteria for areas tributary to the onsite wetlands (see Rule J Wetland Protection analysis).

In addition, consistent with the rate-control requirement in Rule J, the proposed peak discharge rates to Wetlands A and D, as well as discharge rate leaving the site, are less than existing for the 2, 10, and 100-year event. Because the flow rates are not increasing, the project is not likely to impact channel stability. The modeling provided by the applicant shows that the inundation periods for Wetland A during the 1, 2 and 10-year events are increased by between 6.0 to 6.4 hours while the 10-year bounce would be increase by 0.02 feet. The modeling provided by the applicant also shows that the inundation periods for Wetland D during the 1, 2 and 10-year events are increased by between 64.4 to 75.6 hours while the 10-year bounce would be 3.13 feet. Because these changes in inundation period and bounce align with guidance in the Board of Soils and Water Resources (BWSRs) Recommended Wetland Management Standards: Minnesota Routine Assessment Method for Evaluating Wetland Functions, Version 3.0, the RPBCWD engineer concurs that the change in hydrology will likely not adversely impact Wetland A or D. This also supports the engineer’s determination that the project meets the requirements of Rule B, subsection 3.3.

		Wetland D			Wetland A		
		Existing	Proposed	Change	Existing	Proposed	Change
100-Year HWL (ft)		930.14	932.53	2.39	919.12	918.91	-0.21
Inundation Period (hours)	1-Year	11.6	76.0	64.4	74.8	81.2	6.4
	2-Year	13.6	80.0	66.4	80.8	86.8	6.0
	10-Year	14.0	89.6	75.6	93.2	99.2	6.0
	100-Year	15.6	108.0	92.4	111.2	117.6	6.4

Rule B, Subsection 3.4 does not allow placing, constructing or reconstructing structures or paved surfaces within 100 feet of the centerline of any watercourse. Because the impervious surface within 50 feet of the watercourse is associated with a waterbody crossing regulated under Rule G, the requirements set forth by Rule B, subsection 3.4 do not apply (see exception in subsection 3.4a). See Rule C analysis of the applicant’s submitted erosion control plan to demonstrate conformance with Rule B, Subsection 3.5. A note on the plans indicates that activities must be conducted to minimize the potential transfer of aquatic invasive species conforming to Rule B, Subsection 3.6.

Rule C: Erosion Prevention and Sediment Control

Because the project will alter 36.79 acres of land-surface area, the project must conform to the requirements in the RPBCWD Erosion Prevention and Sediment Control rule (Rule C, Subsection 2.1).

The erosion and sediment control plans prepared by ISG Inc. includes installation of perimeter control, inlet protection for storm sewer catch basins, a rock construction entrance, protection of stormwater management facilities, placement of a minimum of 6 inches of topsoil (at 5% organic matter),

construction sequencing, decompaction of pervious areas compacted during construction, and retention of native topsoil onsite. To conform to RPBCWD Rule C requirements the following revisions are needed:

- C1. The Applicant must provide the name and contact information of the individual responsible for erosion control at the site. RPBCWD must be notified if the responsible individual changes during the permit term.

Rule D: Wetland and Creek Buffers

Because the proposed work triggers RPBCWD Rules B, G, and J and there are wetlands downgradient from the work for the proposed project, as well as WCA wetlands that will be disturbed, Rule D, Subsection 2.1a requires the applicant to establish buffer areas. Because the watercourse on the property Because B, C and E will be eliminated by the project, subsection 3.1b requires buffer on the edges of only Wetland A downgradient from the land-disturbing activities. The City of Chaska is the LGU administering WCA requirements and has approved a replacement plan for the filling of Wetlands B, C, and E as well as disturbance in Wetland D. Because the proposed construction activities disturb Wetland D, wetland buffers must be provided around the entire (remaining) wetland on the parcel (Rule D, subsection 3.1a)

A Minnesota Wetland Conservation Act Notice of Decision for the wetland boundaries, dated June 23, 2021, was included with the submittal. The MnRAM analyses submitted indicate that Wetland D and Wetland A located onsite are low and medium value wetlands, respectively. Rule D, Subsection 3.2.b.ii requires wetland buffer with an average of 20 feet from the delineated edge of the wetland, minimum 10 feet for low value wetlands. Rule D, Subsection 3.2.b.iii requires wetland buffer with an average of 40 feet from the delineated edge of the wetland, minimum 20 feet for medium value wetlands. Because Wetland A is encompassed by steep slopes averaging 18 percent or great over a distance of 50 feet or more, the required buffer must extend to the top of the slope. The proposed buffer for Wetland A extends to the top of the steep slope. The buffer widths are summarized in the table below.

Wetland ID	RPBCWD Wetland Value	Required Minimum Width (ft)	Required Average Width (ft)	Required Area (ft ²)	Provided Area (ft ²)	Provided Minimum Width (ft)	Provided Average Width (ft)
Wetland A	Medium	20	40	84,616 ¹	84,616	40	N/A ¹
Wetland D	Low	10	20	29,863	30,116	10	20.2

¹Buffer width cannot be averaged on steep slopes. The buffer area extends to the top of slopes that average steeper than 18% and results in a width greater than the required average, thus project conforms to Rule B, subsection 3.2b

The Landscaping Plan (sheets 26 and 27) indicates all disturbed areas within the buffer will be revegetated using a native seed mix and the existing vegetation will remain, thus conforming to Rule D, Subsection 3.3. The engineer’s review of plan sheets shows that buffer markers will be installed consistent with Rule D, Subsection 3.4. A note is included on the plan sheet indicating the project will be constructed so as to minimize the potential transfer of aquatic invasive species (e.g., zebra mussels, Eurasian watermilfoil, etc.) to the maximum extent possible conforming to Rule D, Subsection 3.6.

To meet the maintenance requirements in RPBCWD Rule D, Subsection 3.3, the applicant must address the following condition:

D1. Buffer areas and maintenance requirements must be documented in a declaration recorded after review and approval by RPBCWD in accordance with Rule D, Subsection 3.5.

Rule G: Waterbody Crossings and Structures

Because the project proposes to construct a waterbody crossing in contact with the bed and bank of the natural drainageway leaving Wetland D, the proposed project must meet the criteria of RPBCWD's Waterbody Crossings and Structures Rule (Rule G, Subsection 2).

The applicant is proposing a waterbody crossing on the southern natural watercourse leaving Wetland D to restore the wetland hydrology and off-set some of the lost wetland functions and values on-site due to filling of three other wetlands, thus demonstrating a specific need as required by Rule G, subsection 3.1b.

Rule G, Subsection 3.2.a requires that the construction of a waterbody crossing in contact with the bed or bank of a waterbody retain adequate hydraulic capacity and assure no net increase in the flood stage of the pertinent waterbody. Stormwater modeling provided by the applicant indicates that the 100-year flood stage for Wetland D will increase as a result of alterations to the existing outlet structure. The applicant has requested an exception to subsection 3.2.a because the proposed waterbody crossing will increase 100-year flood elevation upstream of the crossing from 930.14 feet to 932.53 feet (i.e. an increase of 2.39 feet) to restore the hydrology to the partially drained wetland. See the Rule K discussion for additional information on the exception request.

Due to the existing conditions of the outlet channel not providing navigational capacity, the requirements set forth by Rule G, subsection 3.2.b do not impose a requirement on the project. Because the provided construction plans indicate the installation of a skimmer structure for controlling flow rates from Wetland D to minimize erosion and reduce the potential for scour resulting from peak flows, the engineer concurs that the project is reasonable likely to prevent degradation of water quality in accordance with Rule G, Subsection 3.2.c.

Because the proposed waterbody crossing constitutes a potential impact to wildlife passage along each bank and riparian area near the outlet to Wetland D, the applicant must demonstrate that wildlife passage will be provided (Rule G, subsection 3.2.d). The watercourse is intermittent and does not support a fishery. Revegetation plans provided by the applicant propose native vegetation for the riparian areas along the waterbody crossing to enhance ecological benefit and native plantings upland for stabilization of the berm. Because wildlife native to the area will be able to continue using the native vegetated corridor over the crossing, the engineer concurs that the proposed project is in compliance with subsection 3.2.d.

Rule G, Subsection 3.2.e requires that a constructed waterbody crossing represent the 'minimal impact' solution to a specific need with respect to other reasonable alternatives, based on analysis of at least

two reasonable alternatives. The applicant provided two waterbody crossing alternatives for Wetland D: 1) the proposed outlet control structure and berm and 2) a footbridge with sheet piling and an orifice. The “do nothing” alternative was not a viable solution to restore the wetland hydrology and therefore dismissed from further consideration. The applicant maintains that the footbridge and sheet pile alternative present access and maintenance difficulties, thus the alternative not pursued.

The overall SWPPP plan sheet includes a note directing the contractor that no work affecting the bed or banks of a protected water shall occur between April 1 and June 15 (Rule G, Subsection 3.7a). Banks will be immediately stabilized after completion of permitted work and revegetated as soon as growing conditions allow (Rule G, Subsection 3.7b). A note is included on the plan sheet indicating the project will be constructed so as to minimize the potential transfer of aquatic invasive species (e.g., zebra mussels, Eurasian watermilfoil, etc.) to the maximum extent possible (Rule G, Subsection 3.7c and Rule F, subsection 3.3e).

Rule G, Subsection 3.7d requires compliance with the applicable criteria in section 3 of Rule F. The proposed riprap placement extends from the 10 feet for the waterbody crossing which is the minimum distance needed to provide a stilling pool and, thus representing the minimal encroachment to prevent erosion (Rule F, subsection 3.3a). Based on the applicant’s plans, the project proposes the use stone riprap having an average size of 9 inches, with a geotextile and transition layer of granular bedding sized consistent with the erosion intensity at the outfall locations, thus conforming to Rule F, Subsections 3.3b.

To meet the maintenance requirements in RPBCWD Rule G, Subsection 5, the applicant must address the following condition:

- G1. Waterbody crossing maintenance requirements must be documented in a declaration recorded after review and approval by RPBCWD in accordance with Rule G, Subsection 5.

Rule J: Stormwater Management

Because the project will alter 36.79 of land-surface area, the project must meet the criteria of RPBCWD’s Stormwater Management rule (Rule J, Subsection 2.1). The criteria listed in Subsection 3.1 apply to the entire project site because the project will increase the imperviousness of the entire site by more than 100 percent (Rule J, Subsection 2.3).

Proposed stormwater management facilities include stormwater detention basins (aka wet pond), infiltration basins, wetland retention areas, and a vegetated swale to provide volume control, water quality, and rate control. The proposed vegetated swale, sump catch basin manholes, and grass filter strips will serve as pretreatment for runoff.

Rate Control

In order to meet the rate control criteria listed in Subsection 3.1.a, the 2-, 10-, and 100-year post development peak runoff rates must be equal to or less than the existing discharge rates at all locations where stormwater leaves the site. The Applicant used a HydroCAD hydrologic model to simulate runoff

rates for pre- and post-development conditions for the 2-, 10-, and 100-year frequency storm events using a nested rainfall distribution, and a 100-year frequency, 10-day snowmelt event. The existing and proposed 2-, 10-, and 100-year frequency discharges from the site are summarized in the table below. The proposed stormwater management plan will provide rate control in compliance with the RPBCWD requirements for the 2-, 10-, and 100-year events. Thus, the proposed project meets the rate control requirements in Rule J, Subsection 3.1a.

Modeled Discharge Location	2-Year Discharge (cfs)		10-Year Discharge (cfs)		100-Year Discharge (cfs)		10-Day Snowmelt (cfs)	
	Ex	Prop	Ex	Prop	Ex	Prop	Ex	Prop
From South Wetland D	3.6	1.5	12.6	3.3	48.3	6.2	5.5	2.7
To North Wetland A from Site	3.6	0.9	9.5	1.8	24.2	2.8	1.2	1.0
To Chanhassen Storm Sewer	1.0	0.8	3.5	1.5	8.8	2.8	0.5	0.1

Volume Abstraction

Subsection 3.1.b of Rule J requires the abstraction onsite of 1.1 inches of runoff from the new and disturbed impervious surface of the parcel. An abstraction volume of 48,264 cubic feet is required from the proposed 12.08 acres (35,542 square feet) of impervious area. The proposed wet pond, vegetated swale, sump catch basin manholes, and grass filter strips will serve as pretreatment for runoff into the three infiltration basins and wetlands (Rule J, Subsection 3.1.b.1). Soil borings performed by Braun Intertec on May 21, 2021 show that soils in the project area are primarily clayey sand and sandy lean clay. Braun Intertec conducted twelve double-ring infiltration tests on this site. Two infiltration tests were conducted at the proposed Basin B location on the southeastern end of the site, four tests at Basin E located in the center of the site, and two tests at Basin F located on the northeast portion of the site. The following table summarizes the infiltration testing results as well as the infiltration rate the applicant used for design of the stormwater management facilities. The engineer concurs with the applicant’s design infiltration rates, which are lower than the measured rate to provide a factor of safety. The engineer concurs that the basins will draw down within 48 hours (Rule J, subsection 3.1b.3).

Infiltration Test ID	Location	Measured Infiltration Rate (in/hr)	Design Infiltration Rate (in/hr)
DRI-1 (06/17/21)	Basin B	0.3	0.15
DRI-2 (06/17/21)	Basin B	0.8	
DRI-8 (06/22/21)	Basin E	2.4	0.35
DRI-9 (06/21/21)	Basin E	0.8	
DRI-10 (06/21/21)	Basin E	2.84	
DRI-11 (06/21/2021)	Basin E	0.8	
DRI-14 (06/18/21)	Basin F	0.2	0.15
DRI-15 (06/18/2021)	Basin F	0.22	

Groundwater was not observed at soil borings under the proposed infiltration and detention basins. The subsurface investigation information summarized in the following table shows that groundwater is at least 3 feet below the bottom of the proposed stormwater management facilities (Rule J, Subsection 3.1.b.2.a).

Proposed BMP	Nearest Subsurface Investigation	Boring is within footprint?	Groundwater Elevation (feet)	BMP Bottom Elevation (feet)	Separation (feet)
Basin B (Infiltration Basin)	ST-12	Yes	No groundwater observed at boring bottom (approx. el 919.2)	930.50	11.3
Basin C (Detention Basin)	ST-9	Yes	No groundwater observed at boring bottom (approx. el 917.2)	926.0	8.8
Basin E (Infiltration Basin)	ST-6	No	No groundwater observed at boring bottom (approx. el 929.6)	937.25	7.65
Basin F (Infiltration Basin)	ST-5	No	No groundwater observed at boring bottom (approx. el 932.5)	936.50	4.0

While infiltration Basins B, E, and F are large enough to provide all the project’s required abstraction volume, their location and site topography prevented roughly 5% of the project’s impervious surfaces tributary to Wetland D, all of which is from rear roof drainage, from being routed to the infiltration basins. To provide abstraction of runoff from this rear roof drainage the applicant incorporated a better site design technique outlined in the MPCA MN Stormwater Manual by accounting for runoff directed into a vegetated swale or onto adjacent pervious areas where it can be infiltrated. Because the ability of the wetland buffer to perform as a better site design technique providing abstraction and water quality treatment is dependent on runoff being distributed across the pervious surface, the grading of Lots 15-20 must incorporate flow dispersion techniques or other measures to prevent channelized flow.

The table below summarizes the volume abstraction required and the volume abstraction achieved by the proposed stormwater management facilities on site. The proposed project is in conformance with Rule J, Subsection 3.3.a.

Required Abstraction Depth (inches)	Required Abstraction Volume (cubic feet)	Provided Abstraction Depth (inches)	Provided Abstraction Volume (cubic feet)
1.1	48,236	1.11	48,883

Water Quality Management

Subsection 3.1.c of Rule J requires the Applicant provide volume abstraction in accordance with 3.1b or least 60 percent annual removal efficiency for total phosphorus (TP), and at least 90 percent annual removal efficiency for total suspended solids (TSS) from site runoff, and no net increase in TSS or TP loading leaving the site from existing conditions. Because the stormwater management facilities proposed by the applicant provide abstraction meeting 3.1b and the engineer concurs with the modeling, the engineer finds that the proposed project is in conformance with Rule J, Subsection 3.1.c.

Low floor Elevation

All new buildings must be constructed such that the lowest floor is at least two feet above the 100-year high water elevation or one foot above the emergency overflow of a stormwater-management facility according to Rule J, Subsection 3.6a. In addition, a stormwater-management facility must be constructed at an elevation that ensures that no adjacent habitable building will be brought into noncompliance with this requirement according to Rule J, Subsection 3.6b. The low floor elevation analysis presented above in the Rule B, Floodplain Management analysis section of this report demonstrates the proposed project is in conformance with Rule J, Subsection 3.6.

Maintenance

Subsection 3.7 of Rule J requires the submission of a maintenance plan. All stormwater management structures, facilities, and features must be designed for maintenance access and properly maintained in perpetuity to assure that they continue to function as designed. Because compliance with the RPBCWD stormwater-management requirements is dependent on wetland buffers area and vegetated swales remaining in a natural condition as well as flow dispersion across the buffer areas, these conditions and associated maintenance requirements must be documented in the maintenance declaration recorded after review and approval by RPBCWD.

- J1. Permit applicant must provide a recorded maintenance and inspection declaration. A maintenance declaration template is available on the permits page of the RPBCWD website. (<http://www.rpbcwd.org/permits/>). The declaration must include the all stormwater management facilities as well as the buffers and vegetated swales. The maintenance plan must provide for predominantly native vegetation. A draft declaration must be provided for District review and approval, then recordation.

Wetland Protection

Because the proposed activities discharge to two wetlands on the site and alter the discharge the wetlands receive from the site, the project must conform to RPBCWD wetland protection criteria (Rule J, subsection 3.10). The applicant provided and the Engineer concurs with the below analysis of potential wetland impacts based on Table J1 of RPBCWD Rule J.

Wetland A has been assessed as medium value and Wetland D has been assessed as low value using the MNRAM analysis provided by the applicant. The following tables summarize the allowable change in bounce and inundation duration from Table J1 of RPBCWD Rule J as well as the applicant's analysis for

wetland protection and the potential impacts on the wetlands. The proposed project conforms to the wetland bounce and inundation requirements.

Summary of allowable impacts on onsite wetland from Rule J, Table J1

Waterbody (Wetland Value)	Permitted Bounce for, 10-Year Event	Inundation Period for 1- and 2-Year Event	Inundation Period for 10-Year Event	Runout Control Elevation
Wetland A (Medium)	Existing +/- 1.0 feet	Existing + 2 days	Existing + 14 days	0 to 1.0 ft above existing runout
Wetland D (Low)	No Limit	Existing + 7 days	Existing + 21 days	0 to 4.0 ft above existing runout

Impacts of Project on Wetlands

Wetland (Location)	RPBCWD Wetland Value	Change in Bounce for, 10-Year Event (feet)	1-year change in Inundation Period (days)	2-year change in Inundation Period (days)	10-year change in Inundation Period (days)	Runout Control Elevation (feet)
Wetland A (North)	Medium	+0.02	+0.27	+0.25	+0.25	No Change
Wetland D (South)	Low	+1.7	+2.68	+2.77	+3.15	+1.2

Rule J, Subsection 3.10b requires that any discharge to a low- to medium-value wetland be treated to the water quality treatment criteria in Rule J, subsection 3.1c. The applicant provided MID's and P8 modeling as summarized in the table below demonstrating the runoff from the disturbed areas tributary to Wetland A and Wetland D will be treated in conformance with Rule J, Subsection 3.10b.

Wetland	Wetland Value	TSS Removal	TP Removal
Required		90%	60%
Wetland A	Medium	92.1%	82.2%
Wetland D	Low	95.5%	86.6%

Chloride Management

Subsection 3.8 of Rule J requires the submission of chloride management plan that designates the individual authorized to implement the chloride management plan and the MPCA-certified salt applicator engaged in implementing the plan. The RPBCWD chloride-management plan requirement applies to the streets and common areas of the project site, but not the individual single-family homes. If the streets within the proposed residential development will be within public right of way that will be maintained by the city of Chaska, the City must provide its chloride management plan and its designated state-certified chloride applicator. To close out the permit and release the \$5,000 in financial assurance held for the purpose of chloride management, the permit applicant must provide a chloride management plan that designates the individual authorized to implement the chloride management plan and the MPCA-certified salt applicator engaged in implementing the plan at the site.

Rule K: Variances and Exceptions:

The Applicant has requested one variance from the RPBCWD floodplain rule requirements.

To approve a variance, Rule K requires the Board of Managers to find that because of unique conditions inherent to the subject property the application of rule provisions will impose a practical difficulty on the Applicant. Assessment of practical difficulty is conducted against the following criteria:

1. how substantial the variation is from the rule provision;
2. the effect of the variance on government services;
3. whether the variance will substantially change the character of or cause material adverse effect to water resources, flood levels, drainage or the general welfare in the District, or be a substantial detriment to neighboring properties;
4. whether the practical difficulty can be alleviated by a technically and economically feasible method other than a variance. Economic hardship alone may not serve as grounds for issuing a variance if any reasonable use of the property exists under the terms of the District rules;
5. how the practical difficulty occurred, including whether the landowner, the landowner's agent or representative, or a contractor, created the need for the variance; and
6. in light of all of the above factors, whether allowing the variance will serve the interests of justice.

It is the applicant's obligation to address these criteria to support a variance request. The applicant's variance requests cite several facts related to the development in support of each request, taken from their January 3, 2022 submittal, are attached to this review. Following is the RPBCWD engineer's assessment of information received relevant to the applicant's variance and exception requests.

Variance Request

The local governmental unit (LGU) administering the Wetland Conservation Act (WCA), City of Chaska, approved a replacement plan for the filling of three wetlands on the project site. Rule B subsection 3.2 requires compensatory flood storage within the floodplain of the same waterbody. The Applicant requested a variance from this provision of RPBCWD's Rule B – Floodplain Management and Drainage Alterations.

The applicant asserts that the need for the variance results from the unique condition of the LGU's having approved complete elimination of the three wetlands (Wetland B, Wetland C, Wetland E). Following is the RPBCWD engineer's assessment of information received relevant to the applicant's request for a variance from the compensatory flood storage criteria within the floodplain of the same waterbody:

- Regarding variance criteria 1 – The supporting materials demonstrate the proposed project will involve an aggregate total of 1.13 acre-feet of fill placed and 5.11 acre-feet of compensatory storage in aggregate will be created below the 100-year flood elevation, thus providing a net increase in the floodplain storage. The Comparative Flood Storage table below summarize the fill and compensatory flood storage volume by waterbody.

Waterbody	Existing Flood Elevation	Proposed Flood Elevation	Existing Flood Storage Filled (acre-feet)	Compensatory Flood Storage (acre-feet)
Wetland A	919.12	918.91	0.0	0.0
Wetland B	944.60	completely filled	0.82	0.0
Wetland C	946.85	completely filled	0.01	0.0
Wetland D	930.14	932.53	0.10	0.25
Wetland E	0.69*	completely filled	0.08	0.0
Watercourse connecting Wetland E to D	1.35*	completely filled	0.12	0.0
Basin B	N/A	932.78	N/A	0.0
Basin C	N/A	933.49	N/A	0.0
Basin E	N/A	941.49	N/A	4.77
ST_28	N/A	944.42	N/A	0.02
Swale from FES-39A	N/A	944.74	N/A	0.07
Total			1.13	5.11

*Value represents the 100-year flow depth (feet) as a surrogate due to feature being a sloped wetland or watercourse.

- Regarding variance criteria 2 and 3 – The rate control analysis, abstraction analysis, and water quality assessment submitted demonstrates compliance with Rule B, subsection 3.3, which requires no off-site adverse impacts. The Rule B discussion above illustrates that the proposed alternations will not have an adverse effect to offsite governmental services, water resources, flood levels, or neighboring properties. The proposed variance only impacts the applicant’s property.
- Regarding variance criteria 4 - Technical measures incorporated into the project plan to alleviate the practical difficulty include - creation of compensatory flood storage volume in infiltration basins and a wet detention basin to comply with RPBCWD regulatory requirements, but not within the same floodplain to facilitate site development. Because the wetlands will no longer exist the compensatory storage cannot be provided within the floodplain of the same waterbody.
- Regarding variance criterion 5 - The applicant has created the circumstances leading to the variances, though it did so with the approval of another relevant regulatory body, the LGU administering WCA. The applicant asserts that total avoidance of Wetlands, B, C, and E as well as the channel connecting wetland E to D would make the property less desirable to develop.
- Regarding variance criterion 6 – A stormwater management system is proposed to mitigate potential impacts and improve upon the overall conditions onsite by promoting the re-establishment of wetland vegetation within existing Wetland D.

The engineer finds there is an adequate technical basis for the managers to rely on to grant the requested variance.

Exception Request

The applicant also requested an exception from the Rule G, Subsection 3.2.a requirement to retain adequate hydraulic capacity and assure no net increase in the flood stage of Wetland D. The Board of Managers may approve an exception from a provision of the rules requiring a particular treatment or management strategy, or setting forth a design specification, if an applicant demonstrates that better natural resource protection or enhancement can be achieved by the project as proposed, with such further conditions as the Board of Managers may impose, than would strict compliance with the provision. Rule G, Subsection 3.2.a requires that the construction of a waterbody crossing in contact with the bed or bank of a waterbody retain adequate hydraulic capacity and assure no net increase in the flood stage of the pertinent waterbody. Stormwater modeling provided by the applicant indicates that the 100-year flood stage for Wetland D will increase as a result of the applicant proposed restoration of the Wetland D hydrology. As such, the applicant has requested that RPBCWD grant an exception to subsection 3.2a, as the proposed project provides better natural resource protection and enchantment (Rule K, Section 2). The engineer finds that:

- The elevation of the proposed normal water level of Wetland D was determined by the City of Chaska to establish a normal water level in the wetland to promote the re-establishment of native vegetation. As such, the proposed outlet elevation and normal water level of Wetland D were raised from existing elevations, resulting in an increase in the 100-year flood elevation. While not compliant with Rule G, Subsection 3.2a, the increase in the normal water level will promote the re-establishment of native, wetland plant communities within Wetland D.
- The information submitted by the applicant includes a restoration, planting, and vegetation establishment plan for Wetland D (sheet 69) to ensure the restoration health of the wetland.
- The configuration of the proposed outlet structure for Wetland D was deemed necessary by the applicant to provide rate reduction to the standard of the City of Chaska, which requires a maximum discharge rate of less than 6 cubic feet per second (cfs) from Wetland D (0.2 cfs/acre). This discharge rate is significantly lower than the RPBCWD requirement to be less than the existing 100-year rate of 48 cfs. Because the proposed extended detention of stormwater in Wetland D helps reduce discharge velocities and associated erosive forces in the downstream watercourse, the proposed design provides better resource protection.
- The construction plans prepared by ISG Inc. include the installation of a skimmer structure for controlling flow rates from Wetland D to minimize disturbance and erosion of natural shoreline and bed resulting from peak flows.

Because the proposed waterbody crossing and outlet configuration for Wetland D provide for enhanced ecological conditions that restore an otherwise farmed wetland, the RPBCWD engineer finds that there is ample factual and analytical basis for a determination by the managers that an exception is warranted from compliance with Rule G, subsection 3.2a.

Rule L: Permit Fee Deposit:

The RPBCWD permit fee schedule adopted in February 2020 requires permit applicants to deposit \$3,000 to be held in escrow and applied to cover the \$10 permit-processing fee and reimburse RPBCWD for permit review and inspection-related costs and when a permit application is approved, the deposit

must be replenished to the applicable deposit amount by the applicant before the permit will be issued to cover actual costs incurred to monitor compliance with permit conditions and the RPBCWD Rules. A permit fee deposit of \$3,000 was received on July 27, 2021. The applicant must replenish the permit fee deposit to the original amount due before the permit will be issued. Subsequently, if the costs of review, administration, inspections and closeout-related or other regulatory activities exceed the fee deposit amount, the applicant will be required to replenish the deposit to the original amount or such lesser amount as the RPBCWD administrator deems sufficient within 30 days of receiving notice that such deposit is due. The administrator will close out the relevant application or permit and revoke prior approvals, if any, if the permit-fee deposit is not timely replenished.

- L1. The applicant must replenish the permit fee deposit to the original amount due before the permit will be issued.
- L2. Because the applicant requested a variance and an exception under Rule K, an additional permit fee deposit of \$2,000 is required.

Rule M: Financial Assurance:

	Unit	Unit Cost	# of Units	Total
Rules C: Silt fence:	LF	\$2.50	10,210	\$25,525
Inlet protection	EA	\$100	62	\$6,200
Rock Entrance	EA	\$250	1	\$250
Restoration	Ac	\$2,500	36.79	\$91,975
Rules J: Stormwater Management: Stormwater Management Facilities: 125% of engineer’s opinion of cost (\$534,187)	EA	125% OPC	1	\$667,734
Chloride Management Plan	EA	\$5,000	1	\$5,000
Contingency (10%)		10%		\$79,668
Total Financial Assurance				\$876,352

Applicable General Requirements:

1. The RPBCWD Administrator and Engineer shall be notified at least three days prior to commencement of work.
2. Construction shall be consistent with the plans and specifications approved by the District as a part of the permitting process. The date of the approved plans and specifications is listed on the permit.
3. Construction must be consistent with the plans, specifications, and models that were submitted by the applicant that were the basis of permit approval. The date(s) of the approved plans, specifications, and modeling are listed on the permit. The grant of the permit does not in any way relieve the permittee, its engineer, or other professional consultants of responsibility for the permitted work.
4. The grant of the permit does not relieve the permittee of any responsibility to obtain approval of any other regulatory body with authority.

5. The issuance of this permit does not convey any rights to either real or personal property, or any exclusive privileges, nor does it authorize any injury to private property or any invasion of personal rights, nor any infringement of federal, state, or local laws or regulations.
6. In all cases where the doing by the permittee of anything authorized by this permit involves the taking, using or damaging of any property, rights or interests of any other person or persons, or of any publicly owned lands or improvements or interests, the permittee, before proceeding therewith, must acquire all necessary property rights and interest.
7. RPBCWD's determination to issue this permit was made in reliance on the information provided by the applicant. Any substantive change in the work affecting the nature and extent of applicability of RPBCWD regulatory requirements or substantive changes in the methods or means of compliance with RPBCWD regulatory requirements must be the subject of an application for a permit modification to the RPBCWD.
8. If the conditions herein are met and the permit is issued by RPBCWD, the applicant, by accepting the permit, grants access to the site of the work at all reasonable times during and after construction to authorized representatives of the RPBCWD for inspection of the work.

Findings

1. The proposed project includes the information necessary, plan sheets, and erosion control plan for review.
2. The Applicant has requested a variance from compliance with the Rule B criteria related to providing compensatory storage within the same floodplain.
3. The proposed project will conform to Rules C, D, and J if the Rule Specific Permit Conditions listed above are met.
4. The project will conform to the requirement of Rule G should an exception from compliance with Rule G, subsection 3.2 be approved.

Recommendation:




If the managers grant the variance and exception (with such conditions as the managers may impose), the engineer recommends approval of the permit for a 2 year term, contingent upon:

1. Financial Assurance in the amount of \$876,352.
2. Applicant providing the name and contact information of the individual responsible for erosion and sediment control at the site.
3. Receipt in recordation a maintenance declaration for the operation and maintenance all stormwater management facilities, buffers, and waterbody crossing. Drafts of all documents to be recorded must be approved by the District prior to recordation.
4. The applicant must replenish the permit fee deposit to the original amount due before the permit will be issued including the additional permit fee deposit of \$2,000 because the applicant requested a variance and an exception.

By accepting the permit, when issued, the applicant agrees to the following stipulations:

1. Continued compliance with General Requirements

2. Per Rule J Subsection 4.5, upon completion of the site work, the permittee must submit as-built drawings demonstrating that at the time of final stabilization, all the stormwater facilities conform to design specifications and function as intended and approved by the District. As-built/record drawings must be signed by a professional engineer licensed in Minnesota and include, but not limited to:
 - a. the surveyed bottom elevations, water levels, and general topography of all facilities;
 - b. the size, type, and surveyed invert elevations of all stormwater facility inlets and outlets;
 - c. the surveyed elevations of all emergency overflows including stormwater facility, street, and other;
3. Providing the following additional close-out materials:
 - a. Documentation that disturbed pervious areas remaining pervious have been decompacted per Rule C.2c criteria
4. To close out the permit and release the \$5,000 in financial assurance held for the purpose of the chloride management, the permit applicant must provide a chloride management plan that designates the individual authorized to implement the chloride management plan and the MPCA-certified salt applicator engaged in implementing the plan at the site.
5. Replenish the permit fee deposit to the original amount or such lesser amount as the RPBCWD administrator determines sufficient within 45 days of receiving notice that such deposit is due in order to cover continued actual costs incurred to monitor compliance with permit conditions and the RPBCWD Rules.



Permit Location Map




Feet




RESERVE AT AUTUMN WOODS
Permit 2021-063
Riley Purgatory Bluff Creek
Watershed District




OUTLETS:
 3/4" (ST) TO BASIN (INVERT = 80.0)
 1" (ST) TO WETLAND (INVERT = 80.0)
 1" (ST) TO WETLAND (INVERT = 80.0)
 METAL LIDS ENHANCED OVER 4-4" O.D. OUTLETS TO PROVIDE SPINNING, WHERE TO REMAIN IN PLACE PER MANUFACTURER INSTALLATION INSTRUCTIONS.



BASIN C CROSS SECTION
 NTS SD726



SKIMMER STRUCTURE WITH CAST IN FIELD CONCRETE BAFFLE WALL
 CHASKA, MINNESOTA
 SHEET NO. 570-188




SKIMMER STRUCTURE WITH CAST IN FIELD CONCRETE BAFFLE WALL
 WETLAND D, OUTLET
 CHASKA, MINNESOTA
 SHEET NO. 570-18

INLET TRAP BASIN CONSTRUCTION:

- WORK SHALL INCLUDE - ALL EXCAVATION AND CONSTRUCTION AS OUTLINED IN THE PLANS, SPECIFICATIONS AND DETAILS DURING THE CONSTRUCTION OF THE INFILTRATION BASIN.
- THE CONTRACTOR SHALL MAINTAIN SET FENCE AROUND THE PERIMETER OF THE INFILTRATION BASIN DURING ALL PHASES OF CONSTRUCTION. THE INFILTRATION AREA MUST BE STAKED OFF AND MARKED TO KEEP ALL CONSTRUCTION TRAFFIC.
- THE CONTRACTOR SHALL ENSURE THAT THE INFILTRATION BASIN IS NOT USED AS A SEWAGE TRAP DURING CONSTRUCTION AND THAT NO DEBRIS ENTERS THE BASIN PRIOR TO THE COMPLETION OF CONSTRUCTION AND COMPLETE STABILIZATION OF SURROUNDING AREAS DRAINING TO THE BASIN. ALL EXCAVATION MUST BE COVERED TO PREVENT RAINFALL FROM ENTERING THE INFILTRATION WORK AREA.
- AVOID SOIL COMPACTION IN THE BASIN. EQUIPMENT SHALL BE OPERATED IN THE AREA OF THE BASIN PRIOR TO ITS CONSTRUCTION. AN INVERT IS CONSTRUCTED ONLY LIGHT MOVING EQUIPMENT WITH TRACKS SHALL BE USED.
- AFTER FINAL COMPACTION, THE BASIN FLOOR SHALL BE TILLED TO A DEPTH OF AT LEAST THREE (3) INCHES TO PROVIDE A WELL-AERATED, POROUS SURFACE. SPREADING OF THE SOIL IN THE BASIN SHALL BE AVOIDED AND IF SPREADING DOES OCCUR IT SHALL BE IMMEDIATELY FOLLOWING INFILTRATION BASIN CONSTRUCTION. THE ENTIRE BASIN SHALL BE SEEDED AND FERTILIZED AS INDICATED IN THE PLANS. INFILTRATION BASIN MUST BE FULLY STABILIZED PRIOR TO ANY UPSTREAM INFILTRATION TRAP CONSTRUCTION.
- INFILTRATION TRAP SIZES SHALL NOT BE EXCEEDED WITHOUT APT. OF FINAL GRADE DATE. THE CONTRIBUTING DRAINAGE AREA HAS BEEN CONSTRUCTED AND FULLY STABILIZED. ANY ACCUMULATED SEWAGE MUST BE REMOVED IN A MANNER THAT PREVENTS COMPACTION OF THE BOTTOM. TO PROVIDE A WELL-AERATED, HIGHLY POROUS SURFACE. THE SOILS BELOW AN INFILTRATION TRAP MUST BE LOOSENED TO A MINIMUM DEPTH OF 18 INCHES PRIOR TO PLANTING.

REFER TO SITE RESTORATION PLAN FOR BASIN SEEDING REQUIREMENTS.




BASIN E INFILTRATION BASIN
 NTS S10600

INLET TRAP BASIN CONSTRUCTION:

- WORK SHALL INCLUDE - ALL EXCAVATION AND CONSTRUCTION AS OUTLINED IN THE PLANS, SPECIFICATIONS AND DETAILS DURING THE CONSTRUCTION OF THE INFILTRATION BASIN.
- THE CONTRACTOR SHALL MAINTAIN SET FENCE AROUND THE PERIMETER OF THE INFILTRATION BASIN DURING ALL PHASES OF CONSTRUCTION. THE INFILTRATION AREA MUST BE STAKED OFF AND MARKED TO KEEP ALL CONSTRUCTION TRAFFIC.
- THE CONTRACTOR SHALL ENSURE THAT THE INFILTRATION BASIN IS NOT USED AS A SEWAGE TRAP DURING CONSTRUCTION AND THAT NO DEBRIS ENTERS THE BASIN PRIOR TO THE COMPLETION OF CONSTRUCTION AND COMPLETE STABILIZATION OF SURROUNDING AREAS DRAINING TO THE BASIN. ALL EXCAVATION MUST BE COVERED TO PREVENT RAINFALL FROM ENTERING THE INFILTRATION WORK AREA.
- AVOID SOIL COMPACTION IN THE BASIN. EQUIPMENT SHALL BE OPERATED IN THE AREA OF THE BASIN PRIOR TO ITS CONSTRUCTION. AN INVERT IS CONSTRUCTED ONLY LIGHT MOVING EQUIPMENT WITH TRACKS SHALL BE USED.
- AFTER FINAL COMPACTION, THE BASIN FLOOR SHALL BE TILLED TO A DEPTH OF AT LEAST THREE (3) INCHES TO PROVIDE A WELL-AERATED, POROUS SURFACE. SPREADING OF THE SOIL IN THE BASIN SHALL BE AVOIDED AND IF SPREADING DOES OCCUR IT SHALL BE IMMEDIATELY FOLLOWING INFILTRATION BASIN CONSTRUCTION. THE ENTIRE BASIN SHALL BE SEEDED AND FERTILIZED AS INDICATED IN THE PLANS. INFILTRATION BASIN MUST BE FULLY STABILIZED PRIOR TO ANY UPSTREAM INFILTRATION TRAP CONSTRUCTION.
- INFILTRATION TRAP SIZES SHALL NOT BE EXCEEDED WITHOUT APT. OF FINAL GRADE DATE. THE CONTRIBUTING DRAINAGE AREA HAS BEEN CONSTRUCTED AND FULLY STABILIZED. ANY ACCUMULATED SEWAGE MUST BE REMOVED IN A MANNER THAT PREVENTS COMPACTION OF THE BOTTOM. TO PROVIDE A WELL-AERATED, HIGHLY POROUS SURFACE. THE SOILS BELOW AN INFILTRATION TRAP MUST BE LOOSENED TO A MINIMUM DEPTH OF 18 INCHES PRIOR TO PLANTING.

REFER TO SITE RESTORATION PLAN FOR BASIN SEEDING REQUIREMENTS.



BASIN B INFILTRATION BASIN
 NTS S10600

LENNAR
RESERVE AT
AUTUMN WOODS

CHASKA MINNESOTA

DATE	REVISION	SCHEDULE
10/15/22	CITY COMMENTS	JRS
10/20/22	CITY COMMENTS	JRS
11/17/22	CITY & WATERBESH COMMENTS	TTR

PROJECT NO.	21-24884
FILE NAME	24884.DETAILS
DRAWN BY	JRS
DESIGNED BY	JRS
REVIEWED BY	JRS
ORIGINAL ISSUE DATE	11/02/22
CLIENT PROJECT NO.	

TITLE

STORM WATER
BASIN DETAILS

SHEET



NOTE:
THE CLARITY OF THESE PLANS DEPENDS ON THE QUALITY OF THE ORIGINAL PLAN SET AND MAY RESULT IN MISINTERPRETATION.
THIS DOCUMENT IS THE PROPERTY OF I & S GROUP, INC. AND MAY NOT BE USED, COPIED OR DUPLICATED WITHOUT PRIOR WRITTEN CONSENT.
JEREMY D. FOSS
DATE: _____ LIC. NO. 59871
THIS DOCUMENT IS THE PROPERTY OF I & S GROUP, INC. AND MAY NOT BE USED, COPIED OR DUPLICATED WITHOUT PRIOR WRITTEN CONSENT.

CHASKA MINNESOTA
REVISION SCHEDULE
DATE DESCRIPTION
BY
2/14/22 CITY COMMENTS JRS
3/10/22 CITY & WATERBURY COMMENTS JRS
3/17/22 CITY & WATERBURY COMMENTS JRS

PROJECT NO. 21-24984
FILE NAME 20M SWPPP DETAILS
DRAWN BY JRS
DESIGNED BY JRS
REVIEWED BY JDF
ORIGINAL ISSUE DATE 11/03/22
CLIENT PROJECT NO. _____


TITLE
SHEET NO. _____ OF 71

PROJECT #
SHEET NO. _____ OF _____

STANDARD BMSR 103
GICCT
PRINT NAME / SIGNATURE DATE
LIC. NO. _____

WEETLAND RESTORATION PLAN
ROCK RODENT PROTECTION DETAIL

DESIGN TABLE																	
EMBANKMENT ID	EMBANKMENT DESIGN ELEVATION (FEET)	ROCK LAYOUT TYPE (A, B, OR C)	A	B	C	D	E	F	G	H	I	J	K	L	M	N	ESTIMATED QUANTITY (SQ. FT.)
Wetland D	933.00	C	933.00	SEE SWPPP	3.0	22.5	3.2	12.1	5.4	5.6	4.1	24.0	3.0				



ANGULAR ROCK GRADATION TABLE	
ANGULAR ROCK GRADATION: ONLY CRUSHED ANGULAR ROCK SHALL BE USED. ENGINEER RECOMMENDS CLASS 1 BALLAST ROCK (3/4" - 4"). SUBSTITUTE GRADATION SHALL BE APPROVED BY ENGINEER.	
ROCK DIAMETER (INCHES)	PERCENT OF TOTAL SIZE SMALLER THAN A GIVEN SIZE (%)
2 - 4	100 - 30
< 2	29 - 0

RODENT PROTECTION CONSTRUCTION REQUIREMENTS	
RODENT PROTECTION: • ROCK TRENCH DEPTH MAY VARY: • QUANTITIES ARE BASED ON A MINIMUM 12" WIDE EXCAVATED TRENCH, DEPTHS, AND LENGTHS SPECIFIED IN THE DESIGN TABLE. IF CONTRACTOR CHOOSES TO USE A WIDER BUCKET TO EXCAVATE TRENCH, CONTRACTOR WILL BE RESPONSIBLE FOR QUANTITY OVERAGES AND ADDITIONAL COSTS. • BACK FILL AND BUCKET COMPACT PLACED ROCK IN 12' LIFTS.	

ITEM NO.	DESCRIPTION	UNITS	QUANTITY
251.507	RANDOM SWPPV CLASS III	CY	143
251.502	PROPOSED STORM DRAIN INLET PROTECTION	EACH	62
251.501	STABILIZED CONSTRUCTION EOT	EACH	1
251.504	EROSION CONTROL BLANKET CATEGORY 3N	SF	25,841
251.504	TURF REINFORCEMENT MAT CATEGORY 3	SF	400
	PERIMETER CONTROL	LF	10,279
	CONCRETE WASHOUT AREA	EA	1

QUANTITIES FOR NON-VEGETATIVE AREAS ARE BASED ON THE REQUIREMENTS OF THE CONSTRUCTION SWPPP PLAN AND SHOULD BE ADJUSTED TO MATCH QUANTITIES REQUIRED.

RPCVDO STANDARD EROSION CONTROL NOTES (cont. from SWPPP)

- Natural topography and soil conditions must be protected, including retention onsite of native topsoil to the greatest extent possible.
- Additional measures, such as hydraulic mulching and other practices as specified by the District must be used on slopes of 3:1 (H:V) or steeper to provide adequate stabilization.
- Final site stabilization measures must specify that at least six inches of topsoil or organic matter with at least 5% organic content (shall meet RPCVDO topsoil definition) be spread and incorporated into the underlying soil during final site treatment whenever topsoil has been removed.
- Construction site waste such as discarded building materials, concrete truck washout, chemicals, litter and sanitary waste must be properly managed.
- All temporary erosion and sediment control BMPs must be established until completion of construction and vegetation is established to ensure stability of the site, as determined by the District.
- All temporary erosion and sediment control BMPs must be removed upon final stabilization.
- Soil test beds completed during construction and remaining undisturbed until completion of construction must be deconstructed to achieve a soil compaction pressure of less than 1,000 kilopascals or 200 pounds per square inch in the upper 12 inches of the soil profile while taking care to protect utilities, tree roots, and other existing vegetation.
- Infiltration facilities must not be excavated to within 2-ft of final grade until contributing drainage area has been constructed and fully stabilized. Any accumulated sediment in an infiltration facility must be removed in a manner that prevents compaction of the facility bottom. To provide a well-aerated, highly porous substrate, the soil below an infiltration facility must be amended to a minimum depth of 18" prior to installation or planting.
- All disturbed areas must be stabilized within 7 calendar days after land-disturbing work has temporarily or permanently ceased on a property that drains to an impaired water, within 14 days elsewhere.
- The permittee must, at a minimum, inspect, maintain and repair all disturbed surfaces and all erosion and sediment control facilities and soil stabilization measures every day work is performed on the site and at least weekly until land-disturbing activity has ceased. Thereafter, the permittee must perform these responsibilities at least weekly until vegetative cover is established. The permittee will maintain a log of activities under this section for inspection by the District on request.
- For any in water work, potential transfer of aquatic species (e.g. zebra mussels, Curatella, etc.) shall be limited to the minimum extent possible.
- After inspection of all erosion prevention/sediment control facilities and soil stabilization measures, the permittee may replace or supplement non-functional BMPs with functional BMPs within 48 hours of discovery and prior to the next rainfall event or as soon as possible. When active land-disturbing activities are not underway, inspection and these responsibilities shall take place weekly until vegetative cover is established. Also a log of inspection and repair activities shall be maintained and available per request of the watershed district (RPCVDO).
- No activity affecting the bed or banks of a protected water may be conducted between March 15 and June 15 on watersources, or between April 1 and June 30 on all other watersources, to minimize impacts on fish spawning and migration.
- Banks must be stabilized immediately after completion of permitted work and re-vegetated as soon as growing conditions allow.

EROSION CONTROL LEGEND

SYMBOL	DESCRIPTION
[Pattern]	RANDOM SWPPV CLASS III
[Line]	PERIMETER CONTROL
[Line]	BL FENCE
[Circle]	STORM DRAIN INLET PROTECTION
[Pattern]	TURF REINFORCEMENT MAT, CATEGORY 3N
[Pattern]	STABILIZED CONSTRUCTION EOT
[Pattern]	EROSION CONTROL BLANKET, CATEGORY 3N
[Box]	CONCRETE WASHOUT AREA
[Line]	ROCK CHECK
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)

EROSION CONTROL DOES NOT ACT AS FILL.
 SEE SITE RESTORATION PLAN FOR FINAL TOP OF FINISHMENT.
 SLOPES 1:1 OR GREATER MUST BE STABILIZED IMMEDIATELY FOLLOWING EXCAVATION.
 NOTE: SWPPV COVERAGE INCLUDES ELECTRIC, GAS, TELEPHONE, AND CABLE INSTALLATION. EACH COMPANY OR THEIR SUBCONTRACTOR IS RESPONSIBLE TO FOLLOW THE REQUIREMENTS OF THE INSTALLATION OF SEEDING/SOIL MULCHING DURING CONSTRUCTION OF EACH UTILITY.



EROSION CONTROL LEGEND

SYMBOL	DESCRIPTION
[Pattern]	RANDOM SWPPV CLASS III
[Line]	PERIMETER CONTROL
[Line]	BL FENCE
[Circle]	STORM DRAIN INLET PROTECTION
[Pattern]	TURF REINFORCEMENT MAT, CATEGORY 3N
[Pattern]	STABILIZED CONSTRUCTION EOT
[Pattern]	EROSION CONTROL BLANKET, CATEGORY 3N
[Box]	CONCRETE WASHOUT AREA
[Line]	ROCK CHECK
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)

EROSION CONTROL DOES NOT ACT AS FILL.
 SEE SITE RESTORATION PLAN FOR FINAL TOP OF FINISHMENT.
 SLOPES 1:1 OR GREATER MUST BE STABILIZED IMMEDIATELY FOLLOWING EXCAVATION.
 NOTE: SWPPV COVERAGE INCLUDES ELECTRIC, GAS, TELEPHONE, AND CABLE INSTALLATION. EACH COMPANY OR THEIR SUBCONTRACTOR IS RESPONSIBLE TO FOLLOW THE REQUIREMENTS OF THE INSTALLATION OF SEEDING/SOIL MULCHING DURING CONSTRUCTION OF EACH UTILITY.

EROSION CONTROL LEGEND

SYMBOL	DESCRIPTION
[Pattern]	RANDOM SWPPV CLASS III
[Line]	PERIMETER CONTROL
[Line]	BL FENCE
[Circle]	STORM DRAIN INLET PROTECTION
[Pattern]	TURF REINFORCEMENT MAT, CATEGORY 3N
[Pattern]	STABILIZED CONSTRUCTION EOT
[Pattern]	EROSION CONTROL BLANKET, CATEGORY 3N
[Box]	CONCRETE WASHOUT AREA
[Line]	ROCK CHECK
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)

EROSION CONTROL DOES NOT ACT AS FILL.
 SEE SITE RESTORATION PLAN FOR FINAL TOP OF FINISHMENT.
 SLOPES 1:1 OR GREATER MUST BE STABILIZED IMMEDIATELY FOLLOWING EXCAVATION.
 NOTE: SWPPV COVERAGE INCLUDES ELECTRIC, GAS, TELEPHONE, AND CABLE INSTALLATION. EACH COMPANY OR THEIR SUBCONTRACTOR IS RESPONSIBLE TO FOLLOW THE REQUIREMENTS OF THE INSTALLATION OF SEEDING/SOIL MULCHING DURING CONSTRUCTION OF EACH UTILITY.

EROSION CONTROL LEGEND

SYMBOL	DESCRIPTION
[Pattern]	RANDOM SWPPV CLASS III
[Line]	PERIMETER CONTROL
[Line]	BL FENCE
[Circle]	STORM DRAIN INLET PROTECTION
[Pattern]	TURF REINFORCEMENT MAT, CATEGORY 3N
[Pattern]	STABILIZED CONSTRUCTION EOT
[Pattern]	EROSION CONTROL BLANKET, CATEGORY 3N
[Box]	CONCRETE WASHOUT AREA
[Line]	ROCK CHECK
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)

EROSION CONTROL DOES NOT ACT AS FILL.
 SEE SITE RESTORATION PLAN FOR FINAL TOP OF FINISHMENT.
 SLOPES 1:1 OR GREATER MUST BE STABILIZED IMMEDIATELY FOLLOWING EXCAVATION.
 NOTE: SWPPV COVERAGE INCLUDES ELECTRIC, GAS, TELEPHONE, AND CABLE INSTALLATION. EACH COMPANY OR THEIR SUBCONTRACTOR IS RESPONSIBLE TO FOLLOW THE REQUIREMENTS OF THE INSTALLATION OF SEEDING/SOIL MULCHING DURING CONSTRUCTION OF EACH UTILITY.

EROSION CONTROL LEGEND

SYMBOL	DESCRIPTION
[Pattern]	RANDOM SWPPV CLASS III
[Line]	PERIMETER CONTROL
[Line]	BL FENCE
[Circle]	STORM DRAIN INLET PROTECTION
[Pattern]	TURF REINFORCEMENT MAT, CATEGORY 3N
[Pattern]	STABILIZED CONSTRUCTION EOT
[Pattern]	EROSION CONTROL BLANKET, CATEGORY 3N
[Box]	CONCRETE WASHOUT AREA
[Line]	ROCK CHECK
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)

EROSION CONTROL DOES NOT ACT AS FILL.
 SEE SITE RESTORATION PLAN FOR FINAL TOP OF FINISHMENT.
 SLOPES 1:1 OR GREATER MUST BE STABILIZED IMMEDIATELY FOLLOWING EXCAVATION.
 NOTE: SWPPV COVERAGE INCLUDES ELECTRIC, GAS, TELEPHONE, AND CABLE INSTALLATION. EACH COMPANY OR THEIR SUBCONTRACTOR IS RESPONSIBLE TO FOLLOW THE REQUIREMENTS OF THE INSTALLATION OF SEEDING/SOIL MULCHING DURING CONSTRUCTION OF EACH UTILITY.

EROSION CONTROL LEGEND

SYMBOL	DESCRIPTION
[Pattern]	RANDOM SWPPV CLASS III
[Line]	PERIMETER CONTROL
[Line]	BL FENCE
[Circle]	STORM DRAIN INLET PROTECTION
[Pattern]	TURF REINFORCEMENT MAT, CATEGORY 3N
[Pattern]	STABILIZED CONSTRUCTION EOT
[Pattern]	EROSION CONTROL BLANKET, CATEGORY 3N
[Box]	CONCRETE WASHOUT AREA
[Line]	ROCK CHECK
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)

EROSION CONTROL DOES NOT ACT AS FILL.
 SEE SITE RESTORATION PLAN FOR FINAL TOP OF FINISHMENT.
 SLOPES 1:1 OR GREATER MUST BE STABILIZED IMMEDIATELY FOLLOWING EXCAVATION.
 NOTE: SWPPV COVERAGE INCLUDES ELECTRIC, GAS, TELEPHONE, AND CABLE INSTALLATION. EACH COMPANY OR THEIR SUBCONTRACTOR IS RESPONSIBLE TO FOLLOW THE REQUIREMENTS OF THE INSTALLATION OF SEEDING/SOIL MULCHING DURING CONSTRUCTION OF EACH UTILITY.

EROSION CONTROL LEGEND

SYMBOL	DESCRIPTION
[Pattern]	RANDOM SWPPV CLASS III
[Line]	PERIMETER CONTROL
[Line]	BL FENCE
[Circle]	STORM DRAIN INLET PROTECTION
[Pattern]	TURF REINFORCEMENT MAT, CATEGORY 3N
[Pattern]	STABILIZED CONSTRUCTION EOT
[Pattern]	EROSION CONTROL BLANKET, CATEGORY 3N
[Box]	CONCRETE WASHOUT AREA
[Line]	ROCK CHECK
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)

EROSION CONTROL DOES NOT ACT AS FILL.
 SEE SITE RESTORATION PLAN FOR FINAL TOP OF FINISHMENT.
 SLOPES 1:1 OR GREATER MUST BE STABILIZED IMMEDIATELY FOLLOWING EXCAVATION.
 NOTE: SWPPV COVERAGE INCLUDES ELECTRIC, GAS, TELEPHONE, AND CABLE INSTALLATION. EACH COMPANY OR THEIR SUBCONTRACTOR IS RESPONSIBLE TO FOLLOW THE REQUIREMENTS OF THE INSTALLATION OF SEEDING/SOIL MULCHING DURING CONSTRUCTION OF EACH UTILITY.

EROSION CONTROL LEGEND

SYMBOL	DESCRIPTION
[Pattern]	RANDOM SWPPV CLASS III
[Line]	PERIMETER CONTROL
[Line]	BL FENCE
[Circle]	STORM DRAIN INLET PROTECTION
[Pattern]	TURF REINFORCEMENT MAT, CATEGORY 3N
[Pattern]	STABILIZED CONSTRUCTION EOT
[Pattern]	EROSION CONTROL BLANKET, CATEGORY 3N
[Box]	CONCRETE WASHOUT AREA
[Line]	ROCK CHECK
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)

EROSION CONTROL DOES NOT ACT AS FILL.
 SEE SITE RESTORATION PLAN FOR FINAL TOP OF FINISHMENT.
 SLOPES 1:1 OR GREATER MUST BE STABILIZED IMMEDIATELY FOLLOWING EXCAVATION.
 NOTE: SWPPV COVERAGE INCLUDES ELECTRIC, GAS, TELEPHONE, AND CABLE INSTALLATION. EACH COMPANY OR THEIR SUBCONTRACTOR IS RESPONSIBLE TO FOLLOW THE REQUIREMENTS OF THE INSTALLATION OF SEEDING/SOIL MULCHING DURING CONSTRUCTION OF EACH UTILITY.

EROSION CONTROL LEGEND

SYMBOL	DESCRIPTION
[Pattern]	RANDOM SWPPV CLASS III
[Line]	PERIMETER CONTROL
[Line]	BL FENCE
[Circle]	STORM DRAIN INLET PROTECTION
[Pattern]	TURF REINFORCEMENT MAT, CATEGORY 3N
[Pattern]	STABILIZED CONSTRUCTION EOT
[Pattern]	EROSION CONTROL BLANKET, CATEGORY 3N
[Box]	CONCRETE WASHOUT AREA
[Line]	ROCK CHECK
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)

EROSION CONTROL DOES NOT ACT AS FILL.
 SEE SITE RESTORATION PLAN FOR FINAL TOP OF FINISHMENT.
 SLOPES 1:1 OR GREATER MUST BE STABILIZED IMMEDIATELY FOLLOWING EXCAVATION.
 NOTE: SWPPV COVERAGE INCLUDES ELECTRIC, GAS, TELEPHONE, AND CABLE INSTALLATION. EACH COMPANY OR THEIR SUBCONTRACTOR IS RESPONSIBLE TO FOLLOW THE REQUIREMENTS OF THE INSTALLATION OF SEEDING/SOIL MULCHING DURING CONSTRUCTION OF EACH UTILITY.

EROSION CONTROL LEGEND

SYMBOL	DESCRIPTION
[Pattern]	RANDOM SWPPV CLASS III
[Line]	PERIMETER CONTROL
[Line]	BL FENCE
[Circle]	STORM DRAIN INLET PROTECTION
[Pattern]	TURF REINFORCEMENT MAT, CATEGORY 3N
[Pattern]	STABILIZED CONSTRUCTION EOT
[Pattern]	EROSION CONTROL BLANKET, CATEGORY 3N
[Box]	CONCRETE WASHOUT AREA
[Line]	ROCK CHECK
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)

EROSION CONTROL DOES NOT ACT AS FILL.
 SEE SITE RESTORATION PLAN FOR FINAL TOP OF FINISHMENT.
 SLOPES 1:1 OR GREATER MUST BE STABILIZED IMMEDIATELY FOLLOWING EXCAVATION.
 NOTE: SWPPV COVERAGE INCLUDES ELECTRIC, GAS, TELEPHONE, AND CABLE INSTALLATION. EACH COMPANY OR THEIR SUBCONTRACTOR IS RESPONSIBLE TO FOLLOW THE REQUIREMENTS OF THE INSTALLATION OF SEEDING/SOIL MULCHING DURING CONSTRUCTION OF EACH UTILITY.

EROSION CONTROL LEGEND

SYMBOL	DESCRIPTION
[Pattern]	RANDOM SWPPV CLASS III
[Line]	PERIMETER CONTROL
[Line]	BL FENCE
[Circle]	STORM DRAIN INLET PROTECTION
[Pattern]	TURF REINFORCEMENT MAT, CATEGORY 3N
[Pattern]	STABILIZED CONSTRUCTION EOT
[Pattern]	EROSION CONTROL BLANKET, CATEGORY 3N
[Box]	CONCRETE WASHOUT AREA
[Line]	ROCK CHECK
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)

EROSION CONTROL DOES NOT ACT AS FILL.
 SEE SITE RESTORATION PLAN FOR FINAL TOP OF FINISHMENT.
 SLOPES 1:1 OR GREATER MUST BE STABILIZED IMMEDIATELY FOLLOWING EXCAVATION.
 NOTE: SWPPV COVERAGE INCLUDES ELECTRIC, GAS, TELEPHONE, AND CABLE INSTALLATION. EACH COMPANY OR THEIR SUBCONTRACTOR IS RESPONSIBLE TO FOLLOW THE REQUIREMENTS OF THE INSTALLATION OF SEEDING/SOIL MULCHING DURING CONSTRUCTION OF EACH UTILITY.

EROSION CONTROL LEGEND

SYMBOL	DESCRIPTION
[Pattern]	RANDOM SWPPV CLASS III
[Line]	PERIMETER CONTROL
[Line]	BL FENCE
[Circle]	STORM DRAIN INLET PROTECTION
[Pattern]	TURF REINFORCEMENT MAT, CATEGORY 3N
[Pattern]	STABILIZED CONSTRUCTION EOT
[Pattern]	EROSION CONTROL BLANKET, CATEGORY 3N
[Box]	CONCRETE WASHOUT AREA
[Line]	ROCK CHECK
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)

EROSION CONTROL DOES NOT ACT AS FILL.
 SEE SITE RESTORATION PLAN FOR FINAL TOP OF FINISHMENT.
 SLOPES 1:1 OR GREATER MUST BE STABILIZED IMMEDIATELY FOLLOWING EXCAVATION.
 NOTE: SWPPV COVERAGE INCLUDES ELECTRIC, GAS, TELEPHONE, AND CABLE INSTALLATION. EACH COMPANY OR THEIR SUBCONTRACTOR IS RESPONSIBLE TO FOLLOW THE REQUIREMENTS OF THE INSTALLATION OF SEEDING/SOIL MULCHING DURING CONSTRUCTION OF EACH UTILITY.

EROSION CONTROL LEGEND

SYMBOL	DESCRIPTION
[Pattern]	RANDOM SWPPV CLASS III
[Line]	PERIMETER CONTROL
[Line]	BL FENCE
[Circle]	STORM DRAIN INLET PROTECTION
[Pattern]	TURF REINFORCEMENT MAT, CATEGORY 3N
[Pattern]	STABILIZED CONSTRUCTION EOT
[Pattern]	EROSION CONTROL BLANKET, CATEGORY 3N
[Box]	CONCRETE WASHOUT AREA
[Line]	ROCK CHECK
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)

EROSION CONTROL DOES NOT ACT AS FILL.
 SEE SITE RESTORATION PLAN FOR FINAL TOP OF FINISHMENT.
 SLOPES 1:1 OR GREATER MUST BE STABILIZED IMMEDIATELY FOLLOWING EXCAVATION.
 NOTE: SWPPV COVERAGE INCLUDES ELECTRIC, GAS, TELEPHONE, AND CABLE INSTALLATION. EACH COMPANY OR THEIR SUBCONTRACTOR IS RESPONSIBLE TO FOLLOW THE REQUIREMENTS OF THE INSTALLATION OF SEEDING/SOIL MULCHING DURING CONSTRUCTION OF EACH UTILITY.

EROSION CONTROL LEGEND

SYMBOL	DESCRIPTION
[Pattern]	RANDOM SWPPV CLASS III
[Line]	PERIMETER CONTROL
[Line]	BL FENCE
[Circle]	STORM DRAIN INLET PROTECTION
[Pattern]	TURF REINFORCEMENT MAT, CATEGORY 3N
[Pattern]	STABILIZED CONSTRUCTION EOT
[Pattern]	EROSION CONTROL BLANKET, CATEGORY 3N
[Box]	CONCRETE WASHOUT AREA
[Line]	ROCK CHECK
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)

EROSION CONTROL DOES NOT ACT AS FILL.
 SEE SITE RESTORATION PLAN FOR FINAL TOP OF FINISHMENT.
 SLOPES 1:1 OR GREATER MUST BE STABILIZED IMMEDIATELY FOLLOWING EXCAVATION.
 NOTE: SWPPV COVERAGE INCLUDES ELECTRIC, GAS, TELEPHONE, AND CABLE INSTALLATION. EACH COMPANY OR THEIR SUBCONTRACTOR IS RESPONSIBLE TO FOLLOW THE REQUIREMENTS OF THE INSTALLATION OF SEEDING/SOIL MULCHING DURING CONSTRUCTION OF EACH UTILITY.

EROSION CONTROL LEGEND

SYMBOL	DESCRIPTION
[Pattern]	RANDOM SWPPV CLASS III
[Line]	PERIMETER CONTROL
[Line]	BL FENCE
[Circle]	STORM DRAIN INLET PROTECTION
[Pattern]	TURF REINFORCEMENT MAT, CATEGORY 3N
[Pattern]	STABILIZED CONSTRUCTION EOT
[Pattern]	EROSION CONTROL BLANKET, CATEGORY 3N
[Box]	CONCRETE WASHOUT AREA
[Line]	ROCK CHECK
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)

EROSION CONTROL DOES NOT ACT AS FILL.
 SEE SITE RESTORATION PLAN FOR FINAL TOP OF FINISHMENT.
 SLOPES 1:1 OR GREATER MUST BE STABILIZED IMMEDIATELY FOLLOWING EXCAVATION.
 NOTE: SWPPV COVERAGE INCLUDES ELECTRIC, GAS, TELEPHONE, AND CABLE INSTALLATION. EACH COMPANY OR THEIR SUBCONTRACTOR IS RESPONSIBLE TO FOLLOW THE REQUIREMENTS OF THE INSTALLATION OF SEEDING/SOIL MULCHING DURING CONSTRUCTION OF EACH UTILITY.

EROSION CONTROL LEGEND

SYMBOL	DESCRIPTION
[Pattern]	RANDOM SWPPV CLASS III
[Line]	PERIMETER CONTROL
[Line]	BL FENCE
[Circle]	STORM DRAIN INLET PROTECTION
[Pattern]	TURF REINFORCEMENT MAT, CATEGORY 3N
[Pattern]	STABILIZED CONSTRUCTION EOT
[Pattern]	EROSION CONTROL BLANKET, CATEGORY 3N
[Box]	CONCRETE WASHOUT AREA
[Line]	ROCK CHECK
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)

EROSION CONTROL DOES NOT ACT AS FILL.
 SEE SITE RESTORATION PLAN FOR FINAL TOP OF FINISHMENT.
 SLOPES 1:1 OR GREATER MUST BE STABILIZED IMMEDIATELY FOLLOWING EXCAVATION.
 NOTE: SWPPV COVERAGE INCLUDES ELECTRIC, GAS, TELEPHONE, AND CABLE INSTALLATION. EACH COMPANY OR THEIR SUBCONTRACTOR IS RESPONSIBLE TO FOLLOW THE REQUIREMENTS OF THE INSTALLATION OF SEEDING/SOIL MULCHING DURING CONSTRUCTION OF EACH UTILITY.

EROSION CONTROL LEGEND

SYMBOL	DESCRIPTION
[Pattern]	RANDOM SWPPV CLASS III
[Line]	PERIMETER CONTROL
[Line]	BL FENCE
[Circle]	STORM DRAIN INLET PROTECTION
[Pattern]	TURF REINFORCEMENT MAT, CATEGORY 3N
[Pattern]	STABILIZED CONSTRUCTION EOT
[Pattern]	EROSION CONTROL BLANKET, CATEGORY 3N
[Box]	CONCRETE WASHOUT AREA
[Line]	ROCK CHECK
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	EXISTING CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)
[Line]	PROPOSED CONTOUR (MAJOR INTERVAL)

EROSION CONTROL DOES NOT ACT AS FILL.
 SEE SITE RESTORATION PLAN FOR FINAL TOP OF FINISHMENT.
 SLOPES 1

EROSION CONTROL LEGEND	
SYMBOL	DESCRIPTION
	RANDOM BREAK CLASS III
	PERIMETER CONTROL
	SILT FENCE
	STORM DRAIN INLET PROTECTION
	TURF REINFORCEMENT MAT CATEGORY 14
	STABILIZED CONSTRUCTION DIRT
	EROSION CONTROL BLANKET CATEGORY 2N
	CONCRETE IMPOUT AREA
	ROCK RIPRAP CHECK
	EXISTING CONTOUR (MINOR INTERVAL)
	EXISTING CONTOUR (MAJOR INTERVAL)
	PROPOSED CONTOUR (MINOR INTERVAL)
	PROPOSED CONTOUR (MAJOR INTERVAL)

ENSURE SWPPM DOES NOT ACT AS FILL.
 PERIMETER CONTROL CAN BE SILT FENCE OR SEDIMENT CONTROL LOSS.
 SEE SEE RESTORATION PLAN FOR FINAL TURF ESTABLISHMENT.
 SLOPES 3:1 OR GREATER MUST BE STABILIZED IMMEDIATELY FOLLOWING EXCAVATION.
 NOTE SWPPP COVERAGE INCLUDES ELECTRICAL, GAS, TELEPHONE AND CABLE INSTALLATION. EACH
 COMPANY OR SUBCONTRACTOR IS RESPONSIBLE TO FOLLOW THE REQUIREMENTS OF THE
 INSTALLATION OF SEWER/STORMWATER MATCHING DURING CONSTRUCTION OF EACH UTILITY.



NOTE:
 THE CLARITY OF THESE PLANS DEPENDS ON THE CLARITY OF THE ORIGINAL PLAN SET AND MAY RESULT IN MISINTERPRETATION.
 I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.
 JEREMY D. FOSS
 DATE: _____ LIC. NO. 58871
 THIS DOCUMENT IS THE PROPERTY OF I & S GROUP, INC. AND MAY NOT BE REPRODUCED OR COPIED OR Duplicated WITHOUT PRIOR WRITTEN CONSENT.

LENNAR
RESERVE AT
AUTUMN WOODS

CHASKA MINNESOTA

REVISION	SCHEDULE	BY
DATE	DESCRIPTION	
3/17/22	CITY COMMENTS	JRS
3/17/22	CITY COMMENTS	JRS
3/17/22	CITY & WATERSEWER COMMENTS	TRK

PROJECT NO. 21-24894
 FILE NAME 21-24894.SWPPP
 DRAWN BY JRS
 DESIGNED BY JRS
 REVIEWED BY JDF
 ORIGINAL ISSUE DATE 11/02/22
 CLIENT PROJECT NO. _____

TITLE
PROPOSED SWPPP
(NW)

SHEET
29
 OF 71



PRELIMINARY NOT FOR CONSTRUCTION

NOTE:
 THE CLARITY OF THESE PLANS DEPENDS ON THE CLARITY OF THE ORIGINAL PLAN SET AND MAY RESULT IN MISINTERPRETATION.

THIS DOCUMENT IS THE PROPERTY OF I & S GROUP, INC. AND MAY NOT BE REPRODUCED, COPIED OR DUPLICATED WITHOUT PRIOR WRITTEN CONSENT.

LENNAR
RESERVE AT
AUTUMN WOODS

CHASKA MINNESOTA

DATE	REVISION	DESCRIPTION
08/20/2020	1	ISSUE FOR PERMITS
08/20/2020	2	CITY COMMENTS
08/20/2020	3	CITY COMMENTS
08/20/2020	4	CITY & WATERSHED COMMENTS
08/20/2020	5	TRK

PROJECT NO: 21-24894
 FILE NAME: 21-24894 SWPPP
 DRAWN BY: JRS
 DESIGNED BY: JRS
 REVIEWED BY: JOF
 ORIGINAL ISSUE DATE: 01/02/22
 CLIENT PROJECT NO.:

TITLE



PROPOSED SWPPP (SW)

SHEET **31** OF 71

EROSION CONTROL LEGEND

SYMBOL	DESCRIPTION
	RANDOM SPACING CLASS III
	PERIMETER CONTROL
	BELT FENCE
	STORM DRAIN INLET PROTECTION
	TURF REINFORCEMENT MAT, CATEGORY 74
	STABILIZED CONSTRUCTION EXIT
	EROSION CONTROL BLANKET, CATEGORY 7N
	CONCRETE WASHOUT AREA
	ROCK RIP CHECK
	EXISTING CONTOUR (MAJOR INTERVAL)
	EXISTING CONTOUR (MINOR INTERVAL)
	PROPOSED CONTOUR (MAJOR INTERVAL)
	PROPOSED CONTOUR (MINOR INTERVAL)


EROSION CONTROL DOES NOT ACT AS FILL.
 PERIMETER CONTROL CAN BE SET FENCE OR SEGMENT CONTROL LOG.
 SEE SITE RESTORATION PLAN FOR FINAL TURF SET FURNISHMENT.
 SLOPES 3:1 OR GREATER MUST BE STABILIZED IMMEDIATELY FOLLOWING EXCAVATION.
 NOTE: SWPPP CONFORMANCE INCLUDES ELECTRIC GAS TELEPHONE. ANCHOR INSTALLATION EACH COMPANY OR THEIR SUBCONTRACTOR IS RESPONSIBLE TO FOLLOW THE REQUIREMENTS OF THE INSTALLATION OF BELTING/STABILIZING DURING CONSTRUCTION OF EACH UTILITY.



EROSION CONTROL LEGEND

SYMBOL	DESCRIPTION
	RANDOM RIPRAP - CLASS III
	PERIMETER CONTROL
	SILT FENCE
	STORM DRAIN INLET PROTECTION
	TURF REINFORCEMENT MAT - CATEGORY 2A
	STABILIZED CONSTRUCTION EXIT
	EROSION CONTROL BLANKET - CATEGORY 2A
	CONCRETE PAD/POUR AREA
	ROCK DITCH CHECK
	EXISTING CONTOUR (MAJOR INTERNAL)
	EXISTING CONTOUR (MAJOR INTERNAL)
	PROPOSED CONTOUR (MAJOR INTERNAL)
	PROPOSED CONTOUR (MAJOR INTERNAL)

ENGINE RPPMP DOES NOT ACT AS TILL.
 PERIMETER CONTROL CAN BE SILT FENCE OR SEDIMENT CONTROL LOG.
 SEE SITE RESTORATION PLAN FOR FINAL TURF ESTABLISHMENT.
 SLOPES 3:1 OR GREATER MUST BE STABILIZED IMMEDIATELY FOLLOWING EXCAVATION.
 NOTE: SWPPP COVERAGE INCLUDES ELECTRIC, GAS, TELEPHONE AND CABLE
 INSTALLATION. EACH COMPANY OR THEIR SUBCONTRACTOR IS RESPONSIBLE TO FOLLOW
 INSTALLATION OCCURS AFTER PRIMARY INSTALLATION OF SEEDING/GRASSING/DRAINAGE
 DURING CONSTRUCTION OF EACH UTILITY.



INLET PROTECTION TYP.

EROSION CONTROL BLANKET TYP. (SHADE)

RODENT PROTECTION

SCALE IN FEET

0 40 80

N



PRELIMINARY NOT FOR CONSTRUCTION

NOTE: THE CLARITY OF THESE PLANS BEING THE PROPERTY OF I & S GROUP, INC. AND MAY NOT BE USED, COPIED OR DUPLICATED WITHOUT PRIOR WRITTEN CONSENT.

PROJECT:

CHASKA MINNESOTA

RESERVE AT AUTUMN WOODS

LENNAR

JEREMY D. FOSS

DATE: U.C. NO. 58271

THIS DOCUMENT IS THE PROPERTY OF I & S GROUP, INC. AND MAY NOT BE USED, COPIED OR DUPLICATED WITHOUT PRIOR WRITTEN CONSENT.

REVISIONS SCHEDULE

DATE	DESCRIPTION	BY
2/24/22	CITY COMMENTS	JRS
3/17/22	CITY & WATERBESH COMMENTS	TTR

PROJECT NO.: 21-24884

FILE NAME: 2488 SWPPP

DRAWN BY: JRS

DESIGNED BY: JRS

REVIEWED BY: JDF

ORIGINAL ISSUE DATE: 11/02/21

CLIENT PROJECT NO.:

TITLE:

PROPOSED SWPPP (SE)

SHEET

32

OF 71

SYMBOL	DESCRIPTION
[Symbol]	REMOVE BITUMINOUS PAVEMENT
[Symbol]	REMOVE CONCRETE PAVEMENT
[Symbol]	REMOVE CONCRETE WALK
[Symbol]	REMOVE GRAVEL SURFACE
[Symbol]	DEMOLISH BUILDING (IF OTHERS)
[Symbol]	CLEAR AND GRUB TREES AND UNDERGROUND

CONTRACTOR SHALL VERIFY LOCATION, DEPTH AND NOTIFICATION OF ALL UTILITIES. PAVEMENT REMOVALS SHALL INCLUDE FULL DEPTH SAWCUT AND SECTION REMOVAL.

NOTES

1 COORDINATE REMOVAL OF EXISTING SEPTIC SYSTEM AND WELL ABANDONMENT WITH CARVER COUNTY.

SYMBOL	DESCRIPTION
[Symbol]	REMOVE BITUMINOUS PAVEMENT
[Symbol]	REMOVE CONCRETE PAVEMENT
[Symbol]	REMOVE CONCRETE WALK
[Symbol]	REMOVE GRAVEL SURFACE
[Symbol]	DEMOLISH BUILDING (IF OTHERS)
[Symbol]	CLEAR AND GRUB TREES AND UNDERGROUND

CONTRACTOR SHALL VERIFY LOCATION, DEPTH AND NOTIFICATION OF ALL UTILITIES. PAVEMENT REMOVALS SHALL INCLUDE FULL DEPTH SAWCUT AND SECTION REMOVAL.

NOTES

1 COORDINATE REMOVAL OF EXISTING SEPTIC SYSTEM AND WELL ABANDONMENT WITH CARVER COUNTY.

SYMBOL	DESCRIPTION
[Symbol]	REMOVE BITUMINOUS PAVEMENT
[Symbol]	REMOVE CONCRETE PAVEMENT
[Symbol]	REMOVE CONCRETE WALK
[Symbol]	REMOVE GRAVEL SURFACE
[Symbol]	DEMOLISH BUILDING (IF OTHERS)
[Symbol]	CLEAR AND GRUB TREES AND UNDERGROUND

CONTRACTOR SHALL VERIFY LOCATION, DEPTH AND NOTIFICATION OF ALL UTILITIES. PAVEMENT REMOVALS SHALL INCLUDE FULL DEPTH SAWCUT AND SECTION REMOVAL.

NOTES

1 COORDINATE REMOVAL OF EXISTING SEPTIC SYSTEM AND WELL ABANDONMENT WITH CARVER COUNTY.

SYMBOL	DESCRIPTION
[Symbol]	REMOVE BITUMINOUS PAVEMENT
[Symbol]	REMOVE CONCRETE PAVEMENT
[Symbol]	REMOVE CONCRETE WALK
[Symbol]	REMOVE GRAVEL SURFACE
[Symbol]	DEMOLISH BUILDING (IF OTHERS)
[Symbol]	CLEAR AND GRUB TREES AND UNDERGROUND

CONTRACTOR SHALL VERIFY LOCATION, DEPTH AND NOTIFICATION OF ALL UTILITIES. PAVEMENT REMOVALS SHALL INCLUDE FULL DEPTH SAWCUT AND SECTION REMOVAL.

NOTES

1 COORDINATE REMOVAL OF EXISTING SEPTIC SYSTEM AND WELL ABANDONMENT WITH CARVER COUNTY.

SYMBOL	DESCRIPTION
[Symbol]	REMOVE BITUMINOUS PAVEMENT
[Symbol]	REMOVE CONCRETE PAVEMENT
[Symbol]	REMOVE CONCRETE WALK
[Symbol]	REMOVE GRAVEL SURFACE
[Symbol]	DEMOLISH BUILDING (IF OTHERS)
[Symbol]	CLEAR AND GRUB TREES AND UNDERGROUND

CONTRACTOR SHALL VERIFY LOCATION, DEPTH AND NOTIFICATION OF ALL UTILITIES. PAVEMENT REMOVALS SHALL INCLUDE FULL DEPTH SAWCUT AND SECTION REMOVAL.

NOTES

1 COORDINATE REMOVAL OF EXISTING SEPTIC SYSTEM AND WELL ABANDONMENT WITH CARVER COUNTY.

SYMBOL	DESCRIPTION
[Symbol]	REMOVE BITUMINOUS PAVEMENT
[Symbol]	REMOVE CONCRETE PAVEMENT
[Symbol]	REMOVE CONCRETE WALK
[Symbol]	REMOVE GRAVEL SURFACE
[Symbol]	DEMOLISH BUILDING (IF OTHERS)
[Symbol]	CLEAR AND GRUB TREES AND UNDERGROUND

CONTRACTOR SHALL VERIFY LOCATION, DEPTH AND NOTIFICATION OF ALL UTILITIES. PAVEMENT REMOVALS SHALL INCLUDE FULL DEPTH SAWCUT AND SECTION REMOVAL.

NOTES

1 COORDINATE REMOVAL OF EXISTING SEPTIC SYSTEM AND WELL ABANDONMENT WITH CARVER COUNTY.

SYMBOL	DESCRIPTION
[Symbol]	REMOVE BITUMINOUS PAVEMENT
[Symbol]	REMOVE CONCRETE PAVEMENT
[Symbol]	REMOVE CONCRETE WALK
[Symbol]	REMOVE GRAVEL SURFACE
[Symbol]	DEMOLISH BUILDING (IF OTHERS)
[Symbol]	CLEAR AND GRUB TREES AND UNDERGROUND

CONTRACTOR SHALL VERIFY LOCATION, DEPTH AND NOTIFICATION OF ALL UTILITIES. PAVEMENT REMOVALS SHALL INCLUDE FULL DEPTH SAWCUT AND SECTION REMOVAL.

NOTES

1 COORDINATE REMOVAL OF EXISTING SEPTIC SYSTEM AND WELL ABANDONMENT WITH CARVER COUNTY.

SYMBOL	DESCRIPTION
[Symbol]	REMOVE BITUMINOUS PAVEMENT
[Symbol]	REMOVE CONCRETE PAVEMENT
[Symbol]	REMOVE CONCRETE WALK
[Symbol]	REMOVE GRAVEL SURFACE
[Symbol]	DEMOLISH BUILDING (IF OTHERS)
[Symbol]	CLEAR AND GRUB TREES AND UNDERGROUND

CONTRACTOR SHALL VERIFY LOCATION, DEPTH AND NOTIFICATION OF ALL UTILITIES. PAVEMENT REMOVALS SHALL INCLUDE FULL DEPTH SAWCUT AND SECTION REMOVAL.

NOTES

1 COORDINATE REMOVAL OF EXISTING SEPTIC SYSTEM AND WELL ABANDONMENT WITH CARVER COUNTY.

SYMBOL	DESCRIPTION
[Symbol]	REMOVE BITUMINOUS PAVEMENT
[Symbol]	REMOVE CONCRETE PAVEMENT
[Symbol]	REMOVE CONCRETE WALK
[Symbol]	REMOVE GRAVEL SURFACE
[Symbol]	DEMOLISH BUILDING (IF OTHERS)
[Symbol]	CLEAR AND GRUB TREES AND UNDERGROUND

CONTRACTOR SHALL VERIFY LOCATION, DEPTH AND NOTIFICATION OF ALL UTILITIES. PAVEMENT REMOVALS SHALL INCLUDE FULL DEPTH SAWCUT AND SECTION REMOVAL.

NOTES

1 COORDINATE REMOVAL OF EXISTING SEPTIC SYSTEM AND WELL ABANDONMENT WITH CARVER COUNTY.

SYMBOL	DESCRIPTION
[Symbol]	REMOVE BITUMINOUS PAVEMENT
[Symbol]	REMOVE CONCRETE PAVEMENT
[Symbol]	REMOVE CONCRETE WALK
[Symbol]	REMOVE GRAVEL SURFACE
[Symbol]	DEMOLISH BUILDING (IF OTHERS)
[Symbol]	CLEAR AND GRUB TREES AND UNDERGROUND

CONTRACTOR SHALL VERIFY LOCATION, DEPTH AND NOTIFICATION OF ALL UTILITIES. PAVEMENT REMOVALS SHALL INCLUDE FULL DEPTH SAWCUT AND SECTION REMOVAL.

NOTES

1 COORDINATE REMOVAL OF EXISTING SEPTIC SYSTEM AND WELL ABANDONMENT WITH CARVER COUNTY.

SYMBOL	DESCRIPTION
[Symbol]	REMOVE BITUMINOUS PAVEMENT
[Symbol]	REMOVE CONCRETE PAVEMENT
[Symbol]	REMOVE CONCRETE WALK
[Symbol]	REMOVE GRAVEL SURFACE
[Symbol]	DEMOLISH BUILDING (IF OTHERS)
[Symbol]	CLEAR AND GRUB TREES AND UNDERGROUND

CONTRACTOR SHALL VERIFY LOCATION, DEPTH AND NOTIFICATION OF ALL UTILITIES. PAVEMENT REMOVALS SHALL INCLUDE FULL DEPTH SAWCUT AND SECTION REMOVAL.

NOTES

1 COORDINATE REMOVAL OF EXISTING SEPTIC SYSTEM AND WELL ABANDONMENT WITH CARVER COUNTY.

SYMBOL	DESCRIPTION
[Symbol]	REMOVE BITUMINOUS PAVEMENT
[Symbol]	REMOVE CONCRETE PAVEMENT
[Symbol]	REMOVE CONCRETE WALK
[Symbol]	REMOVE GRAVEL SURFACE
[Symbol]	DEMOLISH BUILDING (IF OTHERS)
[Symbol]	CLEAR AND GRUB TREES AND UNDERGROUND

CONTRACTOR SHALL VERIFY LOCATION, DEPTH AND NOTIFICATION OF ALL UTILITIES. PAVEMENT REMOVALS SHALL INCLUDE FULL DEPTH SAWCUT AND SECTION REMOVAL.

NOTES

1 COORDINATE REMOVAL OF EXISTING SEPTIC SYSTEM AND WELL ABANDONMENT WITH CARVER COUNTY.

SYMBOL	DESCRIPTION
[Symbol]	REMOVE BITUMINOUS PAVEMENT
[Symbol]	REMOVE CONCRETE PAVEMENT
[Symbol]	REMOVE CONCRETE WALK
[Symbol]	REMOVE GRAVEL SURFACE
[Symbol]	DEMOLISH BUILDING (IF OTHERS)
[Symbol]	CLEAR AND GRUB TREES AND UNDERGROUND

CONTRACTOR SHALL VERIFY LOCATION, DEPTH AND NOTIFICATION OF ALL UTILITIES. PAVEMENT REMOVALS SHALL INCLUDE FULL DEPTH SAWCUT AND SECTION REMOVAL.

NOTES

1 COORDINATE REMOVAL OF EXISTING SEPTIC SYSTEM AND WELL ABANDONMENT WITH CARVER COUNTY.



PRELIMINARY NOT FOR CONSTRUCTION PRELIMINARY NOT FOR CONSTRUCTION

NOTE: THE CLARITY OF THESE PLANS DEPENDS ON THE ACCURACY OF THE SURVEY DATA. THESE PLANS NOT APPEAR IN COLOR. THIS IS NOT AN ORIGINAL PLAN SET AND MAY RESULT IN MISINTERPRETATION.

I HEREBY CERTIFY THAT THE PLAN, SPECIFICATION OR CONTRACT DOCUMENTS ARE THE PROPERTY OF I & S GROUP, INC. AND MAY NOT BE REPRODUCED, COPIED OR DUPLICATED WITHOUT PRIOR WRITTEN CONSENT.

DATE: _____ U.C. NO.: 59871
 PROJECT: _____

LENNAR RESERVE AT AUTUMN WOODS



CHASKA MINNESOTA

REVISION	DATE	DESCRIPTION
1	10/22/22	CITY COMMENTS
2	10/22/22	CITY COMMENTS
3	10/22/22	CITY & WATERBESH COMMENTS
4	10/22/22	TRK


PROJECT NO.	21-24894
FILE NAME	24894.DWG
DRAWN BY	JRS
DESIGNED BY	JRS
REVIEWED BY	JOF
ORIGINAL ISSUE DATE	10/02/22
CLIENT PROJECT NO.	

TITLE
EXISTING SITE AND REMOVAL PLAN

SHEET
33
 OF 71



JULIAN DRIVE



BENCHMARK HYDRANT
T.M.F.H5444

ALL CONSTRUCTION INSIDE
THE BOUNDARIES OF THE
SEPARATE CONSTRUCTION
PROJECT

BENCHMARK HYDRANT
T.M.F.H. 58033

BLUFF CREEK BLVD



NOTE:
THE CLARITY OF THESE PLANS DEPENDS
ON THE ACCURACY OF THE DATA PROVIDED.
IF ANY DISCREPANCIES ARE FOUND, THE
ORIGINAL PLAN SET AND MAY RESULT IN
MISINTERPRETATION.

I HEREBY CERTIFY THAT THE PLAN, SPECIFICATION OR
REPORT WAS PREPARED BY ME OR UNDER MY DIRECT
SUPERVISION AND THAT I AM A LICENSED PROFESSIONAL
ENGINEER UNDER THE LAWS OF THE
STATE OF MINNESOTA.
JEREMY D. FOSS

DATE: _____ LIC. NO.: 59871
THIS DOCUMENT IS THE PROPERTY OF I & S GROUP,
INC. AND MAY NOT BE USED, COPIED OR DUPLICATED
WITHOUT PRIOR WRITTEN CONSENT.

PROJECT:

**LENNAR
RESERVE AT
AUTUMN WOODS**

CHASKA, MINNESOTA

REVISION	DATE	DESCRIPTION
1	2/14/22	CITY COMMENTS
2	2/14/22	CITY COMMENTS
3	3/17/22	CITY & WATERBOD COMMENTS
4		TRK

PROJECT NO.: 21-24894
FILE NAME: 2484 GRACK
DRAWN BY: JRS
DESIGNED BY: JRS
REVIEWED BY: JDF
ORIGINAL ISSUE DATE: 6/10/22
CLIENT PROJECT NO.:

TITLE:

**GRADING PLAN
(OVERALL)**

SHEET
58
OF 71



NOTE:
THE CLARITY OF THESE PLANS DEPENDS ON THE ORIGINAL PLAN SET AND MAY RESULT IN MISINTERPRETATION.
I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.
JEREMY D. FOSS


DATE: _____
LIC. NO.: 59871
THIS DOCUMENT IS THE PROPERTY OF I&S GROUP, INC. AND MAY NOT BE REPRODUCED OR DUPLICATED WITHOUT PRIOR WRITTEN CONSENT.

**LENNAR
RESERVE AT
AUTUMN WOODS**

CHASKA, MINNESOTA	
REVISION	SCHEDULE
DATE	DESCRIPTION
BY	
DATE	CITY COMMENTS
BY	
DATE	CITY & WATERBOD COMMENTS
BY	
DATE	
PROJECT NO.	21-24894
FILE NAME	24894.GRDC
DRAWN BY	JRS
DESIGNED BY	JRS
REVIEWED BY	JRS
ORIGINAL ISSUE DATE	11/02/22
CLIENT PROJECT NO.	

**GRADING PLAN
(NW)**

SHEET
59
OF 71





NOTE: THE CLARITY OF THESE PLANS DEPENDS ON THE CLARITY OF THE ORIGINAL PLAN SET AND THIS IS NOT AN ORIGINAL PLAN SET AND MAY RESULT IN MISINTERPRETATION.

I HEREBY CERTIFY THAT THE PLAN, SPECIFICATION OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.



JEREMY D. FOSS
DATE: LC NO. 59871
THIS DOCUMENT IS THE PROPERTY OF I & S GROUP, INC. AND MAY NOT BE USED, COPIED OR REPRODUCED WITHOUT PRIOR WRITTEN CONSENT.

PROJECT: LENNAR RESERVE AT AUTUMN WOODS
CHASKA, MINNESOTA

Table with columns: REVISION, DATE, DESCRIPTION, BY, DATE, CITY COMMENTS, DATE, CITY COMMENTS, DATE, CITY COMMENTS.

PROJECT NO: 21-24894
FILE NAME: 24894.GRDC
DRAWN BY: JRS
DESIGNED BY: JDF
ORIGINAL ISSUE DATE: 11/02/22
CLIENT PROJECT NO.:

TITLE: GRADING PLAN (NE)
SHEET: 60 OF 71



ALL CONSTRUCTION INSIDE AUDUBON ROW PART OF SEPARATE CONSTRUCTION PROJECT

BENCHMARK MOUNTAIN TAPE 18644

WETLAND
1/ = 919.51

SEE SWPPP PLANS AND DETAILS FOR RAWINE SLOPE PROTECTION AND RESTORATION OF EXISTING RAWINE SLOPE

BASIN F
BOTTOM=936.50
HNL=935.96



NOTE: THE CLARITY OF THESE PLANS BEYOND THE ORIGINAL PLAN SET AND MAY RESULT IN MISINTERPRETATION.

I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

JEREMY D. FOSS

DATE: LIC. NO. 59871

THIS DOCUMENT IS THE PROPERTY OF I & S GROUP, INC. AND MAY NOT BE REPRODUCED OR COPIED WITHOUT PRIOR WRITTEN CONSENT.


PROJECT: LENNAR RESERVE AT AUTUMN WOODS

Table with 2 columns: REVISION, DESCRIPTION. Includes rows for DATE, CITY COMMENTS, and CITY & WATERBOD COMMENTS.

PROJECT NO: 21-24894
FILE NAME: 24894.GRDC
DRAWN BY: JRS
DESIGNED BY: JRS
REVIEWED BY: JRS
ORIGINAL ISSUE DATE: 11/02/22
CLIENT PROJECT NO.:

TITLE: GRADING PLAN (SW)

SHEET: 61 OF 71





NOTE: THE CLARITY OF THESE PLANS DEPENDS ON THE CLARITY OF THE ORIGINAL PLAN SET AND MAY RESULT IN MISINTERPRETATION.

I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.
JEREMY D. FOSS
DATE: _____
LIC. NO.: 59871
THIS DOCUMENT IS THE PROPERTY OF I & S GROUP, INC. AND MAY NOT BE REPRODUCED, COPIED OR DULICATED WITHOUT PRIOR WRITTEN CONSENT.

LENNAR RESERVE AT AUTUMN WOODS


CHASKA MINNESOTA

REVISION	DATE	DESCRIPTION
BY		
DATE		
BY		
DATE		
BY		
DATE		

PROJECT NO: 21-24984
 FILE NAME: 24984.GRACE
 DRAWN BY: JRS
 DESIGNED BY: JRS
 CHECKED BY: JDF
 ORIGINAL ISSUE DATE: 11/03/22
 CLIENT PROJECT NO: _____

TITLE

GRADING PLAN (SE)



RESTORATION SCHEDULE

REEL LINE	QTY	DESCRIPTION
67482 SF	EMERGENCY WETLAND (MNDOT 34-41)	
66486 SF	MISC PRUNE GENERAL (MNDOT 34-41)	
103,842 SF	STORMWATER SOUTH AND WEST (MNDOT 34-26)	
64,481 SF	WET MEADOW SOUTH & WEST (MNDOT 34-27)	
86,625 SF	SALT TOLERANT SOD	

CODE REQUIREMENTS SUMMARY

- STREET TREE REQUIREMENTS:**
- 1 OVERSTORY TREE ON EACH SIDE OF THE STREET FOR EVERY 90 FEET OF CENTERLINE
 - 2,370 TOTAL TREES
 - 188 TREES REQUIRED = 188
 - 188 TREES PROVIDED = 188
- SCREEN REQUIREMENTS:**
- MATERIALS AND METHODS AND COLLECTORS WITH PLANT MATERIAL TO PROVIDE A VISUAL SCREEN
 - TREES PROVIDED FOR SCREENING: 78
- EXISTING TREES:**
- (72) SURVIVED TREES MEETING ORBITHANCE THRESHOLD
 - (140) TOTAL PROPOSED REMOVALS
- SIGNIFICANT TREES:**
- (26) TOTAL TREES
 - (45) PROPOSED REMOVALS (7) OF WHICH ARE DEAD
- SOD REQUIRED IN DRIVE-WAY AND IN FRONT YARDS:**
- SOD TO BE PLACED BY BUILDER WITH HOME CONSTRUCTION

PLANT SCHEDULE

EMERGENCY TREE	QTY	BOTANICAL COMMON NAME	SIZE	ROOT
AF	8	ARBE COCCOLEA WHITE FR	6 FT W	8.8.0
AF	14	ARBE FRASERI PRINSEPIER	6 FT W	8.8.0
AF	14	QUERCUS ELIENSIS BARKER'S OAK	6 FT W	8.8.0
AF	17	PRUNUS INDICA AUSTRIAN PINE	6 FT W	8.8.0
AF	14	PRUNUS BESNAIA RED PINE	6 FT W	8.8.0
AF	13	TRIALIA OCCIDENTALIS TECHY TONY ARBORVITAE	6 FT W	8.8.0
OVERSTORY TREES	QTY	BOTANICAL COMMON NAME	SIZE	ROOT
AM	17	ADONIS FREEMANI PREFALL INFALL WALLE	25' CA	8.8.0
AM	15	QUERCUS ELIENSIS BARKER'S OAK	25' CA	8.8.0
AM	17	BETULA NIGRA CULLY TM HERITAGE BIRCH	25' CA	8.8.0
AM	11	QUERCUS ELIENSIS BARKER'S OAK	25' CA	8.8.0
AM	26	QUERCUS TRILICOCOS E. NERMS THORNLESS HONEY LOCUST	25' CA	8.8.0
AM	17	QUERCUS ELIENSIS BARKER'S OAK	25' CA	8.8.0
AM	15	QUERCUS ELIENSIS BARKER'S OAK	25' CA	8.8.0
AM	20	OSTRYA VIRGINICA AMERICAN HOPHORNBEAM	25' CA	8.8.0
AM	4	QUERCUS ALBA WHITE OAK	25' CA	8.8.0
AM	12	QUERCUS BICOLORE SWAMP WHITE OAK	25' CA	8.8.0
AM	6	QUERCUS ELIENSIS BARKER'S OAK	25' CA	8.8.0
AM	15	QUERCUS ELIENSIS BARKER'S OAK	25' CA	8.8.0
AM	12	QUERCUS ROBUR ALBA COMMON HAWKWOOD	25' CA	8.8.0
AM	4	QUERCUS RUBRA RED OAK	25' CA	8.8.0
AM	20	TRIALIA OCCIDENTALIS TECHY TONY ARBORVITAE	25' CA	8.8.0
AM	23	ULMUS PARVIFOLIUS PYRAMIDAL	25' CA	8.8.0



RESTORATION AND PLANTING PLAN

LENNAR RESERVE AT AUTUMN WOODS

CHASKA MINNESOTA

DATE: _____ LIC. NO. 59871

THIS DOCUMENT IS THE PROPERTY OF I & S GROUP, INC. AND MAY NOT BE REPRODUCED, COPIED OR DULICATED WITHOUT PRIOR WRITTEN CONSENT.

PROJECT: _____

REVISION SCHEDULE

NO.	DATE	DESCRIPTION
1	10/20/22	CITY COMMENTS
2	11/17/22	CITY & WATERBESH COMMENTS

PROJECT NO: 21-24884

FILE NAME: 24884.LANDSCAPE

DRAWN BY: JRS

DESIGNED BY: JRS

REVIEWED BY: JRS

ORIGINAL ISSUE DATE: 10/20/22

CLIENT PROJECT NO.:

RESTORATION AND PLANTING PLAN

SHEET **66** OF 71



NOTE: THE CLARITY OF THESE PLANS DEPENDS ON THE CLARITY OF THE ORIGINAL PLAN SET AND MAY RESULT IN MISINTERPRETATION.

I HEREBY CERTIFY THAT THE PLAN, SPECIFICATION OR CONTRACT DOCUMENTS AND PARTS THEREOF ARE THE WORK OF A PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

JEREMY D. FOSS
DATE: _____ LIC. NO. 59871

THIS DOCUMENT IS THE PROPERTY OF ILS GROUP, INC. AND MAY NOT BE REPRODUCED OR COPIED WITHOUT PRIOR WRITTEN CONSENT.

PROJECT: **LENNAR RESERVE AT AUTUMN WOODS**

CHASKA, MINNESOTA

DATE	BY	DESCRIPTION
10/20/22	JRS	CITY COMMENTS
10/20/22	JRS	CITY & WATER-SHED COMMENTS
10/20/22	JRS	CITY & WATER-SHED COMMENTS
10/20/22	JRS	CITY & WATER-SHED COMMENTS

PROJECT NO: 21-24984
FILE NAME: 24984 OVERALL
DRAWN BY: JRS
DESIGNED BY: JRS
REVIEWED BY: JRS
ORIGINAL ISSUE DATE: 10/20/22
CLIENT PROJECT NO: _____

TITLE: **PLANTING AND UTILITY PLAN (OVERALL)**

SHEET: **67** OF 71

SCALE IN FEET: 0 100 200

PLANT SCHEDULE

EVERGREEN TREES	QTY	BOTANICAL COMMON NAME	SIZE	ROOT
AC	8	AMERICAN CORNCOCKLE WHITE PINK	6 FT W x 8.8 D	8.8 D
AL	14	AMERICAN PINE	6 FT W x 8.8 D	8.8 D
PE	14	PIKEA QUILICOIDES VATA BLACK HILLS SPRUCE	6 FT W x 8.8 D	8.8 D
PR	17	PINK BIRCH	6 FT W x 8.8 D	8.8 D
PR	14	PINK BIRCH	6 FT W x 8.8 D	8.8 D
TR	13	TRIAL OCCIDENTALIS TECHY TERRY ARGENTIVE	6 FT W x 8.8 D	8.8 D
DECIDUOUS TREES	QTY	BOTANICAL COMMON NAME	SIZE	ROOT
CA	17	CORNUS FLORIDA PRES'ALL	25' CA x 8.8 D	8.8 D
CA	15	ARJUNUS X AUTUMN SENSORY AUTUMN SPUR UNDER BUCKEYE	25' CA x 8.8 D	8.8 D
CA	17	BETULA NIGRA CULTIVAR 'NINE BRANCH'	25' CA x 8.8 D	8.8 D
CA	11	CATALPA SPECIOSA NORTHERN CATALPA	25' CA x 8.8 D	8.8 D
CA	26	QUERCUS TRILICORNATOS F. AEMERIS THORNLESS HONEY LOCUST	25' CA x 8.8 D	8.8 D
CA	17	QUERCUS ALBA SWAMP WHITE OAK	25' CA x 8.8 D	8.8 D
CA	15	QUERCUS ALBA SWAMP WHITE OAK	25' CA x 8.8 D	8.8 D
CA	20	OSTREA VIRGINIANA ASHLEAF HOP SPRUCE	25' CA x 8.8 D	8.8 D
CA	4	QUERCUS ALBA WHITE OAK	25' CA x 8.8 D	8.8 D
CA	12	QUERCUS BICOLOR SWAMP WHITE OAK	25' CA x 8.8 D	8.8 D
CA	6	QUERCUS ELIPSEOLUS NORTHERN PINE OAK	25' CA x 8.8 D	8.8 D
CA	15	QUERCUS ELIPSEOLUS SWAMP WHITE OAK	25' CA x 8.8 D	8.8 D
CA	12	QUERCUS ROBUR ALBA CUMBOCHMET TM	25' CA x 8.8 D	8.8 D
CA	4	QUERCUS RUBRA RED OAK	25' CA x 8.8 D	8.8 D
CA	20	TILIA CORDATA GREENPINE GREENPINE LITTLE LEAF LINDEN	25' CA x 8.8 D	8.8 D
CA	23	ILAEUS PATRONT PATRONT ELM	25' CA x 8.8 D	8.8 D



WY P&G 12021201 31UG 1014

SITE PREPARATION

HERBICIDE APPLICATION:

1. Weed Identification: Site evaluation shall be conducted prior to site preparation to determine the undesirable and non-native weeds on site. This site evaluation will either be done by the Contractor or the Architect/Engineer's Representative.
2. Weed Eradication: All existing undesirable and non-native plant vegetation should be killed and/or removed from the site with multiple herbicide applications. Common weed species found in wetlands include Reed Canary Grass, non-native Phragmites, and Cattails.
3. Herbicide Selection: In riparian or wetland areas, water-safe herbicides approved for use near water must be used. Pre-emergent herbicides should not be used. For more detailed guidance on herbicide selection, see Appendix 5B of the BWSR Minnesota Wetland Restoration Guide.
3. Herbicide Application: All herbicides should be applied in accordance with state and federal regulations and manufacturer's instructions. Herbicides should not be applied during or within 72 hours of a rain event or when wind velocities exceed 5 miles per hour. Ideally, 3 herbicide applications would be conducted in spring, summer, and fall with seeding occurring in early winter. This latest schedule may need to be adapted to align with the construction timeline.

SEEDBED PREPARATION

1. All restoration areas should be free of any rocks, crop residue, trash, or debris. Mow or harvest oats if used as temporary erosion control.
2. Construction and grading activities can compact the soil. Prior to seeding, any compacted areas must be prepared to about 1.0 to 1.5 inches. If the seedbed is too compacted, decompaction is recommended. On some areas, equipment at right angles to the direction of surface drainage. The disc should not invert the soil. Avoid soil inversion and tilling to preserve soil biology and prevent emergence of weed seeds.
3. Discing may need to be followed by rolling or cultipacking to firm the seedbed. If the seedbed is too loose and fluffy, seeds will be placed too deep for proper germination.

WETLAND SEEDING

1. Seeding will only be conducted after all grading, construction, and site preparation activities are completed. The Contractor must wait 3 days after glyphosate application to seed native species. If other herbicides have been used on site, consult the manufacturer's recommendation for safe re-entry period prior to seeding. Some herbicides can stay in the soil for months and hinder the germination of native plants.
2. Seeding should be conducted by hand broadcasting, mechanical broadcasting, or drilling.
3. The Contractor is responsible for calibrating equipment to deliver seed at the specified rate and to operate equipment in a manner necessary to evenly distribute the seeds over the specified area at the specified rate.
4. Seeded areas may have one pass with a roller or cultipacker to firm the soil and ensure good seed-to-soil contact.
5. Do not apply fertilizers in the areas seeded with native grasses and wildflowers.
6. If necessary, plant a cover crop and/or apply Types 3 weed-free straw mulch for temporary erosion control. Use Oats as a cover crop in spring and summer, use Winter Wheat as a cover crop in fall.

TABLE 1: WET MEADOW SEED MIX 34-274

Common Name	Scientific Name	Rate (kg/ha)	Rate (lb/ac)	% of Mix (by wt)	Seedly (kg/ha)
GRASSES					
Erigeron Bromus	Bromus ciliaris	1.23	1.10	9.18%	445
Bluejoint Grass	Calamagrostis canadensis	0.06	0.05	0.41%	500
Virginia Wild Rye	Elymus virginicus	1.12	1.00	8.37%	155
Ridge Cut Grass	Lernaea eryzoides	0.28	0.25	2.07%	310
Tall Mann Grass	Glyceris grandis	0.17	0.15	1.26%	390
Field Mann Grass	Glyceris striata	0.15	0.14	1.13%	330
Field Doggrass	Poa pratensis	0.39	0.35	2.83%	350
Total Grasses		3.38	3.00	25.00%	3740
SEDGES + BUSHES					
Bristly Sedge	Carex comosa	0.24	0.21	1.78%	236
Pointed Blunt Sedge	Carex apparia	0.06	0.05	0.43%	160
Wetland Sedge	Carex spicata	0.19	0.17	1.40%	210
Wetland Sedge	Carex lasiocarpa	0.19	0.17	1.40%	210
Flax Sedge	Carex lasiocarpa	0.16	0.14	1.13%	500
Path Rush	Alisma Minuta	0.04	0.04	0.34%	1500
Dark Green Bulrush	Scirpus atrovirens	0.20	0.18	1.48%	3000
Woolgrass	Scirpus cyperinus	0.09	0.08	0.67%	5000
Total Sedges and Rushes		1.01	0.90	7.44%	10590
FORBS					
Marsh Milkweed	Asclepias incarnata	0.27	0.24	2.03%	943
Common Bontweed	Elythium perfoliatum	0.02	0.02	0.18%	130
Grass-leaved Goldenrod	Elythium agrippinifolium	0.01	0.01	0.08%	100
Spotted Joe-Pye Weed	Eryngium yuccifolium	0.02	0.02	0.18%	075
Sheepshead	Helium autumnale	0.03	0.03	0.23%	130
Black Oyster Shell	Thalictrum dasycarpum	0.02	0.02	0.16%	240
Great Blue Lobelia	Lobelia spicata	0.02	0.02	0.13%	240
Blue Morney Flower	Minutella ringens	0.01	0.01	0.07%	680
Virginia Mountain Mint	Pycnanthemum virginianum	0.07	0.06	0.53%	510
Great Goldenrod	Solidago gigantea	0.02	0.02	0.14%	150
Eastern Panicled Aster	Syrphidochloa lanceolatum	0.03	0.03	0.22%	150
Yellowstemmed Aster	Syrphidochloa astromum	0.03	0.03	0.22%	150
Yellowstemmed Aster	Syrphidochloa spyzum	0.04	0.04	0.32%	190
Blue Vervain	Verbena hastata	0.15	0.13	1.12%	481
Ironweed	Veronica ascarifolia	0.03	0.03	0.28%	030
Culvert's Foot	Veronicastrum virginicum	0.01	0.01	0.12%	420
Golden Alexanders	Zizia aurea	0.28	0.25	2.05%	100
Total Forbs		2.3	2.10	17.19%	3910
COVER CROP		7.85	7.00	58.37%	312
Total:		13.45	12.00	100.00%	18548

Purpose: Wet meadow / Sedge meadow reconstruction for wetland mitigation or ecological restoration projects

Planting Area: Tallgrass Aspen Parklands, Prairie Parkland, and Eastern Broadleaf Forest Provinces, MPOD Districts (West), 36, 4, Metro, 5, 7 & 8.

VEGETATION ESTABLISHMENT

YEAR 1

1. During the first growing season after planting, all seeded areas must be kept mowed to the extent possible to help control weed growth, allow sunlight to penetrate to the soil surface, and encourage root development on the native species. Mowing should be done in late summer or early fall. Mowing should be done in late summer or early fall to reduce the risk of soil erosion and to compact the wet soil. Some sites may be too wet to allow mowing without causing rut or compaction in which case it is advisable not to mow the area.
2. Mow to a height of 6-8 inches whenever the vegetation reaches 10-12 inches tall, approximately once every 1-4 weeks depending on the rate of vegetation growth.
3. Use of a fall mower or stalk chopper to prevent smothering of native plant seedlings. If a fall mower or stalk chopper is not available, the vegetation must be hayed/bagged and removed from the site, or mowing must be frequent enough to ensure the vegetation is small enough to compost itself back into the site without creating a thick mulch and negatively affecting the native plant seedlings.
4. Spot-treat weeds such as Reed Canary Grass and Canada Thistle with an appropriate herbicide.
5. Do not hand pull any weeds during the first growing season as to not disturb the soil or native seedlings.

LONG-TERM MANAGEMENT

YEAR 2

1. Mow to a height of 6-8 inches up to two times in the spring and early summer to help control weed growth.
2. Spot-treat aggressive perennial weeds such as Reed Canary Grass and Canada Thistle with an appropriate herbicide.

YEAR 3 + BEYOND

1. Periodically monitor wetland for weeds and hydrological issues at least once per year. Healthy stands of native vegetation are important to provide wildlife habitat, capture nutrient runoff, and reduce peak flows during large rain events. If weeds are present, they should be removed. If hydrological issues are present, they should be corrected, and any out-competing invasive species. On-site observations are necessary to spot problems and get them resolved as soon as possible.
2. Spot-treat weeds such as Reed Canary Grass and Canada Thistle with an appropriate herbicide.
3. Consider periodic disturbances such as prescribed fire, mowing, or grazing once every 3-5 years. By necessity, some amount of flexibility is needed when managing wetland restorations. Changes in management strategies and timing are often necessary to react to changing or unexpected project conditions, whether they are due to natural circumstances or manmade circumstances. Adaptive management solutions tailored to site observations are encouraged.



NOTE: THE CLARITY OF THESE PLANS DEPENDS ON THE ACCURACY OF THE SURVEY DATA. ORIGINAL PLAN SET AND MAY RESULT IN MISINTERPRETATION.

WE HEREBY CERTIFY THAT THE PLAN, SPECIFICATION OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

JEREMY D. FOSS

DATE: _____ LIC. NO.: 59271

THIS DOCUMENT IS THE PROPERTY OF ILS GROUP, INC. AND MAY NOT BE REPRODUCED OR COPIED WITHOUT WRITTEN PERMISSION.

**LENNAR
RESERVE AT
AUTUMN WOODS**

CHASKA MINNESOTA

DATE	REVISION	SCHEDULE
10/20/22	CITY COMMENTS	BY
10/20/22	CITY COMMENTS	JRS
10/20/22	CITY & WATERBED COMMENTS	TRK

PROJECT NO.:	21-24984
FILE NAME:	24984 WETLAND REST
DRAWN BY:	JRS
DESIGNED BY:	JRS
REVIEWED BY:	JRS
ORIGINAL ISSUE DATE:	10/02/22
CLIENT PROJECT NO.:	

**TITLE
RESTORATION
AND PLANTING
PLAN
(WETLAND D)**

SHEET

69

OF 71



NOTE:
 THE CLARITY OF THESE PLANS DEPENDS ON THE CLARITY OF THE ORIGINAL PLAN SET AND MAY RESULT IN MISINTERPRETATION.

I HEREBY CERTIFY THAT THE PLAN, SPECIFICATION OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.
 JEREMY D. FOSS
 DATE: _____ LIC. NO.: 59871
 THIS DOCUMENT IS THE PROPERTY OF I & S GROUP, INC. AND MAY NOT BE REPRODUCED OR DUPLICATED WITHOUT PRIOR WRITTEN CONSENT.

**LENNAR
 RESERVE AT
 AUTUMN WOODS**

CHASKA, MINNESOTA

REVISION	DATE	DESCRIPTION
1	10/23/20	CITY COMMENTS
2	11/02/20	CITY COMMENTS
3	11/02/20	CITY & WATERBED COMMENTS


PROJECT NO.	21-24894
FILE NAME	24894 TREE PRES
DRAWN BY	JRS
DESIGNED BY	JRS
ORIGINAL ISSUE DATE	11/02/20
CLIENT PROJECT NO.	

TITLE

**OVERALL TREE
 PRESERVATION**

SHEET **70** OF 71

TREE REMOVAL LEGEND	
SYMBOL	DESCRIPTION
	EXCELLENT
	GOOD
	FAIR
	POOR
	DEAD





NOTE: THE CLARITY OF THESE PLANS DEPENDS ON THE ACCURACY OF THE DATA PROVIDED. THIS IS NOT AN ORIGINAL PLAN SET AND MAY RESULT IN MISINTERPRETATION.

I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION OR CONTRACT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

JEREMY D. FOSS
DATE: _____
LIC. NO.: 59871

THIS DOCUMENT IS THE PROPERTY OF I & S GROUP, INC. AND MAY NOT BE REPRODUCED, COPIED OR DUPLICATED WITHOUT PRIOR WRITTEN CONSENT.

LENNAR RESERVE AT AUTUMN WOODS


CHASKA, MINNESOTA

REVISION	DATE	BY	DESCRIPTION
1	2/24/22	JDF	CITY COMMENTS
2	3/17/22	JDF	CITY & WATERBED COMMENTS

PROJECT NO.	21-24984
FILE NAME	24984 TREE PRES
DRAWN BY	JDF
DESIGNED BY	JDF
ORIGINAL ISSUE DATE	11/03/21
CLIENT PROJECT NO.	

TREE PRESERVATION A

SHEET **71** OF 71





NOTE: THE CLARITY OF THESE PLANS DEPENDS ON THE ACCURACY OF THE SURVEY DATA. THESE PLANS DO NOT APPEAR IN COLOR. THIS IS NOT AN ORIGINAL PLAN SET AND MAY RESULT IN MISINTERPRETATION.

I HEREBY CERTIFY THAT THE PLAN, SPECIFICATION OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.
JEREMY D. FOSS

DATE: _____ LIC. NO.: 59271
THIS DOCUMENT IS THE PROPERTY OF I & S GROUP, INC. AND MAY NOT BE USED, COPIED OR DUPLICATED WITHOUT PRIOR WRITTEN CONSENT.

LENNAR RESERVE AT AUTUMN WOODS


CHASKA MINNESOTA

REVISION SCHEDULE	
NO.	DESCRIPTION
1	CITY COMMENTS
2	CITY COMMENTS
3	CITY & WATERBOD COMMENTS
4	TRK

PROJECT NO: 21-24894
 FILE NAME: 24894 TREE PRES
 DRAWN BY: JRS
 DESIGNED BY: JRS
 REVIEWED BY: JDF
 ORIGINAL ISSUE DATE: 11/02/22
 CLIENT PROJECT NO: _____

TITLE: **TREE PRESERVATION B**

SHEET: **72** OF 77





NOTE: THE CLARITY OF THESE PLANS DEPENDS ON THE CLARITY OF THE ORIGINAL PLAN SET AND MAY RESULT IN MISINTERPRETATION.

I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

JEREMY D. FOSS
DATE: _____ LIC. NO.: 59871

THIS DOCUMENT IS THE PROPERTY OF I & S GROUP, INC. AND MAY NOT BE REPRODUCED, COPIED OR DULICATED WITHOUT PRIOR WRITTEN CONSENT.

LENNAR RESERVE AT AUTUMN WOODS


CHASKA MINNESOTA

REVISION	DATE	BY
1	10/22/22	JDF
2	10/22/22	JDF
3	10/22/22	JDF
4	10/22/22	JDF
5	10/22/22	JDF
6	10/22/22	JDF
7	10/22/22	JDF
8	10/22/22	JDF
9	10/22/22	JDF
10	10/22/22	JDF
11	10/22/22	JDF
12	10/22/22	JDF
13	10/22/22	JDF
14	10/22/22	JDF
15	10/22/22	JDF
16	10/22/22	JDF
17	10/22/22	JDF
18	10/22/22	JDF
19	10/22/22	JDF
20	10/22/22	JDF
21	10/22/22	JDF
22	10/22/22	JDF
23	10/22/22	JDF
24	10/22/22	JDF
25	10/22/22	JDF
26	10/22/22	JDF
27	10/22/22	JDF
28	10/22/22	JDF
29	10/22/22	JDF
30	10/22/22	JDF
31	10/22/22	JDF
32	10/22/22	JDF
33	10/22/22	JDF
34	10/22/22	JDF
35	10/22/22	JDF
36	10/22/22	JDF
37	10/22/22	JDF
38	10/22/22	JDF
39	10/22/22	JDF
40	10/22/22	JDF
41	10/22/22	JDF
42	10/22/22	JDF
43	10/22/22	JDF
44	10/22/22	JDF
45	10/22/22	JDF
46	10/22/22	JDF
47	10/22/22	JDF
48	10/22/22	JDF
49	10/22/22	JDF
50	10/22/22	JDF
51	10/22/22	JDF
52	10/22/22	JDF
53	10/22/22	JDF
54	10/22/22	JDF
55	10/22/22	JDF
56	10/22/22	JDF
57	10/22/22	JDF
58	10/22/22	JDF
59	10/22/22	JDF
60	10/22/22	JDF
61	10/22/22	JDF
62	10/22/22	JDF
63	10/22/22	JDF
64	10/22/22	JDF
65	10/22/22	JDF
66	10/22/22	JDF
67	10/22/22	JDF
68	10/22/22	JDF
69	10/22/22	JDF
70	10/22/22	JDF
71	10/22/22	JDF
72	10/22/22	JDF
73	10/22/22	JDF
74	10/22/22	JDF
75	10/22/22	JDF
76	10/22/22	JDF
77	10/22/22	JDF
78	10/22/22	JDF
79	10/22/22	JDF
80	10/22/22	JDF
81	10/22/22	JDF
82	10/22/22	JDF
83	10/22/22	JDF
84	10/22/22	JDF
85	10/22/22	JDF
86	10/22/22	JDF
87	10/22/22	JDF
88	10/22/22	JDF
89	10/22/22	JDF
90	10/22/22	JDF
91	10/22/22	JDF
92	10/22/22	JDF
93	10/22/22	JDF
94	10/22/22	JDF
95	10/22/22	JDF
96	10/22/22	JDF
97	10/22/22	JDF
98	10/22/22	JDF
99	10/22/22	JDF
100	10/22/22	JDF

PROJECT NO.	21-24884
FILE NAME	24884 TREE IRES
DRAWN BY	JDF
DESIGNED BY	JDF
REVIEWED BY	JDF
ORIGINAL ISSUE DATE	10/02/22
CLIENT PROJECT NO.	

TREE PRESERVATION C

SHEET **73** OF 77





NOTE: THE CLARITY OF THESE PLANS DEPENDS ON THE CLARITY OF THE ORIGINAL PLAN SET AND MAY RESULT IN MISINTERPRETATION.

I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

JEREMY D. FOSS
DATE: _____
LIC. NO.: 59871

LENNAR RESERVE AT AUTUMN WOODS

CHASKA, MINNESOTA

REVISION	DATE	BY	DESCRIPTION
1	2/14/22	JRS	CITY COMMENTS
2	3/17/22	JRS	CITY & WATERBOD COMMENTS
3		JRS	TRK

PROJECT NO: 21-24894
 FILE NAME: 24894 TREE PRES
 DRAWN BY: JRS
 DESIGNED BY: JRS
 ORIGINAL ISSUE DATE: 01/02/22
 CLIENT PROJECT NO: _____

TITLE: **TREE PRESERVATION D**

SHEET: **74** OF 77

